

Rate Design Investigation Appendix C

Stakeholder Presentations



March 18, 2025

ComEd Allocation of costs to Delivery Service and Supply

John Leick
ComEd Senior Manager, Retail Rates

Background and Discussion Today

Background

- ComEd received a Final Order from the Illinois Commerce Commission ("Commission") on January 16, 2025, in its Rate Design Investigation filing (ICC Docket No. 24-0378).
- As a part of the Final Order, the Commission included several directives requiring further actions related to issues that were raised by intervenors in the docket.
- One of those issues is the allocation of costs to Supply and Delivery Service.
- Specifically, the Commission directed Staff to conduct an investigation into the appropriate allocation between Supply and Delivery Service costs and to engage with ComEd and interested stakeholders on the appropriate allocation method. Staff must file a report with the Commission discussing its findings and providing recommended revisions or actions no later than one year of the date of the final Order (i.e., by January 2026). Final Order at 35.

For Discussion Today

- Review historical proceedings that addressed the allocation of costs to Supply and touch on key stakeholder positions and Commission Orders that support the method used today to allocate costs.
- Walk through the current methodology and process used by ComEd to allocate costs to Supply.
- Review tariff and statute related to cost recovery for Supply and Delivery Service.

Historical Proceedings Addressing Allocation of Costs to Supply and Delivery Service

Historical Proceedings Addressing Allocation of Costs to Delivery Service and Supply – ICC Docket No. 07-0566

2007 Docket No. 07-0566 (General Increase in Electric Rates)

REACT Position

- REACT proposed shifting more than \$64.8 million (40%) of Customer costs from ComEd's delivery service rates to ComEd's supply rates, arguing the costs were supply-related Customer costs improperly included in delivery service rates. *Final Order at 183.*
- "Costs incurred by ComEd to procure energy should be recovered from those customers who have caused the cost to be incurred." *REACT Ex. 3.0 at 6.*
- Costs were functionalized for the categories "Billing – Computation & Data Management," "Bill Issue & Processing," and "Customer Information" (excluding meter reading). *REACT Ex. 7.0 at 18; REACT Ex. 7.1.*
- ComEd's delivery service rates are improperly inflated because its supply administration costs are artificially low thus, providing ComEd with a competitive pricing advantage over RES. *REACT Ex 7.0 at 3.*

COMED Position

- ComEd stated that REACT's proposal to carve out \$64.9 million of so-called Customer Care costs from ComEd's delivery service rates and reallocate these costs to ComEd's supply rates is improper and unsupported. *Final Order at 169.*
- ComEd stated that REACT's proposal was in direct conflict with Commission decisions in its procurement plan and related supply tariffs. *Final Order at 170.*
- ComEd argued that since REACT is making a strong case for assigning costs to the cost-causer, it could also make similar arguments in assigning costs it incurs to make competitive choice possible for customers that choose to take their supply from a RES. *ComEd Ex. 30 at 59.*
- ComEd stated that all Customer Care Costs should be assignable to all distribution customers and REACT failed to prove that any Customer Costs would be avoided if all customers served under Rate BES migrate to alternative suppliers. *Final Order at 171.*

STAFF Position

- Staff acknowledged that some portion of Customer Care Costs might properly be allocated to supply function because it appeared intuitive that ComEd's role as supplier of energy in addition to providing delivery function would have some impact on the level of these costs. *Final Order at 189.*

COMMISSION Final Order

- The Commission was of the view that some percentage of Customer Care Costs may well be attributable specifically to bundled supply customers and mentioned that it was reasonable to investigate the allocation of Customer Care Costs. *Final Order at 208.*

Historical Proceedings Addressing Allocation of Costs to Delivery Service and Supply – ICC Docket 08-0532

2008 Docket No. 08-0532 (Rate Design Investigation)

The Commission initiated an RDI on September 10, 2008. In its initiating order, the Commission, among other directives, ordered ComEd to analyze the cost of providing Customer Care to customers with alternative suppliers versus those with ComEd. *Initiating Order at 2.*

COMED Position

- ComEd undertook a study to analyze the costs it incurs in providing services and determined if these costs were sensitive to customers switching to a RES from ComEd. *ComEd Ex. 2.0 at 4.84-86.*
 - In this study, ComEd identified ~\$138 million in 2006 O&M costs for analysis, excluding costs related to Metering Services, Large Customer Services, Demand Management and Advertising, leaving ~\$92 million for further review. These cost categories were excluded as they were indisputably related to delivery service. *ComEd Ex. 2.1.*
 - ComEd assessed the impact of customer switching to RES supply service on these costs, finding no reduction at current switching levels and additional costs for higher switching volumes (i.e., at 1%, 10% and 100%). *Final Order at 56.*

REACT Position

- Using an embedded cost of service approach, REACT proposed an \$88 million shift in distribution costs from delivery function to the supply function. *Final Order at 67.*
 - Rather than restrict the analysis only to O&M direct costs as ComEd did, REACT included the costs associated with the full revenue requirement, and allocated the identified Customer Care Costs equally between the delivery and supply functions, splitting them 50/50. *Final Order at 67-68.*

COMMISSION Final Order

- Commission directed ComEd to file an embedded cost of service study for these costs and to also include the results of its avoided cost study (Switching Study). *Final Order at 69.*

comEd

Prepared for Workshop Discussion Purposes Only

Commonwealth Edison Company					
Customer Services Study Results					
For the Year Ending December 31, 2006					
Line No.	Department / Activity	Costs Analyzed	Decreased (Increased) Costs at 1% Switching	Decreased (Increased) Costs at 10% Switching	Decreased (Increased) Costs at 100% Switching
	(a)	(b)	(c)	(d)	(e)
1	Metering Services (1)	\$ 14,018,844	-	-	-
2	Large Customer Services (1)	7,384,138	-	-	-
3	Demand Management (1)	4,301,814	-	-	-
4	Advertising (1)	612,800	-	-	-
5	Subtotal	\$ 46,317,684	-	-	-
6	Billing	16,762,238	-	-	-
7	Payments Processing	2,761,878	-	-	-
8	Revenue Management	6,282,990	-	-	-
9	Field and Meter Services	5,446,982	-	-	-
10	Customer Contact Center	22,715,326	-	48,650	486,502
11	Electric Supplier Services	914,272	-	(102,355)	(244,278)
12	Market Research	1,325,621	-	-	-
13	Information Technology	13,798,026	-	501	(2,164,898)
14	Support Services	17,240,947	-	-	-
15	Other (2)	2,755,244	-	-	-
Total Analyzed		\$ 91,862,996	\$ -	\$ (55,004)	\$ (2,030,764)
Amounts Not Analyzed (3)		\$ 601,880	-	-	-
Grand Total of Study		\$ 138,585,430	\$ -	\$ (55,004)	\$ (2,030,764)

Historical Proceedings Addressing Allocation of Costs to Delivery Service and Supply – ICC Docket 10-0467

2010 Docket No. 10-0467 (General Increase in Electric Rates)

COMED Position

- ComEd performed two studies to allocate customer service (otherwise referred to as customer care) costs between distribution and supply functions, the "Switching Study" and the "Allocation Study." ComEd Ex. 19.0 at 5; ComEd Ex. 19.1; ComEd Ex. 19.2.
 - The Switching Study, analyzes the costs ComEd incurs in providing customer services to determine if these costs are sensitive to customers switching to a retail electric supplier ("RES") from ComEd. The second, entitled the Allocation Study, examines the costs ComEd incurs in providing customer services and allocates these costs between delivery and supply.
 - ComEd identified the costs to be reviewed for purposes of the customer service studies as the 2009 direct O&M costs submitted in ComEd's June 30, 2010 (initial) rate case filing.

REACT Position

REACT, however, proposed use of the Allocation Study when allocating these costs, arguing that the Switching Study relies on speculative customer switching scenarios that do not accurately reflect cost causation. Final Order at 209.

STAFF Position

- Staff argued that the Switching Study presented a more reasonable approach than the Allocation Study. Final Order at 205.

COMMISSION Final Order

- The Commission concluded that ComEd analyzed the correct pool of costs in the "Switching Study," with some exceptions regarding "Direct O&M Costs vs. Total Costs."Final Order at 210.
- The Commission also acknowledged the need for a traditional embedded cost study but noted that many customer care costs will be incurred by ComEd regardless of the supplier. Final Order at 210.
- The Commission did not adopt the Allocation Study. Final Order at 213. The Commission therefore rejects REACT's proposed adjustments to the Allocation Study.

Historical Proceedings Addressing Allocation of Costs to Delivery Service and Supply – ICC Docket 10-0467

Switching Study (Avoided Cost Study) included in Docket 10-0467

- The Switching Study determines the share of customer care costs that are supply-related, by assessing whether they are sensitive to the number of customers switching to supply service provided by RES.
- The Switching Study, examined the effect of three customer switching scenarios, in which, 1%, 10% and 100% of customers choose a RES.
- Based on its study, ComEd realized no cost savings when its supply customers switch to a RES. *ComEd Ex. 19.0 Rev at 1-2; 19.1.*
- ComEd argued that it must incur delivery service costs for all customers, regardless of their electricity supplier, and shifting these costs to supply understates the true delivery service costs. For instance, metering costs are entirely delivery service costs, not supply costs. *Final Order at 207.*
- ComEd also stated that the Switching Study aligns with past Commission treatment of customer service costs as delivery costs, and deviating from this approach would set a negative precedent for Illinois utilities. *Final Order at 208.*
- Staff defended the Switching Study, stating it accurately reflected switching levels and shows that customer care costs will rise even with increase switching. *Final Order at 206.*

Commonwealth Edison Company					
Switching Study Results					
For the Year Ending December 31, 2009					
Line No.	Department / Activity	Costs Analyzed	Decreased (Increased) Costs at 1% Switching	Decreased (Increased) Costs at 10% Switching	Decreased (Increased) Costs at 100% Switching
		70	90	90	90
1	Metering Services (1)	48,049,417	-	-	-
2	Advertising (1)	2,339,560	-	-	-
3	Subtotal	\$ 50,388,977	-	-	-
4	Field and Meter Services	6,326,077	-	-	-
5	Billing	22,155,768	-	854	8,576
6	Customer Contact Center	25,855,365	-	53,100	531,002
7	Large Customer Solutions	8,091,400	-	-	-
8	Revenue Management	10,258,810	-	-	-
9	Revenue Protection	947,000	-	-	-
10	Demand Management	4,741,082	-	(59,400)	(193,050)
11	Electric Supplier Services	287,000	-	-	-
12	Market Research	1,707,886	-	-	-
13	Information Technology	29,074,802	-	(90,950)	(2,660,500)
14	Support Services	5,900,359	-	-	-
15	Other (2)	10,023,008	-	-	-
Total Analyzed		\$125,256,298	\$ -	\$ (56,392)	\$ (2,318,970)
Amounts Not Analyzed (3)		\$ 596,095	-	-	-
Grand Total of Study		\$176,231,385	\$ -	\$ (56,392)	\$ (2,318,970)

Historical Proceedings Addressing Allocation of Costs to Delivery Service and Supply – ICC Docket 10-0467

Allocation Study (Embedded Cost Study)
included in Docket 10-0467

- Allocation Study uses the embedded cost approach to allocate customer care costs between the supply and distribution functions.
- Using the allocation methodologies in the study, it found that 82% of ComEd's customer services cost should be allocated to delivery services. *ComEd Exs. 19.0 at 8; 19.02.*
- ComEd argued that the Allocation Study is based more on assumptions that are unrelated to ComEd's actual customer service operations. *ComEd Ex. 19.0 at 8.*
- Staff argued that this approach shifts significant customer care costs to the supply function, potentially allowing unbundled service customers to bypass some costs and will also result in a subsidy for customers under a RES, distorting prices and creating inefficiencies. *Final Order at 206.*

Commonwealth Edison Company Allocation Study Results				
For the Year Ending December 31, 2009				
Line No.	Department / Activity (a)	Costs Analyzed (b)	Costs Allocated to Supply (c)	Costs Allocated to Delivery (d)
1	Metering Services (1)	48,049,417	-	48,049,417
2	Advertising (1)	2,338,560	-	2,338,560
3	Subtotal	\$ 50,388,977	\$ -	\$ 50,388,977
4	Field and Meter Services	6,326,077	1,648,151	4,677,925
5	Billing	22,155,768	4,222,179	17,933,589
6	Customer Contact Center	25,655,365	6,682,330	18,973,034
7	Large Customer Solutions	8,091,400	52,730	8,038,670
8	Revenue Management	10,208,810	5,524,186	4,684,624
9	Revenue Protection	847,053	26,343	821,010
10	Demand Management	4,741,082	1,067,901	3,673,181
11	Electric Supplier Services	297,000	-	297,000
12	Market Research	1,707,696	25,615	1,682,071
13	Information Technology	29,074,692	6,374,565	22,700,127
14	Support Services	5,900,359	1,003,169	4,897,190
15	Other (2)	10,051,008	4,458,780	5,592,227
Total Analyzed		\$ 125,256,298	\$ 31,085,680	\$ 94,170,618
Subtotal of Departments		\$ 175,645,275	\$ 31,085,680	\$ 144,559,595
Amounts Not Analyzed (3)		\$ 586,090	\$ 103,726	\$ 482,364
Grand Total of Study		\$ 176,231,365	\$ 31,189,406	\$ 145,041,959

Historical Proceedings Addressing Allocation of Costs to Delivery Service
and Supply – ICC Dockets 13-0387 and 14-0312

2013 Docket No. 13-0387
Rate Design Investigation

- **REACT** In the 2013 RDI, Witness Merola argued that ComEd's Customer Care Costs should be allocated based on the function that incurs these costs. Specifically, Customer Care Costs associated with ComEd Supply service should be recovered from ComEd supply rate and not ComEd's delivery service rates. *REACT Ex. 3.0 at 16.*
- **COMED** argued that REACT's proposal to reallocate ComEd's Customer Care Costs was improper and would reduce ComEd's Commission approved delivery service revenue requirement, which is not revenue requirement neutral and thus, outside the scope of an RDI proceeding. *Final Order at 62.*
- **STAFF** asserted that the Commission reject REACT's recommendations. *Final Order at 52.*
- **COMMISSION** directed ComEd to provide an updated Customer Cost Allocation Study in its next formula rate update filing. *Final Order at 57.*

2014 Docket No. 14-0312
Formula Rate Update

- **COMED** presented three approaches in evaluating its customer care costs using 2013 actual costs; Switching Study, Allocation Study, and Alternative Study. *Final Order at 92.*
- ComEd engaged B&V to review its Switching study and Allocation Study and provide an analysis, with results presented by Mr. Feingold who also addressed the Alternative Study. *ComEd Ex. 7.0 at 39.*
- ComEd claimed the Switching Study is the most accurate method for apportioning customer care costs and aligns with other Illinois utilities and also noted that most jurisdictions with retail competition allow utilities to recover customer care costs through delivery charges. *Final Order at 93; ComEd Ex. 7.0 at 64.*
- **RESA** proposed a modified Allocation Study, which allocates approximately \$52 million to ComEd's default supply rate. *Final Order at 97.*
- **STAFF** argued that the Switching Study was a more accurate approach because it shows how customer care costs did not decline significantly despite fewer customers staying with ComEd supply. *Final Order at 99.*
- Staff did not support using the Allocation Study to segment customer care costs between delivery and supply functions, but stated that if the Commission adopted this approach, Staff recommended ComEd's Alternative Study. *Final Order at 101.*
- **COMMISSION** adopted ComEd's Alternative Study, allocating approximately \$11 million to the supply function. *Final Order at 104.*

Historical Proceedings Addressing Allocation of Costs to Delivery Service and Supply – ICC Docket 14-0312

Switching Study (Avoided Cost Study) included in Docket 14-0312

- The Switching Study determines the share of customer care costs that are supply-related, by assessing whether they are sensitive to the number of customers switching to supply service provided by RES.
- The Switching Study, cost impacts at 64%, 69% and 100% customer switching levels, showing how costs change with varying levels of switching. *Final Order at 93; ComEd Ex. 7.0 at 39.*
- Based on its study, ComEd realized its customer costs do not with customer switching to RES-provided supply services. *Final Order at 93; ComEd Ex. 2.0 at 40.*
- RESA claimed the Switching Study was based on the flawed premise that customer care costs should decrease as customers switch from Rate BES supply service. *Final Order at 95.*
- Staff asserted that ComEd’s treatment of customer care costs is similar to other Illinois utilities in the United States, and changing this approach could set an undesirable precedent. *Final Order at 100.*

Commonwealth Edison Company				
Switching Study Results				
For the Year Ending December 31, 2013				
Line No.	Department / Activity	Costs at 69% Switching	Decreased (Increased) Costs at 64% Switching	Decreased (Increased) Costs at 100% Switching
	(B)	(C)	(D)	(E)
1	Metering Services (1)	61,732,262	-	-
2	Advertising (1)	-	-	-
3	Subtotal	\$ 61,732,262	-	-
4	Field and Meter Services	12,096,540	-	-
5	Billing	7,256,221	-	-
6	Customer Contact Center	37,987,643	-	132,797
7	Customer Relations (4)	1,363,461	-	-
8	Large Customer Solutions	9,054,583	-	-
9	Revenue Management	20,007,076	-	-
10	Revenue Protection	2,291,422	-	-
11	Debtand Management	4,510,803	-	-
12	Electric Supplier Services (3)	-	-	-
13	Market Research	-	-	-
14	Information Technology	27,971,048	112,343	(696,525)
15	Support Services	8,318,780	-	-
16	Other (2)	2,686,688	-	-
Total Analyzed		\$ 141,855,375	\$ 112,343	\$ (563,729)
Grand Total of Study		<u>\$ 203,407,637</u>	<u>\$ 112,343</u>	<u>\$ (563,729)</u>

Historical Proceedings Addressing Allocation of Costs to Delivery Service and Supply – ICC Docket 14-0312

- Alternative Study (Commission Approved)
Included in Docket 14-0312
- This study considers the results of the Switching Study by identifying and allocating costs associated with business activities that are sensitive to changes in customer switching.
 - ComEd's Alternative Study would allocate approximately \$11 million of ComEd's call center costs to supply function whilst RESA's modified Alternative Study would allocate approximately \$34 million of ComEd's call center costs to the supply function. *Final Order at 102 – 103.*
 - Staff stated that this method minimizes the impact of unbundling costs and recognizes the common aspect of customer service activities. *Final Order at 101 – 102.*
 - All parties agreed the Alternative Study was acceptable if the Switching Study was rejected. *Final Order at 104.*
 - The Commission found ComEd's Alternative Study a suitable starting point for allocating care costs to the default supply function, noting that call center expenses decrease as customers switch to RESs. *Final Order at 103 – 104.*

Commonwealth Edison Company				
Alternate Analysis				
Costs for the Year Ending December 31, 2013				
Line No.	Department / Activity	Total Costs (O&M and Indirects) Analyzed	Total Costs Allocated to Supply	Total Costs Allocated to Delivery
1	Customer Contact Center	86,119,784	10,927,146	77,192,638
Grand Total of Study		\$ 86,119,784	\$ 10,927,146	\$ 77,192,638

Current Methodology for Allocation to Supply and Delivery Service

ComEd's Current Methodology - Allocation of Costs to Delivery Service and Supply

- ComEd follows the Commission ordered Alternative Study methodology from Docket 14-0312
- The Alternative Study used the Switching Study to identify whether any costs changed with changes in switching level, and if they did, used the Allocation Study to quantify the amount of that cost for the delivery and supply functions
- ComEd updates its Customer Care Supply Allocation Study annually to assign a portion of the customer care costs to the supply function and recover that portion through ComEd's supply rates. The study results are included as an exhibit in ComEd's delivery service reconciliation filings (*ComEd Ex. 4.03, ICC Docket 24-0304*)
- The next updated study will be included in ComEd's 2024 Reconciliation and Performance Metrics Evaluation filing in May 2025

Mechanics and inputs for the annual Customer Care Supply Allocation Study updates:
(using data from the Customer Care Study from ICC Docket 24-0304 reconciling 2023 actuals in examples)

- 1) Compile current Customer Contact Center direct costs for an annual period
- Customer contact center costs recorded in FERC Account 903 – Customer Records and Collection Expenses, which is Operations and Maintenance ("O&M") are reviewed for departments and projects related to the call center activities. The costs are differentiated by whether they are payroll or other using subaccount information from ComEd's general ledger.

Commonwealth Edison Company							
2023 Customer Contact Center Costs in Account 903 - Customer Records and Collection Expenses							
Dept ID	Dept - Descr	Proj - ID	Proj - Descr	Account Type	Customer Contact Center Costs	Customer Contact Center Payroll Costs	Customer Contact Center Other Costs
486	Residential Implementation	13CSSS03	Business Transformation & Tech	Other	\$150	\$0	\$150
1451	Oak Brook Call Center	TCCUST	Customer Service Training G&A	Payroll	\$129,737	\$129,737	\$0
1461	Customer Relations West	CSSB02	Investigate Billing Exceptions	Payroll	\$72,845	\$72,845	\$0
1461	Customer Relations West	CSSS01	Respond to Customer Complaints	Payroll	\$1,068,821	\$1,068,821	\$0
1474	LCS-Suburban	CSCC02	Call Center Employee Costs	Payroll	\$159	\$159	\$0
1497	Project Planning ComEd	13CSSS03	Business Transformation & Tech	Other	\$14,337	\$0	\$14,337

comEd

Prepared for Workshop Discussion Purposes Only

ComEd's Current Methodology - Allocation of Costs to Delivery Service and Supply

- 2) Compile Call Center Activity and Allocators
- Calls handled by ComEd personnel in the Customer Contact Center during the same annual period are reviewed
 - The calls are identified by: (a) a "Group" which are related to Billing, Care Programs, outages, moving, needing correspondence, or other activities, (b) the Group is further segmented into a "Category" which are related to balance, budget, credit, payment options, transfer, turn on, turn off, and other categories, and (c) a "Description" of the call.

Commonwealth Edison Company 2023 Call Center Activity				
Group	Category	Description	Handled Transactions	Designation
Billing	Balance	Activity Statement Agent	965	Bill Allocator
Billing	Balance	Activity Statement Fail Out	608	Bill Allocator
Billing	Balance	Balance Info Agent	36,625	Bill Allocator
Correspondence	Correspondence	OSR Activity Statement	7,962	Not Used for Allocation
Correspondence	Correspondence	Landlord agreement	43,822	Bill Allocator
Correspondence	Correspondence	Misc correspondence	39,172	Not Used for Allocation
Correspondence	Correspondence	Heat disclosure	32,651	Not Used for Allocation
Correspondence	Correspondence	Account maintenance	7,776	Revenue Allocation
Correspondence	Correspondence	Streetlight Outage ComEd	9,236	Distribution

ComEd's Current Methodology - Allocation of Costs to Delivery Service and Supply

3) Develop allocation to Supply and Delivery Services

- Each combination explains the nature of the call and is assigned one of the four following allocator designations:

(1) Revenue Allocator – Calls related to Payment Plans, Service Disconnection, Actual Payments, ComEd Care Program, Application Verification, W9 forms, or Electronic Fund Transfers ("EFT"). In 2023, there were 1,674,931 calls with a Revenue Allocator Designation. These calls were allocated to delivery and supply based on the Revenue Allocator.

The Revenue allocator is computed by taking the distribution, i.e., delivery, and supply revenues to compute the percentage related to delivery and supply. The revenue data is from ComEd's Annual ICC Form 21 Filing. In addition, the delivery revenue also includes the PORCB receivables, which are the receivables from ComEd providing billing of supply services for Retail Electric Suppliers ("RESs"). For 2023 the Revenue Allocator is 72.29% to delivery and 27.71% to supply.

Commonwealth Edison Company			
2023 Base Revenues Used to Calculate Revenue Allocator			
Retail Customer Designation	Distribution		Supply
	Base Rate Revenue		Base Rate Revenue
R: Residential	\$	2,287,700,299	\$ 1,574,575,483
N: Nonresidential ⁽¹⁾	\$	2,355,514,351	\$ 567,782,481
A: All Other ⁽²⁾	\$	\$2,429,571	\$ 5,161,063
PORCB Receivables	\$	907,892,471	
Total	\$	5,603,536,692	\$ 2,147,519,007
2023 Revenue Allocator		72.29%	27.71%
(1) Commercial & Industrial Sales (Retail or Commercial, Large or Industrial)			
(2) Public Street & Highway Lighting, Other Sales to Public Authorities, Sales to Railroads & Railways			

(2) Distribution Allocator - Calls related to Moving, Outages, Meter Reading, Vegetation Management (trees), Wiring Issues, Street Lights, Duplicate Documentation, or ComEd Sponsored Programs. In 2023, there were 1,069,911 calls with a Distribution Designation. These calls were allocated 100% to delivery.

(3) Not Used for Allocation - Calls that are not assigned to the Bill, Revenue, or Distribution allocator, such as unidentified calls or web correspondence do not impact the calculation of the Call Center Allocator. In 2023, there were 229,525 calls with a Not Used for Allocation designation. These calls were not allocated or included in the total used in the analysis, so they do not impact the resulting Call Center Allocator.

ComEd's Current Methodology - Allocation of Costs to Delivery Service and Supply

(4) **Bill Allocator** – Calls (referred as "Transactions" in the exhibit) related to a Balance Inquiry, Budget Billing, Payment, Voice Response Unit ("VRU") or Summary Billing. As an example, there were 965 handled transactions identified as "Activity Statement Agent" which would be related to viewing the related bill line items and are assigned to Bill Allocator. In 2023, there were 365,352 calls with a Bill Allocator designation. These calls were allocated to delivery and supply based on the Bill Allocator.

The Bill Allocator is computed by counting the number of line items on residential and non-residential bills for different delivery classes and determining an average number of lines for residential and non-residential, ComEd and RES supplied, and for supply, delivery, and taxes and others sections of the bills. This measures the amount of space the bill uses for the delivery and supply functions. For 2023 the Bill Allocator is 75.76% to delivery and 24.64% to supply

A. Number of Lines on Bills						B. Average Number of Lines on Bills					
Customer Type	Supply	Description	Supply Lines	Delivery Lines	Tax Lines	Customer Type	Supply	Avg Supply Lines	Avg Delivery Lines	Avg Tax Lines	% Delivery
Nonresidential	ComEd	Ready (100 - 1000)	5	4	6	Nonresidential	ComEd	3.47	4.10	6.43	75%
Nonresidential	ComEd	Demanded (100 - 400)	5	5	5	Residential	ComEd	3.97	4.90	5.93	75%
Nonresidential	ComEd	Demanded (1 - 100)	5	4	5	Nonresidential	RES	2.50	4.00	5.00	85%
Residential	ComEd	Light	5	4	5	Residential	RES	3.00	4.00	5.00	90%
Residential	ComEd	Light	5	4	5						
Residential	ComEd	Ready (Single)	5	4	5						
Nonresidential	RES	POPCB	4	4	5						
Nonresidential	RES	Day	0	4	5						
Residential	RES	POPCB	1	4	5						
Residential	RES	Day									

Section C: 2023 Number of Bills by Supplier, Residential/Nonresidential, and Type of Bill

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual Total	Weighted % Delivery	% Weighted % Delivery
ComEd Supply															
Nonresidential	395,542	397,087	398,062	396,570	398,857	397,578	396,031	396,283	254,405	252,849	252,098	231,840	4,153,742	7.4%	8%
Residential	3,470,709	3,484,498	3,478,102	3,460,874	3,466,202	3,461,239	3,453,486	3,452,172	3,452,542	3,442,812	3,444,802	3,454,038	41,124,468	74.0%	94%
Grand Totals Supplier (ComEd)															
Nonresidential															
DUAL	40,890	40,837	40,831	39,802	39,812	41,684	39,891	39,143	38,873	38,862	38,711	36,239	477,585	0.9%	1%
POPCB	56,512	56,690	56,104	55,702	55,200	60,451	62,704	64,681	64,103	63,838	64,800	67,115	861,697	1.4%	1%
Day	39,208	39,001	38,898	38,808	38,744	38,436	38,802	38,629	38,571	38,399	38,630	445,333	0.8%	1%	
Residential															
DUAL	11	12	12	12	12	20	20	16	16	24	15	20	1,489	0.0%	0%
POPCB	644,847	647,144	676,984	680,066	683,564	749,951	712,251	717,946	715,789	725,239	742,146	748,421	8,414,793	15.1%	14%
Day	10	10	10	10	10	10	10	10	10	10	10	10	110	0.0%	0%
Totals	4,307,741	4,315,779	4,307,828	4,297,698	4,295,873	4,314,579	4,258,879	4,258,814	2,546,592	2,538,967	2,538,932	2,400,611	55,571,114	100.0%	100%

Prepared for Workshop Discussion Purposes Only

ComEd's Current Methodology - Allocation of Costs to Delivery Service and Supply

4) Compute the Call Center Allocator

The Call Center Allocator used to allocate Customer Contact Center Costs to Delivery and Supply is computed from the number of calls in each designation and the allocation percentage for Delivery and Supply

2023 Call Center Allocator			
Allocator	Number of Calls	% Delivery	% Supply
Revenue Allocator	1,674,931	72.29%	27.71%
Bill Allocator	365,352	75.76%	24.24%
Distribution	1,069,911	100.00%	0.00%
Call Center Allocator	3,110,193	82.23%	17.77%

5) Apply the Call Center Allocator

The Call Center Allocator percentage is applied to the Customer Contact Center payroll and other costs to determine the amount allocated to Supply

2023 Customer Contact Center Direct Costs to Delivery and Supply			
Account Type	Direct Cost	Direct Cost to Delivery	Direct Cost to Supply
	(a)	(b) = (a) x 82.23%	(c) = (a) x 17.77%
Payroll	\$51,909,110	\$42,685,595	\$9,223,516
Other	\$4,474,940	\$3,679,806	\$795,134
Total	\$56,384,050	\$46,365,401	\$10,018,649

ComEd's Current Methodology - Allocation of Costs to Delivery Service and Supply

Mechanics of the annual Customer Care Supply Allocation Study updates (continued):

6) Indirect cost factors are then applied to the direct Customer Contact Center costs that will be allocated to Supply

Types of Indirect Cost Factors Applied	Description of indirect costs	Applied To	Rate for 2023
Benefits	Average Rate for pensions, health care, incentives and payroll taxes	Payroll	59.48%
Affiliated Interest Agreement ("AIA") Non-Common Back Office Rate	Indirect labor costs related to office facilities, human resources function, payroll department and computer equipment and software	Payroll	49.49%
Affiliated Interest Agreement Common Back Office Rate	Indirect labor costs related to accounting, legal, procurement, forms and other administrative and general expenses	Payroll and Other	9.12%

7) The indirect costs calculated are added to the direct costs to get the total costs allocated to Supply for the Customer Contact Center and Billing Costs

The Direct and Indirect Customer Contact Center Costs and Allocation to Delivery and Supply for 2023									
The Indirect Customer Contact Center Costs									
Account Type	Direct Cost ⁽¹⁾	Benefits Factor	Benefits (c) = (a) x (b)	AIA Noncommon Factor	AIA Noncommon (e) = (a) x (d)	AIA Common Factor	AIA Common (g) = (b) + (e) x (f)	Indirect Cost	
	(a)	(b)	(c) = (a) x (b)	(d)	(e) = (a) x (d)	(f)	(g) = (b) + (e) x (f)	(h) = (c) + (e) + (g)	
Payroll	\$51,909,110	59.48%	\$30,875,539	49.49%	\$25,689,819	9.12%	\$5,158,761	\$61,724,118	
Other	\$4,474,040	0%	\$0	0%	\$0	9.12%	\$408,115	\$408,115	
Total	\$56,383,050		\$30,875,539		\$25,689,819		\$5,566,875	\$68,132,233	
The Direct and Indirect Customer Contact Center Costs									
Account Type	Direct Cost ⁽¹⁾	% Delivery ⁽²⁾	Direct Cost Allocated to Delivery (d) = (a) x (b)	Indirect Cost (e) = (d) x (f)	Indirect Cost Allocated to Delivery (m) = (d) x (m)	Indirect Cost Allocated to Supply (n) = (m) x (n)	Direct and Indirect Cost to Delivery (o) = (d) + (n)	Direct and Indirect Cost to Supply (p) = (e) + (n)	
	(a)	(b)	(d) = (a) x (b)	(e) = (d) x (f)	(m) = (d) x (m)	(n) = (m) x (n)	(o) = (d) + (n)	(p) = (e) + (n)	
Payroll	\$51,909,110	62.23%	\$42,685,595	\$9,223,516	\$81,724,118	\$50,756,614	\$10,967,504	\$93,442,209	\$20,191,020
Other	\$4,474,040	62.23%	\$3,679,896	\$795,134	\$408,115	\$335,598	\$772,516	\$4,015,452	\$687,659
Total	\$56,383,050		\$46,365,491	\$10,018,649	\$82,132,233	\$51,092,213	\$11,040,020	\$97,457,614	\$21,058,679

(1) From the Customer Contact Center Payroll and Other Costs identified from FERC Account #33.

(2) From the C&I Customer Allocation and Section 1.1 Distribution column of Section 1.1 of the 2023 C&I General Rate.

Prepared for Workshop Discussion Purposes Only

Historical Customer Care Center Costs Allocated to Supply and Customers Taking ComEd Supply and Alternative Supply

- The next updated study will be included in ComEd's 2024 Reconciliation and Performance Metrics Evaluation filed May 2025

Docket	Year Costs Incurred	Customer Care Center Costs Analyzed (1)	Cost allocated to Supply (1)(2)	% of Costs Allocated to Supply	% of Customers on Rate DE SIDE SHTOU	% of Customers on Rate RDS	YoY % Change for Customers on Rate RDS
24-0304	2023	\$ 118,516,283	\$ 21,058,669	18%	77.7%	22.3%	2.5%
23-0345	2022	121,008,923	26,740,383	22%	80.2%	19.8%	-3.8%
22-0302	2021	118,497,480	21,045,399	18%	76.4%	23.6%	-5.0%
21-0367	2020	112,947,481	18,033,925	16%	71.4%	28.6%	-2.3%
20-0393	2019	118,350,446	12,853,561	11%	69.1%	30.9%	-3.0%
19-0387	2018	117,501,546	11,725,449	10%	66.1%	33.9%	-0.4%
18-0808	2017	110,847,868	13,587,830	12%	65.7%	34.3%	-3.6%
17-0196	2016	103,259,011	13,932,539	13%	62.1%	37.9%	-4.4%
16-0259	2015	93,683,253	13,106,182	14%	57.7%	42.3%	-18.7%
15-0287	2014	96,215,843	12,239,148	13%	39.0%	61.0%	-7.4%
14-0312	2013	88,119,784	10,927,146	12%	31.6%	68.4%	

(1) Includes direct and indirect costs
(2) Amounts are shown in Schedules App 7 and WP 7 of ComEd's Annual Formula Rate Reconciliation filings for Delivery Services for the dockets listed

Allocation of the Customer Care Costs to Supply – Impact on Delivery Service Rates

❖ The estimated delivery rate's impact of removing the additional ~\$21M of Customer Care Costs from ComEd's ECOS is as follows:

Delivery Class	\$/Month Impact		Delivery Class	\$/Month Impact
Single Family Without Electric Space Heat	\$0.39		Large Load (Over 400 kW ≤ 1,000 kW)	\$6.88
Multi Family Without Electric Space Heat	\$0.39		Very Large Load (Over 1,000 kW ≤ 10,000 kW)	\$44.66
Single Family With Electric Space Heat	\$0.39		Extra Large Load (Over 10,000 kW)	\$107.25
Multi Family With Electric Space Heat	\$0.39		High Voltage	\$26.14
Watt-Hour	\$0.38		Railroad	\$309.07
Small Load (0 ≤ 100 kW)	\$0.48		Fixture-Included Lighting	\$0.80
Medium Load (Over 100 kW ≤ 400 kW)	\$0.89		Dusk to Dawn Lighting	\$0.42
			General Lighting	\$0.46

- ❖ The costs are customer-related and assigning the costs to a per-kWh supply adjustment does not represent how the costs are incurred.
- ❖ The costs are not the same across all delivery classes because the allocator for Account 903 also includes other weighting factors like manual billing and billing adjustments and also account management for large accounts.

Allocation of the Customer Care Costs to Supply – Impact on Supply Rates

- ❖ For comparison, the allocation of \$21M of Customer Care Costs in Supply rates is based on the number of customers in each supply rate, so Rate BES is allocated almost 98%:
 - **Rate BES**
 - Purchased Electricity Charges includes \$20,664,000.
 - The rate impact is 0.1031 €/kWh.
 - Average monthly bill impact of \$0.63 at the average residential usage of 609 kWhs.
 - **Rate BESH:**
 - Miscellaneous Procurement Components Charge includes \$336,000.
 - The rate impact is 0.0084 €/kWh.
 - Average monthly bill impact of \$0.05 at the average residential usage of 609 kWhs.
- ❖ Based on the previous computations, a residential BES customer has a monthly net impact of $\$0.63 - \$0.39 = \$0.24$ and a residential RES customers has a monthly net impact of $-\$0.39$. Average residential BESH customers have a net decrease: $\$0.05 - \$0.39 = -\$0.34$.
- ❖ Larger nonresidential customers with RES supply have monthly bill reductions from $-\$44$ to $-\$300$.
 - ❖ BESH Extra Large Load Customer $5\text{M kWh} \times \$0.0084 = \$420 - \$107 = \313

Public Utilities Act and Tariff Provisions

Tariff and Public Utility Act Language

Delivery Services:

Section 16-102 of the Public Utilities Act (PUA) describes delivery services as "those services provided by the electric utility that are necessary in order for the transmission and distribution systems to function so that retail customers located in the electric utility's service area can receive electric power and energy from suppliers other than the electric utility, and shall include, without limitation, standard metering and billing services." 220 ILCS 5/16-102 (Definitions).

Section 16-108 of PUA describes the recovery of costs of providing delivery service. 220 ILCS 5/16-108 (Recovery of Costs Associated with the Provision of Delivery and Other Services). Subsection 16-108(c) describes that: "Charges for delivery services shall be cost based, and shall allow the electric utility to recover the costs of providing delivery services through its charges to its delivery service customers that use the facilities and services associated with such costs. Such costs shall include the costs of owning, operating and maintaining transmission and distribution facilities." *Id.*

Tariff and Public Utility Act Language

Delivery Services (continued):
Rate MRPP – Multi-Year Rate Plan Pricing (Rate MRPP) recovery of delivery service costs through delivery service charges is described in the Purpose section of the tariff :
"The purpose of this tariff is to effectuate the provisions of Section 16-108.18 of the Public Utilities Act (Act) to allow the Company to recover delivery service costs through delivery service charges determined in a Multi-Year Rate Plan (MRP) approved by the Illinois Commerce Commission (ICC) and recover or refund the adjustments as described in the Determination of the Delivery Adjustment Amount and the Determination of the Total Plan Adjustment Factor sections of this tariff." ILL. C. C. No. 10, 1st Revised Sheet No. 612.

Tariff and Public Utility Act Language

Supply:
Rider PE – Purchased Electricity (Rider PE) definition of costs.
The Purpose section of Rider PE provides that the Company recovers the costs of procuring power and energy under the rider pursuant to Section 16-111.5 of the PUA. 220 ILCS 5/16-111.5 (Provisions Relating to Procurement). The costs to be recovered are described in subsection(l) of Section 16-111.5:
“The tariffs shall include a formula rate or charge designed to pass through both the costs incurred by the utility in procuring a supply of electric power and energy for the applicable customer classes with no mark-up or return on the price paid by the utility for that supply, plus any just and reasonable costs that the utility incurs in arranging and providing for the supply of electric power and energy.” 220 ILCS 16-111.5(l).
Section 1-5(13)(F) of the IPA Act
Section 1-5(13)(F) of the IPA Act states “Continue to review its policies and practices to determine how best to meet its mission of providing the lowest cost power to the greatest number of people, at any given point in time, in accordance with applicable law.” 20 ILCS 360/1-5(13)(F).

Appendix

comed

Prepared for Workshop Discussion Purposes Only



Allocation and Recovery of Supply Administration Costs

- **The following projected supply administration cost are included in the wholesale supply costs;**
 - Credit cost associated with margin posted to PJM and Qualified Institution Costs for the holding of Supplier Cash,
 - Energy Acquisition Procurement Related Costs,
 - Wages and Salary Allocation per the final Order in ICC Docket No. 15-0287,
 - Cash and Working Capital,
 - Projected expenses for the annual reconciliation proceedings of procurement costs,
 - Projected legal expenses primarily associated with procurement plan submission during the current Planning Year,
 - Procurement Monitor and IPA Costs (including IPA Consultant & IPA Admin), and
 - Customer Care and Collection Agency Fees.
- **The actual recoveries are reconciled to the actual costs monthly and any over/(under) recovery is then either charged or (credited) to customers via the purchase electricity adjustment.**
 - There is a four-month lag on the reconciling adjustments reflected in the purchase electricity adjustments.
- **The supply riders are subject to annual audit and reconciliation.**

Incorporation of Supply Administration Costs in Rates

- **The projected supply administration costs are incorporated in the cents per kWh supply charges ;**
 - The projections are based upon historical direct charges and allocations approved in the most recent rate case order.
- **The cost are accrued monthly based upon the projected costs and then periodically reconciled to the actual costs.**
 - There is a four-month lag on the reconciling adjustments reflected in the purchase electricity adjustments.
- **The supply riders are subject to annual audit and reconciliation.**
 - The supply admin costs are then presented and explained in the testimony of Energy Acquisition.



Investigation into Allocation of Supply Costs ICC Docket 24-0378

SUMMARY OF POSITIONS OF THE COALITION TO REQUEST EQUITABLE ALLOCATION OF COSTS TOGETHER (REACT)

COMPRISED OF:
CHARTER DURA-BAR, LLC (F/K/A WELLS MANUFACTURING, INC.)
CITGO PETROLEUM CORP. (F/K/A PDV MIDWEST REFINING, LLC)
MAGID GLOVE AND MANUFACTURING COMPANY
METROPOLITAN WATER RECLAMATION DISTRICT OF GREATER CHICAGO

Final Order

- ... the Commission is concerned with the potential impacts caused by misallocation between supply and delivery service costs. (Page 35)
 - Accordingly, ***the Commission directs Staff to conduct an investigation into the appropriate allocation between supply and delivery service costs and to engage with the Company and interested stakeholders on the appropriate allocation method. (Page 35)***
 - REACT proposes that the Commission reject the CCSA Study and in the interim use an Average Number of Services allocator to allocate customer care costs between supply and delivery. ComEd notes that this proposal would reallocate approximately \$61 million of customer care costs to ComEd supply customers. ***The Commission finds REACT's proposal is rejected as REACT's concerns should be addressed in the investigation directed above. (Page 41)***

REACT: Call Center Cost Allocation

Problem

- ComEd’s divides annual Customer Call Center costs between (i) Supply and (ii) Delivery
- But the cost allocation to Supply is based on arbitrary variables that do not relate to cost causation
 - *“The Commission primarily supports cost causation-based allocation” (Final Order at 83).*

Table 5 – Summary of the Allocators and Number of Calls Assigned in 2023 (See ComEd Ex 5.0 at 38:726-727)

Allocator	Number of Calls	% Delivery	% Supply
Revenue Allocator ^A	1,674,931	72.29%	27.71%
Bill Allocator ^B	365,352	75.76%	24.24%
Distribution	1,069,911	100.00%	0.00%
Call Center Allocator	3,110,193	82.23%	17.77%

^A % Supply of calls in ‘Revenue Allocator’ based on 27.7% of ComEd’s reported revenue is derived from supply. (See ComEd Ex 5.0 39: 731-738.)

^B % Supply of calls in ‘Bill Allocator’ based on 24.2% of “amount of space the bill uses for the delivery and supply functions”. (ComEd Ex 5.0 at 39:739-40:751.)

REACT: Customer Service Allocation Costs

Results

- ComEd attributes only 17% of Call Center traffic to Supply customers
- Of \$118 million in annual Call Center costs, only \$21 million is attributed to Supply customers
- But 78% of ComEd customers are taking Supply Service

Relevant Cost Allocations for \$118 million in annual Cost Center Costs

Allocator	Cost of Calls	% Delivery	% Supply
Revenue Allocator ^A	\$63,546,493	\$45,937,760	\$17,608,733
Bill Allocator ^B	\$13,861,370	\$10,501,374	\$3,359,996
Distribution	\$40,592,175	\$40,592,175	\$0
Call Center Allocator	\$118,000,000	\$97,031,400	\$20,968,600

^A % Supply of calls in "Revenue Allocator" based on **27.7% of ComEd's reported revenue is derived from supply.** (See ComEd Ex 5.0 39: 731-738.)

^B % Supply of calls in "Bill Allocator" based on 24.2% of **"amount of space the bill uses for the delivery and supply functions".** (ComEd Ex 5.0 at 39:739-40:751.)

REACT: Customer Service Allocation Costs

Solution A

- Customer Call Center costs should be based on data that should be accessible by ComEd
 - A ComEd Supply customer calling about anything but distribution should be considered a “supply” cost
 - A RES customer calling about ComEd Supply also should be considered a “supply” cost

Solution B

- Customer Call Center costs could be based on data that reflects the proportionality of ComEd’s customer load:
 - Maintain ComEd’s Allocator approach
 - Replace arbitrary Supply variables with the proportion of ComEd Supply customers

REACT: Customer Service Allocation Costs

ComEd Call Center Allocators	TOPICS OF CALLS TO COMED CALL CENTERS			ALLOCATION OUTPUTS	
	Total	Distribution + Supply	Distribution Only	CALLS	% OF CALLS
STEP 1					
Revenue Allocator		1,674,931		1,674,931	
Bill Allocator		365,352		365,352	
Distribution			1,069,911	1,069,911	
Call Center Allocator		2,040,283	1,069,911	3,110,194	
STEP 2					
Call Center Allocator	0	2,040,283	1,069,911	3,110,194	100%
Customers on Retail Supply	21.2%	432,540		432,540	13.9%
Customers in ComEd Supply	78.8%	1,607,743		1,607,743	51.7%
Distribution			1,069,911	1,069,911	34.4%

- Customer Call Center costs could be based on data that reflects the proportionality of ComEd's customer load:
 - Maintain ComEd's Call Center Allocators
 - Replace arbitrary Supply percentages with the proportion of ComEd Supply customers
- Calls assigned to "Distribution-Only" are concerned with non-Supply issues
- Calls assigned to "Revenue Allocator" or "Bill Allocator" may concern either Supply or other issues and must be split:
 - 78.8% of calls in these categories are designated "Supply" based on 78.8% of ComEd customers being served on Supply
 - 21.2% of calls in these categories are designated "Distribution" based on 21.2% of ComEd customers being served by RESS

REACT: Customer Service Allocation Costs

Broader Issue	Examples
- Costs for any Shared Services should be allocated between ComEd’s Supply and Delivery functions in a revenue-neutral manner that: - Closely mirrors actual utilization; or - Applies transparent cost allocators that track with the potential for service utilization (e.g., number of accounts, percentage of load, etc.)	- Billing services (current) - Uncollectibles (current) - Customer Call Center Costs (proposed)

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.01:

Referencing the Customer Care Cost Allocation Study or CCSA, please:

- a) Provide an updated Customer Care Cost Allocation with the most current information.
- b) Explain how often this Customer Care Cost Allocation is updated.
- c) Identify and explain any changes to the analysis since the approval in Docket 14-0312.
- d) Identify and explain any additional refinements of the current model that can be made to improve the accuracy of allocating costs.

RESPONSE:

- a) See the attachment labeled as RML 1.01_Attach 1 for the most recently updated Customer Care Cost Allocation Study that was included as ComEd Ex. 5.06 in ICC Docket No. 24-0378.
- b) The Customer Care Cost Allocation Study is updated annually. The next updated study will be included in ComEd's 2024 Performance Adjustment and Annual Adjustment filing, required to be filed no later than May 1, 2025.
- c) The same analysis and steps are followed to update the current Customer Care Cost Allocation Study that were used for the Alternative Analysis Study approved in ICC Docket No. 14-0312. Each year the costs are reviewed and allocators are updated with current data. In reviewing the Customer Care Cost Allocation Studies from prior years, it was identified that in the studies submitted in ICC Docket No. 23-0345 and ICC Docket No. 24-0304, there were costs unrelated to the Customer Care Center that were inadvertently included in addition to the actual costs for the Customer Care Center resulting in approximately \$4.6 million and \$3.7 million being removed from Delivery Service rates in ICC Docket No. 23-0345 and ICC Docket No. 24-0304, respectively, and allocated to Supply. ComEd has ensured that the Customer Care Cost Allocation Study to be submitted in the 2024 Annual Performance Evaluation proceeding will only include costs related to the Customer Care Center.
- d) ComEd has not identified a need for refinements of the current model.

Commonwealth Edison Company

The Direct and Indirect Customer Contact Center Costs and Allocation to Delivery and Supply for 2023

Section A. The Direct and Indirect Customer Contact Center Costs

Account Type	Direct Cost ⁽¹⁾	Benefits Factor ⁽²⁾	Benefits	AIA Noncommon Factor ⁽³⁾	AIA Noncommon	AIA Common Factor ⁽⁴⁾	AIA Common	Indirect Cost	
	(a)	(b)	(c) = (a) x (b)	(d)	(e) = (a) x (d)	(f)	(g) = ((c) + (e)) x (f)	(h) = (c) + (e) + (g)	
Payroll	\$51,909,110	59.48%	\$30,875,539	49.49%	\$25,689,819	9.12%	\$5,158,761	\$61,724,118	
Other	\$4,474,940	0%	\$0	0%	\$0	9.12%	\$408,115	\$408,115	
Total	\$56,384,050		\$30,875,539		\$25,689,819		\$5,566,875	\$62,132,233	

Section B. The Direct and Indirect Customer Contact Center Costs

Customer Contact Center	Direct Cost	% Delivery ⁽⁵⁾	Direct Cost Allocated to Delivery	Direct Cost Allocated to Supply	Indirect Cost	Indirect Cost Allocated to Delivery	Indirect Cost Allocated to Supply	Direct and Indirect Cost to Delivery	Direct and Indirect Cost to Supply
	(i) = (a)	(j)	(k) = (i) x (j)	(l) = (i) - (k)	(m) = (b)	(n) = (m) x (j)	(o) = (m) - (n)	(p) = (k) + (n)	(q) = (l) + (o)
	\$51,909,110	84.23%	\$44,885,395	\$5,223,516	\$61,724,118	\$50,756,614	\$10,967,504	\$93,442,209	\$20,191,029
	\$4,474,940	0.23%	\$1,679,806	\$275,134	\$408,115	\$335,508	\$72,516	\$4,015,402	\$967,659
	\$56,384,050		\$46,365,401	\$10,018,649	\$62,132,233	\$51,092,213	\$11,040,020	\$97,457,614	\$21,058,689

Notes

(1) From the Customer Contact Center Labor Costs and Customer Contact Center Other Costs columns of the 2023 Account 903 tab

(2) Average Rate for pensions, health care, incentives and payroll taxes ("Benefits"), apply to Payroll

(3) Affiliated Interest Agreement ("AIA") Non Common Back Office Rate - indirect labor costs related to office facilities human resources function, payroll department and computer equipment and software ("AIA Noncommon"), apply to Payroll

(4) AIA Common Back Office Rate - indirect labor costs related to accounting, legal, procurement, forms and other administrative and general expenses ("AIA Common"), apply to Benefits and AIA Noncommon related to Payroll

(5) From the Call Center Allocator row and the % Distribution column of Section C of the 2023 Call Center tab

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 41 of 580

Commonwealth Edison Company									
2023 Customer Contact Center Costs in Account 903 - Customer Records and Collection Expenses									
Dept ID	Dept - Descr	Proj - ID	Proj - Descr	Account Type	Customer Contact Center Costs	Customer Contact Center Payroll Costs	Customer Contact Center Other Costs		
486	Residential Implementation	13CSS503	Business Transformation & Tech	Other	\$150	\$0	\$150		
522	Business & Customer Support	ITCS1331	IL Clean Energy Law - NM O&M	Payroll	\$3,670	\$3,670	\$0		
1450	VP Customer Care	13CSS503	Business Transformation & Tech	Other	(\$37,530)	\$0	(\$37,530)		
1450	VP Customer Care	CSC001	Call Center Management	Other	\$884	\$0	\$884		
1450	VP Customer Care	CSV002	Manage Personnel - Acct 903	Other	\$413,986	\$0	\$413,986		
1450	VP Customer Care	CSV002	Manage Personnel - Acct 903	Payroll	\$324,206	\$324,206	\$0		
1451	Oak Brook Call Center	BITA612C	ComEd/PECO CC&B Impl O&M 2.0	Payroll	(\$22,599)	(\$22,599)	\$0		
1451	Oak Brook Call Center	CSC00001	Call Center Management	Other	\$105	\$0	\$105		
1451	Oak Brook Call Center	CSC001	Call Center Management	Other	\$1,851,842	\$0	\$1,851,842		
1451	Oak Brook Call Center	CSC001	Call Center Management	Payroll	\$9,908,066	\$9,908,066	\$0		
1451	Oak Brook Call Center	CSC002	Call Center Employee Costs	Other	\$192,310	\$0	\$192,310		
1451	Oak Brook Call Center	CSC002	Call Center Employee Costs	Payroll	\$30,480,268	\$30,480,268	\$0		
1451	Oak Brook Call Center	CSC002	Call Center Credit Disconnect	Payroll	\$5,425	\$5,425	\$0		
1451	Oak Brook Call Center	CSR002	Collect Customer Payment	Payroll	\$6,052	\$6,052	\$0		
1451	Oak Brook Call Center	TCCUST	Customer Service Training G&A	Other	\$125	\$0	\$125		
1451	Oak Brook Call Center	TCCUST	Customer Service Training G&A	Payroll	\$129,737	\$129,737	\$0		
1452	Chicago Reg Call Center	CSC001	Call Center Management	Other	\$0	\$0	\$0		
1454	Resource Management	CSC001	Call Center Management	Other	\$628,543	\$0	\$628,543		
1454	Resource Management	CSC001	Call Center Management	Payroll	\$2,042,229	\$2,042,229	\$0		
1454	Resource Management	CSS001	Respond to Customer Complaints	Payroll	\$0	\$0	\$0		
1457	eChannel	CSC001	Call Center Management	Other	\$0	\$0	\$0		
1460	SrVP Cust Operations ComEd	CSMG701	Customer Ops PMO Expense	Other	\$8,768	\$0	\$8,768		
1460	SrVP Cust Operations ComEd	CSV002	Manage Personnel - Acct 903	Other	\$188	\$0	\$188		
1461	Customer Relations West	13CSS503	Business Transformation & Tech	Other	\$0	\$0	\$0		
1461	Customer Relations West	CSC001	Call Center Management	Payroll	\$10,443	\$10,443	\$0		
1461	Customer Relations West	CSS002	Investigate Billing Exceptions	Payroll	\$72,845	\$72,845	\$0		
1461	Customer Relations West	CSS001	Respond to Customer Complaints	Other	\$53,930	\$0	\$53,930		
1461	Customer Relations West	CSS001	Respond to Customer Complaints	Payroll	\$1,068,821	\$1,068,821	\$0		
1474	LCS-Suburban	CSC002	Call Center Employee Costs	Payroll	\$159	\$159	\$0		
1492	Revenue Management	CSC001	Call Center Management	Other	\$3,149	\$0	\$3,149		
1492	Revenue Management	CSC001	Call Center Management	Payroll	\$48,810	\$48,810	\$0		
1492	Revenue Management	CSC002	Call Center Employee Costs	Payroll	\$79,528	\$79,528	\$0		
1492	Revenue Management	CSS002	Investigate Billing Exceptions	Payroll	\$5,511	\$5,511	\$0		
1493	Billing - WEST	CSC002	Call Center Employee Costs	Payroll	\$5,673	\$5,673	\$0		
1493	Billing - WEST	CSS002	Investigate Billing Exceptions	Other	\$1,334,192	\$0	\$1,334,192		
1493	Billing - WEST	CSS002	Investigate Billing Exceptions	Payroll	\$7,646,181	\$7,646,181	\$0		
1497	Project Planning ComEd	13CSS503	Business Transformation & Tech	Other	\$14,337	\$0	\$14,337		
1497	Project Planning ComEd	CSC001	Call Center Management	Payroll	\$10,825	\$10,825	\$0		
1511	AMI Operations	CSEM18	Provide AMR Cellular Services	Other	\$0	\$0	\$0		
1511	AMI Operations	CSEM18	Provide AMR Cellular Services	Other	\$125	\$0	\$125		
1511	AMI Operations	ITTFPCST	Tools for People - Customer	Other	\$78	\$0	\$78		
3460	Regional Operations Chicago	CSC001	Call Center Management	Other	\$0	\$0	\$0		
3460	Regional Operations Chicago	CSC001	Call Center Management	Payroll	\$55	\$55	\$0		
3460	Regional Operations Chicago	CSC002	Call Center Employee Costs	Other	\$486	\$0	\$486		
3460	Regional Operations Chicago	CSC002	Call Center Employee Costs	Payroll	(\$10,362)	(\$10,362)	\$0		
3461	Field Service Chicago	CSC001	Call Center Management	Other	\$150	\$0	\$150		
3461	Field Service Chicago	CSC002	Call Center Employee Costs	Other	\$924	\$0	\$924		
3461	Field Service Chicago	CSC002	Call Center Employee Costs	Payroll	(\$1,448)	(\$1,448)	\$0		
3463	Field Service Chgo So	CSC002	Call Center Employee Costs	Other	\$1,837	\$0	\$1,837		
3463	Field Service Chgo So	CSC002	Call Center Employee Costs	Payroll	\$9,879	\$9,879	\$0		
4468	Field Service Maywood	CSC001	Call Center Management	Other	(\$2,605)	\$0	(\$2,605)		
4468	Field Service Maywood	CSC001	Call Center Management	Payroll	\$263	\$263	\$0		
6460	Field Services Support	CSC001	Call Center Management	Other	\$0	\$0	\$0		
6460	Field Services Support	CSC001	Call Center Management	Payroll	\$15	\$15	\$0		
6460	Field Services Support	CSC002	Call Center Employee Costs	Other	\$6	\$0	\$6		
6460	Field Services Support	CSC002	Call Center Employee Costs	Payroll	\$3,569	\$3,569	\$0		
6463	Field Service University Park	CSC002	Call Center Employee Costs	Other	\$1,633	\$0	\$1,633		
6463	Field Service University Park	CSC002	Call Center Employee Costs	Payroll	(\$1,537)	(\$1,537)	\$0		
6468	Field Service Bolingbrook	CSC002	Call Center Employee Costs	Other	\$1,143	\$0	\$1,143		
6468	Field Service Bolingbrook	CSC002	Call Center Employee Costs	Payroll	(\$1,056)	(\$1,056)	\$0		
7460	Regional Ops Rock River	CSC001	Call Center Management	Other	\$0	\$0	\$0		
7460	Regional Ops Rock River	CSC001	Call Center Management	Payroll	(\$5,747)	(\$5,747)	\$0		
7460	Regional Ops Rock River	CSC002	Call Center Employee Costs	Other	(\$35)	\$0	(\$35)		

2024CRDICCCEAI 0000003

Commonwealth Edison Company								
2023 Customer Contact Center Costs in Account 903 - Customer Records and Collection Expenses								
Dept ID	Dept - Descr	Proj - ID	Proj - Descr	Account Type	Customer		Customer	
					Contact Center	Contact Center	Contact Center	Contact Center
					Costs	Payroll Costs	Other Costs	
7460	Regional Ops Rock River	CSCC02	Call Center Employee Costs	Payroll	(\$194)	(\$194)	\$0	
7460	Regional Ops Rock River	CSFM15	Provide Billing Services	Other	\$1,858	\$0	\$1,858	
7460	Regional Ops Rock River	CSFM15	Provide Billing Services	Payroll	\$46,108	\$46,108	\$0	
7460	Regional Ops Rock River	CSFM16	Cut Outs for Non Payment	Other	\$394	\$0	\$394	
7460	Regional Ops Rock River	CSFM16	Cut Outs for Non Payment	Payroll	\$5,551	\$5,551	\$0	
7460	Regional Ops Rock River	CSFM17	Cut In Non Payment Accounts	Other	\$131	\$0	\$131	
7460	Regional Ops Rock River	CSFM17	Cut In Non Payment Accounts	Payroll	\$2,151	\$2,151	\$0	
7460	Regional Ops Rock River	CSFM24	Field & Mtr Non Field Activity	Other	\$1,836	\$0	\$1,836	
7460	Regional Ops Rock River	CSFM24	Field & Mtr Non Field Activity	Payroll	\$37,418	\$37,418	\$0	
7460	Regional Ops Rock River	CSFMS01	FMS Management Oversight	Other	\$0	\$0	\$0	
7460	Regional Ops Rock River	CSFMS01	FMS Management Oversight	Payroll	(\$2)	(\$2)	\$0	
7460	Regional Ops Rock River	ITTFPCST	Tools for People - Customer	Other	\$522	\$0	\$522	
7467	Field Service Aurora	CSCC02	Call Center Employee Costs	Other	\$1,480	\$0	\$1,480	
7467	Field Service Aurora	CSCC02	Call Center Employee Costs	Payroll	(\$1,401)	(\$1,401)	\$0	
8579	ComEd Cust Assistance Program	CSCC01	Call Center Management	Other	\$0	\$0	\$0	
Total					\$56,384,050	\$51,905,110	\$4,474,940	

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 43 of 580

Commonwealth Edison Company 2023 Call Center Activity			
Section			
A. 2023 Call Volumes			
Group	Category	Description	Handled Transactions Designation
Billing	Balance	Activity Statement Agent	965 Bill Allocation
Billing	Balance	Activity Statement Fall Out	608 Bill Allocation
Billing	Balance	Balance Info Agent	36,625 Bill Allocation
Billing	Balance	Balance Info Fall Out	1,690 Bill Allocation
Billing	Balance	Bill History Fall Out	1,953 Bill Allocation
Billing	Balance	Duplicate Bill Agent	3,308 Bill Allocation
Billing	Balance	Duplicate Bill Fall Out	248 Bill Allocation
Billing	Budget	Budget Billing Agent	4,571 Bill Allocation
Billing	Budget	Budget Billing Fall Out	24,173 Revenue Allocation
Billing	Credit	Cut Out For Non Pay Agent	42,448 Revenue Allocation
Billing	Credit	Cut Out For Non Pay Fall Out	19,696 Bill Allocation
Billing	Credit	Disconnect Notice Agent	76,979 Bill Allocation
Billing	Credit	Disconnect Notice Fall Out	157 Bill Allocation
Billing	Credit	DPA Agent	48,730 Bill Allocation
Billing	Credit	DPA Fall Out	9,903 Bill Allocation
Billing	Credit	Early Contact	20,636 Bill Allocation
Billing	Credit	Extension Fall Out	6,366 Bill Allocation
Billing	Credit	Payment Extension Agent	12,136 Bill Allocation
Billing	Credit	Payment Extension Fall Out	29,853 Bill Allocation
Billing	Credit	RES Cred-Collect	8,265 Revenue Allocation
Billing	Miscellaneous	BCST	40,472 Revenue Allocation
Billing	Miscellaneous	ComEd Payments	2,809 Revenue Allocation
Billing	Miscellaneous	Miscellaneous Billing Agent	99,524 Revenue Allocation
Billing	Miscellaneous	Miscellaneous Billing Fall Out	831,282 Revenue Allocation
Billing	Miscellaneous	RES Other	8,453 Bill Allocation
Billing	Miscellaneous	Verify Payment Agent	21,903 Revenue Allocation
Billing	Miscellaneous	Verify Payment Fall Out	112,926 Revenue Allocation
Billing	Payment Options	eBill Agent	112 Revenue Allocation
Billing	Payment Options	eBill Fall Out	47 Revenue Allocation
Billing	Payment Options	EFT Agent	1,407 Revenue Allocation
Billing	Payment Options	EFT Fall Out	39,262 Revenue Allocation
Billing	Payment Options	Locate Payment Agent - Fall Out	629 Revenue Allocation
Billing	Payment Options	Locate Payment Agent - Request Agent	236 Revenue Allocation
Billing	Payment Options	Make a Payment Agent	205,572 Revenue Allocation
Billing	Payment Options	Make a Payment Fall Out	137,301 Revenue Allocation
Care	Care - English	CARE English	24,512 Revenue Allocation
Care	Care - English	ComEd Programs	1,059 Revenue Allocation
Care	Care - English	Smart Ideas	3,027 Revenue Allocation
Care	Care - Spanish	CARE Spanish	2,740 Revenue Allocation
Correspondence	Correspondence	Service Application ComEd	74,507 Revenue Allocation
Correspondence	Correspondence	OSR Activity Statement	7,962 Not Used for Allocation
Correspondence	Correspondence	Landlord agreement	43,822 Bill Allocation
Correspondence	Correspondence	Misc correspondence	39,172 Not Used for Allocation
Correspondence	Correspondence	Heat disclosure	32,651 Not Used for Allocation
Correspondence	Correspondence	Account maintenance	7,776 Revenue Allocation
Correspondence	Correspondence	Medical Letter ComEd	7,829 Not Used for Allocation
Correspondence	Correspondence	Budget Billing ComEd	3 Bill Allocation
Correspondence	Correspondence	ESO	25,030 Bill Allocation
Correspondence	Correspondence	Streetlight Outage ComEd	9,236 Distribution
Correspondence	Correspondence	Account history	5,871 Not Used for Allocation
Correspondence	Correspondence	Veinmail	1,854 Not Used for Allocation
Correspondence	Correspondence	GAA Request	11,720 Not Used for Allocation
Correspondence	Correspondence	OSR Duplicate Bill	2,521 Distribution
Correspondence	Correspondence	Duplicate Bill	6,726 Bill Allocation
Correspondence	Correspondence	Summary bill	2,406 Bill Allocation
Correspondence	Correspondence	OSR Medical Equipment	5,377 Bill Allocation
Correspondence	Correspondence	EFT Autopay ComEd	14 Bill Allocation
Correspondence	Correspondence	Priority correspondence	1,172 Revenue Allocation
Correspondence	Correspondence	OSR Credit Letter	586 Not Used for Allocation
Correspondence	Correspondence	IVR Processing Error ComEd	Revenue Allocation
Correspondence	Correspondence	Miscellaneous Central Handling ComEd	204 Distribution
Correspondence	Correspondence	Vegetation	2,309 Distribution
Correspondence	Correspondence	AC Cycling ComEd	16 Distribution
Correspondence	Correspondence	POS_ID ComEd	45 Distribution
Correspondence	Correspondence	Meter reading	268 Distribution
Correspondence	Correspondence	OSR Request ComEd	222 Distribution
Correspondence	Correspondence	BCST Miscellaneous	13 Not Used for Allocation
Correspondence	Correspondence	Utility Scan Report	396 Distribution
Correspondence	Correspondence	Start Service COMED	227 Revenue Allocation
Correspondence	Correspondence	Transfer Service COMED	11 Revenue Allocation
Correspondence	Correspondence	Stop Service COMED	23 Distribution
Customer Choice	Residential	Customer Choice Agent Eng	2,306 Not Used for Allocation

2024CRDICC AI 0000005

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 44 of 580

Group	Category	Description	Handled Transaction	Designation
Customer Choice	Residential	Customer Choice Fall Out Eng	15,728	Not Used for Allocation
Customer Choice	Spanish	Customer Choice Agent Spa	525	Not Used for Allocation
Customer Choice	Spanish	Customer Choice Fall Out Spa	4,449	Not Used for Allocation
Moving	Miscellaneous	Final Bill NL	252	Distribution
Moving	Miscellaneous	RES Start Stop	2,917	Distribution
Moving	Transfer	Transfer Service	61,241	Distribution
Moving	Transfer	Visual Voice Customer - Check Contac	1,807	Distribution
Moving	Turn Off	Stop Service Agent	5,734	Distribution
Moving	Turn Off	Stop Service Fall Out	110,972	Distribution
Moving	Turn Off	Visual Voice Customer - Check Contac	2,059	Distribution
Moving	Turn On	Start Service	456,961	Distribution
Moving	Turn On	Visual Voice Customer - Check Contac	8,190	Distribution
Other	Miscellaneous	AC Cycling	748	Distribution
Other	Miscellaneous	AMI Deployment	9	Distribution
Other	Miscellaneous	Energy Efficiency Loan	676	Distribution
Other	Miscellaneous	Home Energy Audit	2,138	Distribution
Other	Miscellaneous	Meter Reading Agent	1,862	Distribution
Other	Miscellaneous	Meter Reading Fall Out	66	Distribution
Other	Miscellaneous	Miscellaneous NL	40,847	Distribution
Other	Miscellaneous	Peak Time Savings Agent	1,485	Distribution
Other	Miscellaneous	Smart Grid	320	Distribution
Other	Miscellaneous	Solar Agent	3,168	Not Used for Allocation
Other	Miscellaneous	Solar Inter Connection	2,668	Not Used for Allocation
Other	Miscellaneous	Solar Net Metering	3,008	Not Used for Allocation
Other	Miscellaneous	Web Help	15,922	Not Used for Allocation
Outage	Emergency	Police Fire	13,715	Not Used for Allocation
Outage	Emergency	RES Outage	8,743	Distribution
Outage	Emergency	Wire Down	62,486	Distribution
Outage	Emergency	Electric Emerg	14,559	Distribution
Outage	Miscellaneous	Facility Protection	6,411	Distribution
Outage	Miscellaneous	Miscellaneous Outage	30,421	Distribution
Outage	Miscellaneous	Straight to Agent	54,695	Not Used for Allocation
Outage	Miscellaneous	Text Alerts Agent	1,223	Not Used for Allocation
Outage	Miscellaneous	Text Alerts Fall Out	450	Not Used for Allocation
Outage	Miscellaneous	Tree Trimming	1,071	Distribution
Outage	Miscellaneous	Voltage Information	5,110	Distribution
Outage	Report	Bilingual Outage	1,474	Distribution
Outage	Report	Dim Flicker Agent	19,059	Distribution
Outage	Report	Partial Outage Fall Out	825	Distribution
Outage	Report	Report Outage Agent	68,041	Distribution
Outage	Report	Report Outage Fall Out	94,513	Distribution
Outage	Report	Street Light Outage	2,973	Distribution
Total			3,335,718	

B. Number of Handled Transactions (Calls) by Designation

Designation	Number of Calls
Revenue Allocation ⁽¹⁾	1,674,531
Bill Allocation ⁽²⁾	365,352
Distribution ⁽³⁾	1,069,911
Not Used for Allocation ⁽⁴⁾	228,525
Total Number of Calls	3,338,719

C. Allocation of the Number of Calls to Distribution and Supply

Designation	Number of Calls	Allocation to Delivery and Supply		Allocated Number of Calls	
		% Distribution	% Supply	Distribution	Supply
Revenue Allocator	1,674,531	72.25%	27.75%	1,210,872	464,009
Bill Allocator	365,352	75.76%	24.24%	276,773	88,579
Distribution	1,069,911	100.00%	0.00%	1,069,911	0
Call Center Allocator	3,110,193	82.23%	17.77%	2,557,556	552,637

Notes

- (1) Revenue Allocation - Transaction related to Payment Plans, Service Disconnection, Actual Payments, ComEd Care Program Application Verification, W9 forms, or Electronic Fund Transfers (EFT)
- (2) Bill Allocation - Transaction related to a Balance, Budget Billing, Payments, Voice Response Unit (VRU), or Summary Billin
- (3) Distribution Allocation - Transactions related to Moving, Outages, Meter Reading, Vegetation Management (trees), Wiring Issues Street Lights, Duplicate Documentation, or ComEd Sponsored Programs
- (4) Not Used for Allocation - Transactions specifically related to unidentified calls or web correspondence

2024CRDICCBAI 0000006

Commonwealth Edison Company
2023 Base Revenues Used to Calculate Revenue Allocator

Retail Customer Designation	Distribution Base Rate Revenue		Supply Base Rate Revenue	
R: Residential	\$	2,287,700,299	\$	1,574,575,463
N: Nonresidential ⁽¹⁾	\$	2,355,514,351	\$	567,782,481
A: All Other ⁽²⁾	\$	52,429,571	\$	5,161,063
PORCB Receivables	\$	907,892,471		
Total	\$	5,603,536,692	\$	2,147,519,007
2023 Revenue Allocator		72.29%		27.71%

Notes:
(1) Commercial & Industrial Sales (Small or Commercial, Large or Industrial)
(2) Public Street & Highway Lighting, Other Sales to Public Authorities,
Sales to Railroads & Railways.

Commonwealth Edison Company
2023 Bill Allocation - Ratio of Delivery lines vs Total lines on a bill

Section A

Number of Lines on Bills					
Customer Type	Supply	Description	Supply Lines	Delivery Lines	Tax Lines
Nonresidential	ComEd	Hourly (400 - 1000)	5	4	6
Nonresidential	ComEd	Demand (100 - 400)	3	5	7
Nonresidential	ComEd	Demand (0 - 100)	3	4	7
Residential	ComEd	Single	3	4	5
Residential	ComEd	Multi	3	4	7
Residential	ComEd	Hourly (Single)	5	4	5
Nonresidential	REES	PORCB ⁽¹⁾	4	4	7
Nonresidential	REES	Dual ⁽²⁾	0	4	7
Residential	REES	PORCB ⁽¹⁾	1	4	5
Residential	REES	Dual			

Section B

Average Number of Lines on Bills				
Customer Type	Supply	Avg Supply Lines	Avg Delivery Lines	% Delivery
Nonresidential	ComEd	3.67	4.33	75%
Residential	ComEd	3.67	4.00	73%
Nonresidential	REES	2.00	4.00	65%
Residential	REES	1.00	4.00	50%

Section C

2023 Number of Bills by Supplier, Residential/Nonresidential, and Type of Bills																
	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual Total	Weighted	% Delivery	Weighted % Delivery
ComEd Supply																
Nonresidential	395,542	397,087	398,962	396,570	396,857	397,078	396,051	396,203	234,405	232,960	232,098	231,840	4,103,742	7.4%	75%	6%
Residential	3,670,709	3,684,498	3,678,102	3,665,874	3,666,202	3,661,239	3,653,496	3,652,172	2,952,542	2,942,812	2,944,923	2,954,038	41,124,606	74.0%	73%	54%
Total Electric Suppliers (REES)																
Nonresidential																
DUAL	40,690	40,837	40,811	39,902	39,812	41,068	39,993	39,145	38,671	38,661	38,731	39,239	477,568	0.9%	85%	1%
PORCB	76,512	76,499	78,134	78,762	79,238	80,618	82,754	84,061	84,553	85,016	86,881	87,215	981,897	1.8%	85%	1%
SDB ⁽³⁾	39,209	39,063	38,898	38,908	38,880	38,748	38,636	38,602	38,629	38,551	38,589	38,629	465,333	0.8%	85%	1%
Residential																
DUAL	18	21	22	15	0	793	668	16	18	24	15	20	1,689	0.0%	90%	0%
PORCB	644,617	647,544	676,964	681,064	683,904	704,981	715,251	717,946	715,709	735,359	743,746	749,621	8,416,730	15.1%	90%	14%
SDB	31	31	31	31	31	30	30	30	30	30	30	30	328	0.0%	90%	0%
Total	4,867,831	4,885,180	4,887,954	4,887,685	4,884,984	4,824,550	4,784,368	4,782,223	4,084,458	4,014,420	4,004,937	4,000,624	55,511,118	100.0%		46.8%

Notes:

(1) Rider PORCB - Purchase of Receivables with Consolidated Billing.

Dual bill means customers receive a delivery service bill from ComEd and a supply service bill from REES.

(3) SDB means customer receive a single bill that includes both delivery and supply service bill.

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.02:

Staff understands the genesis of the current analysis utilized by ComEd referenced in RML 1.01 was a response to the shortfalls identified utilizing the switching or allocation studies. Please confirm Staff's understanding is correct and:

- a) Provide an updated switching and alternative analysis for comparison purposes to the current model being used.
- b) Identify and discuss the relative strengths and weaknesses that may be found in the CCSA, switching study and the allocation study, and their underlying mechanics and/or calculations as used for allocation of Customer Care Costs.
- c) Explain whether ComEd has considered other methods to allocate billing calculation costs that may have been more relevant than either the CCSA, switching study or the allocation study and describe those methods.

RESPONSE:

As a general response to the question and statement that "Staff understands the genesis of the current analysis utilized by ComEd in RML 1.01 was a response to the shortfalls identified utilizing the switching or allocation studies," it is ComEd's position that the Switching Study presented in ICC Docket No. 10-0467 and ICC Docket No. 14-0312 is the best tool to assess whether a certain level of Customer Care Costs change due to customers switching suppliers, however, the Commission did not adopt the Switching Study and adopted a hybrid Alternative Study. Moving Delivery costs to Supply should receive careful consideration related to why costs should be allocated and how much cost, and the Commission adopted an approach they found to be reasonable and the fairest to ComEd and RES Supply customers.

- a) Updating the switching study will require coordination with multiple departments. ComEd will provide a supplemental response to this data request, including an updated Switching Study and alternative analysis, by early May 2025.
- b) The Customer Care Cost Allocation Study or CCSA is a hybrid of the Switching and Allocation studies and looks at the specific Customer Care Costs that were identified as sensitive to changes in the level of customer switching, which were the Customer Care Costs, and quantifies the portion of costs to be allocated to ComEd's Supply function using the total embedded costs for the Customer Care Center as the pool of costs to be allocated. The underlying mechanics for the CCSA were included in ICC Docket No. 24-0378, Leick Reb., ComEd Ex. 5.0 at 35:662 - 43:789. The exhibit and description can be found in the attachment labeled as RML 1.01_Attach 1.

A strength of the CCSA is that it limits the allocation to an area of cost that has been shown to actually be impacted based on the Switching Study - the Customer Care Center. While ideally, an actual avoided cost amount would be used to allocate amounts to Supply, the calculation for the allocation used in the CCSA, based off of granular contact

center information and appropriate allocation factors produce an acceptable amount to allocate to Supply.

The Switching Study examines whether the customer service costs are sensitive to customers switching from ComEd Supply to RES Supply to determine what costs, if any, are directly related to ComEd's Delivery service. This approach is designed to show what ComEd costs, if any, would be eliminated or increased at different switching levels. The underlying mechanics for the Switching Study were described in ICC Docket No. 14-0312, Donovan Dir., ComEd Ex. 7.0, p 39-44. The study results were included as ComEd Ex. 7.05 in Docket 14-0312, which is provided in the attachment labeled as RML 1.02_Attach 1. A strength of the Switching Study is that it determines how Customer Care Costs would **actually** change, due to customers switching suppliers. The Switching Study also recognizes that ComEd is the default provider that must stand ready to serve customers that have chosen to receive Supply service from a RES.

The Allocation Study seeks to determine what portion of Customer Care Costs are related to Delivery service and what portion is related to Supply service by applying allocation factors that are developed to approximate the relative contribution of each service function to the costs in question. The underlying mechanics for the Allocation Study were described in ICC Docket 14-0312, Donovan Dir., ComEd Ex. 7.0, p 40-43. The study results were included as ComEd Ex. 7.04 in Docket 14-0312, which is provided in the attachment labeled as RML 1.02_Attach 2. A weakness of the Allocation Study is that it assumes that all of ComEd's customer service costs are variable in nature. It also assumes that some Customer Care Costs across the board are attributable to Delivery service and some are not. Also, while the Allocation Study apportions a certain percentage of customer care costs to the ComEd Supply function, there is no corresponding allocation of costs from the Delivery function to a RES Supply function for those customer care activities that ComEd undertakes, which are related to electric supply provided by RESs. In the event that ComEd's Customer Care Costs are not considered to be common costs that ComEd incurs on behalf of all its approximately 4.1 million (meter) customers, and are instead allocated on the basis of an assumption that some Customer Care Costs are associated just with customers receiving electric supply service from ComEd, then it is reasonable to assume that some Customer Care Costs are associated with just customers receiving electric supply service from RESs.

- c) ComEd understands this subpart to be asking if ComEd evaluated including other costs that may not be included in the Customer Care Costs that are currently being allocated in the CCSA.

No, ComEd has not considered including other costs outside of the Customer Care Costs since the Commission provided directives on the methodology.

Leading up to the Commission's directive for the change in allocating Customer Care Costs to Supply in ICC Docket 14-0312, consistent with the statute, the Commission approved ComEd's allocation of Delivery-related expenses to Delivery rates in ComEd's first post-Restructuring Act rate case addressing Delivery service charges for all customers, which assigned customer care costs to the Delivery service revenue requirement. See *Commonwealth Edison Co.*, ICC Docket No. 01-0423 (Interim Order April 1, 2002) at 62-63; *Commonwealth Edison Co.*, ICC Docket No. 01-0423 (Final Order March 28, 2003) at 71-72. Since that time and in subsequent proceedings including ICC Docket 05-0597, ICC Docket 07-0528/07-0531 (Cons.), ICC Docket 07-0566, ICC Docket 08-0532, ICC Docket 10-0467, ICC Docket 14-0312 and ICC Docket 24-0387, additional costs for allocation have been proposed and discussed in those dockets, however, there was no Commission order to expand the scope of the costs.

In the Final Order of ICC Docket 10-0487, the Commission stated: “The Commission concludes, based upon the evidence presented, that ComEd analyzed the correct pool of costs in the “Switching Study,” except, as is provided herein regarding “Direct O&M Costs v. Total Costs,” which is set forth directly below.” Subsequently, ComEd did include the indirect costs.

Commonwealth Edison Company
Switching Study Results

For the Year Ending December 31, 2013

Line No.	Department / Activity (a)	Costs at 69% Switching (b)	Decreased (Increased) Costs at 64% Switching (c)	Decreased (Increased) Costs at 100% Switching (e)
1	Metering Services (1)	61,752,262	-	-
2	Advertising (1)	-	-	-
3	Subtotal	\$ 61,752,262	-	-
4	Field and Meter Services	12,056,540	-	-
5	Billing	7,506,221	-	-
6	Customer Contact Center	37,987,643	-	132,797
7	Customer Relations (4)	1,063,461	-	-
8	Large Customer Solutions	9,054,583	-	-
9	Revenue Management	28,007,976	-	-
10	Revenue Protection	2,291,422	-	-
11	Demand Management	4,510,803	-	-
12	Electric Supplier Services (3)	-	-	-
13	Market Research	-	-	-
14	Information Technology	27,971,046	112,343	(696,525)
15	Support Services	8,318,780	-	-
16	Other (2)	2,886,899	-	-
	Total Analyzed	\$ 141,655,375	\$ 112,343	\$ (563,729)
	Grand Total of Study	<u>\$ 203,407,637</u>	<u>\$ 112,343</u>	<u>\$ (563,729)</u>

(1) These costs were not further analyzed because the departments / activities relate solely to ComEd's distribution service.

(2) Other includes costs of the Project and Support, Claims, and the Credit Disconnect departments.

(3) There were no costs related to Electric Supplier Services in 2013 because projects from previous years had already been completed.

(4) The Customer Relations department was included in the (Other) category in 2010. Because of increased and better reporting in 2013, costs were able to be further analyzed in 2013.

Commonwealth Edison Company
Allocation Study Results

Actual Costs for the Year Ending December 31, 2013

Line No.	Department / Activity	Costs Analyzed	Costs Allocated to Supply	Costs Allocated to Delivery
	(a)	(b)	(c)	(d)
1	Metering Services (1)	61,752,262	-	61,752,262
2	Advertising (1)	-	-	-
3	Subtotal	\$ 61,752,262	-	\$ 61,752,262
4	Field and Meter Services	12,056,540	114,939	11,941,601
5	Billing	7,506,221	1,126,496	6,379,725
6	Customer Contact Center	37,987,643	4,710,594	33,277,049
7	Customer Relations (4)	1,063,461	169,831	893,631
8	Large Customer Solutions	9,054,583	90,546	8,964,037
9	Revenue Management	28,007,976	2,378,458	25,629,518
10	Revenue Protection	2,291,422	241,996	2,049,426
11	Demand Management	4,510,803	511,912	3,998,891
12	Electric Supplier Services (3)	-	-	-
13	Market Research	-	-	-
14	Information Technology	27,971,046	2,636,593	25,334,452
15	Support Services	8,318,780	-	8,318,780
16	Other (2)	2,886,899	156,346	2,730,554
	Total Analyzed	\$ 141,655,375	\$ 12,137,711	\$ 129,517,663
	Subtotal of Departments	\$ 203,407,637	\$ 12,137,711	\$ 191,269,926
	Grand Total of Study	<u>\$ 203,407,637</u>	<u>\$ 12,137,711</u>	<u>\$ 191,269,926</u>

(1) These costs were not further analyzed because the departments / activities relate solely to ComEd's distribution service.

(2) Other includes costs of the Project and Support, Claims, and the Credit Disconnect departments.

(3) There were no costs related to Electric Supplier Services in 2013 because projects from previous years had already been completed.

(4) The Customer Relations department was included in the (Other) category in 2010. Because of increased and better reporting in 2013, costs were able to be further analyzed in 2013.

Tab: 2014 Testimony Exhibit

April 2014

2024CRDICCAl 0000013

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.03:

Using the most current information, please provide a comparison of the Supply cost by customer class between ComEd rates to Alternative Retail Electric Supplier (ARES) rates.

RESPONSE:

ComEd understands this request to be asking for available public information related to ARES rates and not to disclose the information ARES's pass to ComEd for billing under ComEd's Rider PORCB - Purchase of Receivables with Consolidated Billing.

The following website for "Plug in Illinois" lists ComEd's current Price to Compare ("PTC") and offerings from ARES that chose to list their offerings:
<https://plugin.illinois.gov/your-available-choices/offers.html?said=1>

The "Plug in Illinois" website also contains a list of ARES rates for municipalities with municipal aggregation where the residents within a governmental body (municipality, county, etc.) are provided the option of electing service with an ARES at a set rate.
<https://plugin.illinois.gov/municipal-aggregation/municipal-aggregation-list.html>

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.04:

Does ComEd track whether calls, questions, concerns, or complaints from customers ("Customer Inquiries") received by ComEd's call center are related to supply charges or delivery services charges between ComEd and ARES customers. If the answer is yes, then please provide the percentage of Customer Inquiries that are supply related and the percentage that are delivery services related. If the answer is no, then please explain in detail why not.

RESPONSE:

The ComEd call center does not track "Customer Inquiries" by Supply or Delivery service charges or by ComEd and ARES customers. ComEd has an obligation to deliver electricity to all customers regardless of where Supply is purchased, and as such, there has been no specific need to monitor calls by these categories.

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.05:

Did ComEd's Customer Care Costs increase or decrease (in total) between 2014 and 2024, as the number of customers that have switched to an ARES supply has increased? If so, provide the increase by year and identify the factors which ComEd attributes the change.

RESPONSE:

The table below shows the Customer Care Center costs for years 2013 through 2023, the year-over-year ("YoY") change in cost and the year-over-year change in customers on Rate RDS taking Supply from an ARES. The 2024 costs will be provided in ComEd's 2024 Performance Adjustment and Annual Adjustment filing in May. Over the 10-year period of 2013 to 2023, there was only one year where the number of customers switching to an ARES increased. In 2023, the number of customers switching to ARES increased by 2.6% and the Customer Care Center cost decreased by 3.9%. In other years during 2013-2023, as the number of customers on an ARES decreased, there was no consistent pattern, where costs in some years increased and in some years decreased.

Docket	Year Costs Incurred	Customer Care Center Costs Analyzed	YoY Cost Increase/ (decrease) %	YoY % Change in Customers on Rate RDS
24-0304	2023	\$ 118,516,283	-2.1%	2.6%
23-0345	2022	121,008,923	2.1%	-3.9%
22-0302	2021	118,497,480	4.9%	-5.2%
21-0367	2020	112,947,481	-4.6%	-2.4%
20-0393	2019	118,350,446	0.6%	-3.3%
19-0387	2018	117,601,546	6.1%	-0.3%
18-0808	2017	110,847,868	7.3%	-3.7%
17-0196	2016	103,259,011	10.2%	-4.3%
16-0259	2015	93,683,253	-2.6%	-19.4%
15-0287	2014	96,215,843	9.2%	-7.4%
14-0312	2013	88,119,784		

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.06:

Does ComEd incur Customer Care Costs when a customer switches to ARES for their supply service. Please explain in detail.

RESPONSE:

Yes. As an Electric Distribution Company ("EDC") in Illinois, ComEd incurs costs when a customer switches to or from an ARES supplier for energy service, as well as when a customer switches between ARES suppliers. For example, the Electric Supplier Services Department ("ESSD") within ComEd's Energy Acquisition group manages ComEd's operating relationships with ARES in ComEd's service territory. ESSD facilitates Electronic Data Interchange ("EDI") data transmittals to or from ARES, performs validation, processing, and communication tasks, and addresses questions on switching, all of which serve to support ARES (and Community Supply, as Community Supply entities also engage in customer enrollments) by ensuring customers are successfully switched in ComEd's billing system. ESSD also administers Rider PORCB – Purchase of Receivables with Consolidated Billing - whereby ARES provide ComEd with supply charges to present on ComEd customer bills. Similarly, Energy Acquisition's Wholesale Settlement Operations, Wholesale Markets and Development, and Wholesale Billing and Credit groups include ARES and their supply customers in creating and scheduling customer load responsibilities in the PJM wholesale market, calculating customers' Peak Load Contribution and Network Service Peak Load values, reconciliation and posting to PJM of scheduled loads to actual meter readings, and ensuring accurate allocation of PJM costs in the ComEd Zone.

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.07:

Does ComEd incur Customer Care Costs when a customer switches to an ARES provider for their supply service? If so, please explain how the costs are incurred in detail.

RESPONSE:

This is a duplicate request to RML 1.06. See ComEd's Response to Staff Data Request RML 1.06.

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.08:

Would ComEd agree that it is the default supply service provider (see 220 ILCS 5/16-103(c)) and thus it must stand ready to serve customers that have chosen to receive supply service from ARES?

- a) If ComEd agrees, is it ComEd's position that regardless of the number of customers that switch away from ComEd for supply service, ComEd must incur the necessary costs to stand ready to serve them when those customers return to ComEd?
- b) If ComEd does not agree, please explain.

RESPONSE:

Yes, ComEd agrees that as part of its obligations as an electric utility, ComEd is required to stand ready to provide Supply-related services to all customers, including those who may have previously been customers of an ARES.

- a) Yes, ComEd agrees that it must incur the necessary costs to ensure it is capable of serving customers that return from ARES service to take ComEd's Supply service.
- b) Not applicable.

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.09:

In Docket 24-0378, ICEA-RESA witness Frank Lacey's opines that \$492 million should be allocated to the default service. (ICEA-RESA Ex. 4.0,8)

- a) How does that compare to the allocation that ComEd determined under the updated CCSA study from RML 1.01 above?
- b) Please provide an analysis or explanation for what the differences are between the 2 approaches.

RESPONSE:

- a) In ICC Docket No. 24-0378, ICEA-RESA witness Frank Lacey opines that \$492 million should be allocated to the default service (Lacey Reb., ICEA-RESA Ex. 4.0 at 8) while ComEd's allocation resulted in \$21 million being allocated. ComEd's \$21 million allocation is described in more detail in the Rebuttal Testimony of ComEd witness Leick in the underlying RDI proceeding, ICC Docket No. 24-0378, ComEd Ex. 5.0 at 35 - 43. Also, see the attachment to ComEd's Response to Staff Data Request RML_1.01 labeled as RML 1.01_Attach 1.
- b) The CCSA is a hybrid of the Switching and Allocation studies and looks at the specific Customer Care Costs that were identified as sensitive to changes in the level of customer switching, the Customer Care Center costs, and quantifies the portion of costs to be allocated to ComEd's Supply function using the total embedded costs for the Customer Care Center as the pool of costs to be allocated. The underlying mechanics for the CCSA were included in ICC Docket No. 24-0378, Leick Reb., ComEd Ex. 5.0 at 35:662 - 43:789.

ComEd's understanding of ICEA-RESA witness Frank Lacey's recommendation to allocate \$492 million to default service involves:

- 1. Identifying Costs: Certain FERC accounts related to default service are reassigned to Supply.
- 2. Using Allocators: Costs are allocated based on the number of customers and revenue.

3. Assigning Costs: Costs attributable RES Supply remain in Delivery rates, paid by all customers.
4. Implementation: Allocators are applied to FERC accounts, redistributing costs based on customer numbers and revenue.

This approach raises fairness concerns as RES Supply costs are socialized among ComEd Supply customers. This understanding was included in greater detail in ICC Docket No. 24-0378, Leick Reb., ComEd Ex. 5.0 at 44:826 - 49:879.

Finally, the proposed cost categories to reallocate Delivery to Supply by ICEA-RESA extend beyond the Customer Care Center Costs and are across several cost categories as shown below in their "Rebuttal" proposal in the table from Leick Sur., ComEd Ex. 10.0 at 30:594 in ICC Docket No. 24-0378. As ComEd witness Leick discussed in his rebuttal testimony in that proceeding, none of the cost category subfunctions identified by ICEA-RESA in Table 2 implicate the Supply function. See ICC Docket No. 24-0378, Leick Reb., ComEd Ex. 5.0 at 52:913 - 60:1087.

Table 2 – Change in ICEA-RESA Proposal to Move Delivery Costs to Supply

	Direct	Rebuttal	Difference
2026 Cost of Service by Subfunction:	(a)	(b)	(c) = (b) - (a)
Shared Distribution Lines (Over 4kV)	\$141,214,977	\$44,637,545	(\$96,577,431)
Secondary Voltage Dist. Lines	-\$127,040	\$2,334,834	\$2,461,874
Services	\$107,712,548	\$0	(\$107,712,548)
Customer Installation – Other	\$70,625,410	\$13,724,629	(\$56,900,781)
Metering Services	\$153,751,040	\$153,751,040	\$0
Billing – Computation & Data Mgmt.	\$205,588,457	\$205,588,457	\$0
Indirect Uncollectibles	\$5,294,949	\$5,294,949	\$0
Bill Issue & Processing	\$21,647,770	\$21,647,770	\$0
Customer Information	\$10,828,373	\$45,053,078	\$34,224,706
Illinois Electricity Distribution Tax	\$207,766,000	\$0	(\$207,766,000)
Total	\$924,302,485	\$492,032,304	(\$432,270,181)

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.10:

Have the external or internal auditors evaluated ComEd's allocation methodology with respect to Customer Care Costs and compliance with NARUC guidance (Cost guidelines for Cost Allocation and Affiliate Transactions, Section D, P. 3, see: <https://pubs.naruc.org/pub/539BF2CD-2354-D714-51C4-0D70A5A95C65> and made a determination? If yes, please explain why not.

RESPONSE:

The external or internal auditors have not evaluated ComEd's allocation methodology with respect to Customer Care Costs for compliance with NARUC guidance (Cost Guidelines for Cost Allocation and Affiliate Transactions, Section D, P. 3). This is because the NARUC guideline is not applicable to the allocation methodology in question. The guideline pertains to affiliate transactions and affiliates are defined in the document as: "Affiliates - companies that are related to each other due to common ownership or control." The costs in question are internal costs to ComEd and do not involve affiliate transactions.

ComEd notes that costs related to the procurement of energy are already allocated to the Supply function and recovered in ComEd's Supply rates. See the attachment labeled as RML 1.10_Attach 1, the Direct Testimony of ComEd witness Christopher Foley, ComEd Exhibit 2.0, in ICC Docket No. 24-0079, which reconciles the revenues collected to the cost incurred under ComEd's Supply rates (for June 2022 - May 2023). In his testimony at lines 4:73 - 20:391 he discusses the Energy Acquisition Departments, Other Administrative and Operational Costs and the allocation of those costs in ComEd's Supply riders,

The Supply riders are subject to annual audit. The audit is conducted by Exelon Audit Services (EAS). The results are filed with the Illinois Commerce Commission and presented as evidence in the annual reconciliation proceedings. See the attachment labeled as RML 1.10_Attach 2, the EAS Report presented as ComEd Ex. 1.01 in the most recently completed Supply reconciliation proceeding, ICC Docket No. 24-0079 in which EAS reports that the controls are effective.

STATE OF ILLINOIS

ILLINOIS COMMERCE COMMISSION

COMMONWEALTH EDISON COMPANY	)	
	)	Docket No. 24-0079
Reconciliation of revenues collected under	)	
power procurement riders with actual costs	)	
associated with power procurement	)	
expenditures.	)	

Direct Testimony of

CHRISTOPHER M. FOLEY

Director, Energy Acquisition
Commonwealth Edison Company

TABLE OF CONTENTS

I. INTRODUCTION AND BACKGROUND 1

 A. Witness Identification 1

 B. Background, Qualifications, and Experience..... 1

 C. Purpose of Testimony 2

 D. Recommendations..... 3

 E. Attachments to Direct Testimony 3

II. ADMINISTRATIVE AND OPERATIONAL COSTS FOR PROCURING
ELECTRIC POWER AND ENERGY FOR RIDER PE, RATE BESH, AND RATE
RTOUPP CUSTOMERS 4

 A. Internal Administrative and Operational Costs..... 5

 B. Other Administrative and Operational Costs..... 11

III. REASONABLENESS OF THE ADMINISTRATIVE AND OPERATIONAL
COSTS 16

IV. COMPLIANCE WITH THE PROCUREMENT PLAN 20

1 **I. INTRODUCTION AND BACKGROUND**

2 **A. Witness Identification**

3 Q. **What is your name and business address?**

4 A. My name is Christopher M. Foley. My business address is Commonwealth Edison
5 Company ("ComEd"), 1919 Swift Drive, Oak Brook, Illinois 60523.

6 Q. **By whom are you employed and in what capacity?**

7 A. I am employed by ComEd as Director, Energy Acquisition.

8 **B. Background Qualifications, and Experience**

9 Q. **What are your duties and responsibilities in your current position?**

10 A. In my current capacity, I am responsible for leading and managing ComEd's Energy
11 Acquisition Department, which is responsible for procurement of wholesale electric
12 supply, PJM Interconnection, LLC ("PJM") wholesale market settlements, and Retail
13 Choice functions for ComEd. This includes overseeing the administrative and operational
14 processes used to procure electric power and energy.

15 Q. **What is your professional experience?**

16 A. I actively practiced law from 1992 until 1999, primarily as a trial attorney. In 2001, I
17 became in-house counsel for Edison Mission Energy, an independent power producer. I
18 have been employed by ComEd since 2014. I was Director, Energy Policy until July 2019
19 and then moved to my current position as Director, Energy Acquisition. While I am a
20 licensed attorney, my testimony does not reflect any legal opinions or advice.

21 Q. **What is your educational background?**

22 A. I have a Bachelor of Arts from Washington College, a Juris Doctor from Widener
23 University, and a Master of Business Administration from The George Washington
24 University.

25 Q. **Have you submitted testimony to the Illinois Commerce Commission (“ICC” or
26 “Commission”) in prior proceedings?**

27 A. Yes. I provided testimony in support of ComEd in several reconciliation proceedings,
28 including Rider PE, Rate BESH, and Rate RTOUPP reconciliation (also known as the
29 “power procurement”) proceedings, (ICC Docket Nos. 20-0133, 21-0094, 22-0103, and
30 23-0064).

31 **C. Purpose of Testimony**

32 Q. **What is the purpose of your testimony?**

33 A. The purpose of my testimony is to describe and support the reasonableness of ComEd’s
34 administrative and operational costs associated with the procurement of electric power and
35 energy for retail customers and served under: Rider PE – Purchased Electricity (“Rider PE”
36 or “fixed-price”), Rate BESH – Basic Electric Service Hourly Pricing (“Rate BESH” or
37 “hourly-priced”), and Rate RTOUPP – Residential Time of Use Pricing Pilot (“Rate
38 RTOUPP” or “TOU”) for the Reconciliation Period (i.e., the period involved in this
39 proceeding under the applicable tariffs, June 1, 2022 through May 31, 2023). In addition,
40 I explain how ComEd complied with the applicable procurement plan approved by the
41 Commission.

42 More specifically, in my testimony, I: (1) provide a description of the types of
43 administrative and operational costs that were recovered from retail customers under the
44 tariff provisions of Rider PE, Rate BESH, and Rate RTOUPP; (2) explain how ComEd's
45 administrative and operational costs associated with procuring electric power and energy
46 were charged to retail customers served under those three tariffs; (3) explain why it was
47 reasonable for ComEd to incur such costs to procure electric power and energy for those
48 retail customers; and (4) discuss compliance with the Procurement Plan approved by the
49 Illinois Commerce Commission ("Commission" or "ICC") in Docket 21-0717.

50 **D. Recommendations**

51 Q. **What are your recommendations?**

52 A. I recommend the Commission approve the amount of administrative and operational costs
53 that ComEd incurred in procuring electric power and energy for retail customers and served
54 under Rider PE, Rate BESH, and Rate RTOUPP during the Reconciliation Period, and find
55 that these costs were reasonable. Furthermore, I recommend the Commission find that
56 ComEd fully complied with the applicable Commission-approved Procurement Plan.

57 **E. Attachments to Direct Testimony**

58 Q. **Are you sponsoring any attachments to your testimony?**

59 A. Yes. Attached hereto are:

- 60 • **ComEd Exhibit ("Ex.") 2.01**, which contains general descriptions and
61 breakdowns of the various categories of administrative and operational costs that
62 ComEd incurred in procuring electric power and energy for retail customers during
63 the Reconciliation Period. I provide a conclusion about the reasonableness of these

64 costs and the basis for that conclusion in Section III of my testimony. ComEd Ex.
65 2.01 reflects certain administrative and operational costs associated with Rates
66 BESH and RTOUPP that were allocated on a load-weighted basis. ComEd witness
67 Heather N. Hopkins explains in her direct testimony the reason for the use of the
68 load-weighted allocations in ComEd Ex. 2.01. See ComEd Ex. 1.0.

69 • **ComEd Ex. 2.02**, which contains general descriptions and breakdowns of the
70 various categories of administrative and operational costs that ComEd incurred in
71 procuring electric power and energy for retail customers during the Reconciliation
72 Period. ComEd Ex. 2.02 does not reflect load-weighted allocations.

73 **II. ADMINISTRATIVE AND OPERATIONAL COSTS FOR PROCURING**
74 **ELECTRIC POWER AND ENERGY FOR RIDER PE, RATE BESH, AND RATE**
75 **RTOUPP CUSTOMERS**

76 Q. **Generally, what were the administrative and operational costs associated with the**
77 **procurement of electric power and energy for retail customers served under Rider**
78 **PE, Rate BESH, and Rate RTOUPP for the Reconciliation Period?**

79 A. There were two types of administrative and operational costs during the Reconciliation
80 Period. First were internal administrative and operational costs related to the procurement-
81 related functions of ComEd's Energy Acquisition Department. Second were
82 administrative and operational costs other than the Energy Acquisition Department costs
83 that ComEd incurred to obtain products or services needed by the Energy Acquisition
84 Department to perform its procurement-related functions. ComEd Ex. 2.01 presents a
85 summary schedule of both costs. While the Commission's Order commencing this
86 proceeding required only that ComEd address in testimony its internal administrative and

87 operational costs, in past reconciliation proceedings the Staff of the Commission (“Staff”)
88 has inquired about other types of administrative and operational costs. *Commonwealth*
89 *Edison Co.*, ICC Docket No. 24-0079, Initiating Order (Jan. 31, 2024) at 3. Accordingly,
90 I discuss those other costs in my direct testimony.

91 **A. Internal Administrative and Operational Costs**

92 Q. **How was ComEd’s Energy Acquisition Department organized during the**
93 **Reconciliation Period?**

94 A. The ComEd Energy Acquisition Department consisted of five functional groups:
95 Procurement Planning and Strategy; Wholesale Billing and Credit; Wholesale Supplier
96 Operations; Wholesale Markets and Development; and Electric Supplier Services.

97 Q. **What functions did the Procurement Planning and Strategy group perform during**
98 **the Reconciliation Period?**

99 A. The Procurement Planning and Strategy group was responsible for developing and
100 advocating ComEd’s position in the annual procurement and reconciliation proceedings,
101 fulfilling ComEd’s responsibilities in Illinois Power Agency (“IPA”) procurement events.

102 Q. **How was the Procurement Planning and Strategy group organized and staffed?**

103 A. During the Reconciliation Period, the work was performed by one full-time equivalent
104 (“FTE”) analyst.

105 Q. **What were the costs associated with operating the Procurement Planning and**
106 **Strategy group during the Reconciliation Period?**

107 A. The costs consisted primarily of labor, including benefits. Other costs included office
108 space, computer and telephone equipment, and providing services and other support to
109 RESs.

110 Q. **What functions did the Wholesale Billing and Credit group perform during the**
111 **Reconciliation Period?**

112 A. The Wholesale Billing and Credit group validated PJM's invoiced charges to ComEd and
113 initiated payments to PJM for confirmed services. They also validated charges to ComEd
114 from ComEd's wholesale suppliers and initiated payments for those deliveries. They also
115 managed all wholesale supplier contracts, including the Master Power Purchase and Sale
116 Agreements from the biannual procurement events and the Master Renewable Energy
117 Purchase and Sale Agreements from previous procurement events. Finally, they monitored
118 and processed PJM-required credit, including collateral payments to PJM and the return of
119 collateral from PJM.

120 Q. **How was the Wholesale Billing and Credit group organized and staffed?**

121 A. During the Reconciliation Period, there was a Senior Manager of the group who oversaw
122 two Managers that supervised the collective work of seven FTE analysts.

123 Q. **What were the costs associated with operating the Wholesale Billing and Credit group**
124 **during the Reconciliation Period?**

125 A. The costs consisted primarily of labor, including benefits. Other costs included office
126 space, computer and telephone equipment, and providing services and other support to
127 RESs.

128 Q. **What functions did the Wholesale Supplier Operations group perform during the**
129 **Reconciliation Period?**

130 A. The Wholesale Supplier Operations group performed several daily processes. It validated
131 individual retail customer enrollments for each Retail Electric Supplier ("RES") to ensure
132 that the daily load responsibilities of each RES were accurate. It calculated individual retail
133 customer Capacity Peak Load Contributions and Network Service Peak Load
134 Contributions, aggregated them by the responsible RES, and submitted them to PJM so
135 that PJM properly billed each RES for generation capacity and transmission service. The
136 group submitted daily load bids for the retail load served by ComEd into the PJM Day-
137 Ahead energy market. It forecasted RES hourly energy load serving responsibilities and
138 monitored the hourly load serving responsibilities submitted by each RES to PJM to ensure
139 good-faith scheduling. The group forecasted and submitted to PJM hourly load serving
140 responsibility estimates for the load supplied by ComEd. It also confirmed scheduled
141 physical deliveries by ComEd's wholesale suppliers. Finally, the Wholesale Supplier
142 Operations group performed the settlement of actual versus estimated supplier load
143 responsibilities with PJM.

144 Q. **How was the Wholesale Supplier Operations Development group organized and**
145 **staffed during the Reconciliation Period?**

146 A. During the Reconciliation Period, there was one Senior Manager who oversaw two FTE
147 analysts and a Manager, who supervised the work of three FTE analysts, in the Wholesale
148 Supplier Operations group.

149 Q. **What were the costs associated with operating the Wholesale Supplier Operations**
150 **group?**

151 A. The costs consisted primarily of labor, including benefits. Other costs included office
152 space, computer and telephone equipment, training expenses, and the maintenance and
153 support of the Retail Office ("RO") software, and other back-office systems that stored and
154 analyzed customer and supplier data and were used to submit this data to PJM.

155 Q. **What functions did the Wholesale Markets and Development group perform during**
156 **the Reconciliation Period?**

157 A. The primary role of the Wholesale Markets and Development group was to calculate the
158 hourly load of the ComEd's Transmission Zone in PJM on a daily basis. This calculation
159 was the starting point for the allocation of load responsibilities to ComEd and each RES in
160 the ComEd Zone. This calculation was done by obtaining hourly meter values for all
161 generation meters (excluding "behind-the-meter" generation) and all transmission tie-line
162 meters associated with the ComEd Zone. The hourly zonal load was calculated by taking
163 the sum of all generation within the zone, adding simultaneous imports, and subtracting
164 simultaneous exports. In addition, this group ensured compliance with certain North

165 American Electric Reliability Corporation (“NERC”) and Reliability First Corporation
166 standards.

167 Q. **How was the Wholesale Markets and Development group organized and staffed**
168 **during the Reconciliation Period?**

169 A. During the Reconciliation Period, there was one Senior Manager who supervised three FTE
170 analysts in the Wholesale Markets and Development group.

171 Q. **What were the costs associated with operating the Wholesale Markets and**
172 **Development group?**

173 A. The costs consisted primarily of labor, including benefits. Other costs included office
174 space, computer and telephone equipment, and training expenses. The functions of this
175 group were required solely for the purposes of fulfilling ComEd’s obligations to PJM as
176 an electric distribution company, and these functions were required regardless of whether
177 ComEd provided supply services to any customer. There was no incremental work
178 required in this group because of ComEd’s supply responsibilities to its retail customers.
179 Therefore, none of the costs associated with the functions of this group have been allocated
180 to the costs recovered under Rider PE, Rate BESH, and Rate RTOUPP.

181 Q. **What functions did the Electric Supplier Services group perform during the**
182 **Reconciliation Period?**

183 A. The primary responsibility of the Electric Supplier Services group was to serve as the main
184 point of contact with RESs, including certifying new RESs and addressing RES issues.
185 The group processed customer enrollments with RESs and processed customer enrollments

186 to ComEd's hourly-priced service. In addition, the group served as the key point of contact
187 with Community Supply developers, including setting up developers in the Community
188 Supply portal and assisting with Community Supply Subscriber enrollments. Finally, the
189 group provided historical customer usage data to market participants that had customer
190 authorization to receive the data.

191 Q. **How was the Electric Supplier Services group organized and staffed?**

192 A. During the Reconciliation Period, there was a Senior Manager who oversaw two Managers
193 that supervised the collective work of 10 FTE employees.

194 Q. **What were the costs associated with the Electric Supplier Services group during the
195 Reconciliation Period?**

196 A. The costs consisted primarily of labor, including benefits. Other costs included computer
197 and telephone equipment, training expenses, and providing services and other support to
198 RESs.

199 Q. **During the Reconciliation Period, were there any additional internal administrative
200 and operational costs related to the procurement-related functions of ComEd's
201 Energy Acquisition Department?**

202 A. Yes. As Director, Energy Acquisition, all five groups reported to me during the
203 Reconciliation Period, and I oversaw the work performed within these groups related to
204 procurement administrative costs. In addition, the Vice President, Strategy and Energy
205 Policy to whom I reported, and our administrative assistant, spent a portion of their time
206 working on procurement-related activities.

207 Q. **How did ComEd charge the internal administrative and operational costs that you**
208 **describe above between Rider PE, Rate BESH and Rate RTOUPP and other ComEd**
209 **tariffs?**

210 A. During this Reconciliation Period, each employee directly charged their time (i.e., daily,
211 or weekly), based on activities related to either ComEd's procurement responsibilities (for
212 either electric supply, renewable energy credits ("RECs"), zero emissions credits
213 ("ZECs"), or carbon mitigation credits ("CMCs")) or ComEd's responsibilities as an
214 electric distribution company. Hence, the internal administrative and operational costs
215 related to the procurement-related functions of ComEd's Energy Acquisition Department
216 that are part of the Energy Acquisition Department Internal Costs listed in ComEd Ex. 2.01
217 reflect the direct costs to Rider PE, Rate BESH, and Rate RTOUPP procurement activities.

218 **B. Other Administrative and Operational Costs**

219 Q. **What were the administrative and operational costs other than the Energy**
220 **Acquisition Department costs that ComEd incurred to obtain products or services**
221 **needed by the Energy Acquisition Department to perform its procurement-related**
222 **functions during the Reconciliation Period?**

223 A. In general, these were the costs that ComEd's Energy Acquisition Department incurred in
224 procuring electric power and energy for ComEd's retail customers, excluding the internal
225 costs of ComEd's Energy Acquisition Department and the direct costs of the electric supply
226 itself, *e.g.*, energy, capacity, ancillary, and transmission services to serve ComEd's
227 customers. I describe and breakdown these cost categories as they appear in ComEd Ex.
228 2.01.

229 Q. **What were the Information Technology Systems Costs during the Reconciliation**
230 **Period?**

231 A. These were the costs incurred to maintain and support the Retail Office (RO) software that
232 is used by the Energy Acquisition Department's Wholesale Supplier Operations. RO is a
233 standard industry wholesale settlements software program that assists in the determination
234 of the amount of load served by ComEd pursuant to Rider PE, Rate BESH, and Rate
235 RTOUPP. PJM requires that ComEd report this information daily. When ComEd needs
236 to revise the RO system in response to various PJM rule changes, consistent with the
237 Commission's approval in ICC Docket No. 05-0597 and standard accounting practices,
238 ComEd capitalizes those costs and amortizes them over a five-year period. See ComEd
239 Ex. 2.01.

240 Q. **What were the PJM Credit Costs during the Reconciliation Period?**

241 A. PJM Credit Costs represent the credit facility costs for the posting of PJM-required credit.
242 PJM requires collateral of all members as insurance for payment of services rendered to
243 serve the load. The applicable ICC-approved Procurement Plan provides for ComEd to
244 procure the electric supply to balance the load of its fixed-price customers directly from
245 the PJM energy markets. See *Illinois Power Agency*, ICC Docket No. 21-0717, 2022
246 Illinois Power Agency Final Electricity Procurement Plan (Feb. 7, 2022) ("2022
247 Procurement Plan") at 2, 73, 76, and 78.

248 Similarly, Section 16-111.5(a) of the Public Utilities Act ("PUA") requires ComEd
249 to procure the electric supply to serve the full load of its hourly-priced customers from the
250 "applicable market," i.e., PJM, as well. In addition, ComEd procures energy, capacity,

251 ancillary, and transmission services to serve its fixed-price, hourly-priced, and TOU
252 customers from PJM. See 2022 Procurement Plan at 2, 4, 5, 78, and 96. Thus, ComEd
253 must post collateral for this load.

254 PJM requires its members that are in a net buyer position to post collateral to cover
255 PJM's exposure to possible payment default. Because ComEd has no generation of its
256 own, it will typically be in a position that requires it to buy from the market and therefore
257 be required to post collateral. Because the contracts for the block energy products (which
258 are most of the energy that ComEd procures) require the suppliers to physically deliver this
259 supply, ComEd is not required to post collateral for this portion of its load. This PJM
260 requirement, which ComEd has consistently supported, serves to minimize the amount of
261 PJM credit costs that ComEd must incur.

262 Q. **What were the IPA Fees and ICC Procurement Monitor Costs during the**
263 **Reconciliation Period?**

264 A. IPA Fees are billed to ComEd, as provided for in the IPA Act, to pay for consultants and
265 administrators engaged by the IPA to help in the development and implementation of the
266 applicable procurement plan. 20 ILCS 3855. The Procurement Monitor Costs are costs
267 directly associated with the payment of bills by ComEd for the professional services of a
268 Procurement Monitor who was employed by Staff for the purposes of monitoring the fixed-
269 price procurement process. The costs shown on ComEd Ex. 2.01 for IPA Fees and
270 Procurement Monitor Costs include the costs related to the 2022 Procurement Plan
271 proceeding, ICC Docket No. 21-0717, which were incurred and passed through to
272 customers during the Reconciliation Period.

273 Q. **What were the Procurement Plan and Reconciliation Proceeding Costs during the**
274 **Reconciliation Period?**

275 A. These were primarily costs incurred in developing, obtaining approval for, and
276 implementing the 2022 Procurement Plan, covering the period June 2022 through May
277 2027, which was approved by the Commission in ICC Docket No. 21-0717. Also included,
278 when applicable, were procurement-related costs that were incurred during the
279 Reconciliation Period and generally related to issues that arose in administering existing
280 electric supply and to the reconciliation process and proceedings. These costs, when
281 applicable, were passed through to customers as they were incurred. These costs consisted
282 primarily of legal services from counsel external to ComEd, as well as expert witnesses
283 and consulting charges.

284 Q. **What were the Supply-Related Administrative Costs during the Reconciliation**
285 **Period?**

286 A. In ComEd's annual formula rate update and revenue reconciliation proceedings, ICC
287 Docket Nos. 21-0367 and 22-0302, the ICC determined that a certain portion of ComEd's
288 Administrative and General ("A&G") expenses previously recovered in its Distribution
289 costs should be classified as supply-related costs.¹ Those types of expenses were originally
290 identified by the Commission as supply-related in ICC Docket No. 11-0721 and are
291 included in ComEd's Supply-Related Administrative Costs as shown in ComEd Ex. 2.01.

¹ ICC Docket Nos. 20-0393 and 21-0367 reconciled ComEd's actual delivery service costs to the revenue requirement in effect during 2020 and 2021, respectively. See *Commonwealth Edison Co.*, ICC Docket No. 21-0367, Final Order (Dec. 1, 2021) at 10, 35; *Commonwealth Edison Co.*, ICC Docket No. 22-0302, Final Order (Nov. 17, 2022) at 11, 24.

292 Q. **What were the Customer Care and Collection Agency Costs during the Reconciliation**
293 **Period?**

294 A. Customer Care Costs are expenses that are recorded in Federal Energy Regulatory
295 Commission ("FERC") Accounts 901-910. These expenses include the costs of
296 maintaining and servicing customer accounts, such as call center personnel, meter reading,
297 recordkeeping, and billing and credit activities. Collection Agency Costs are the fees that
298 ComEd pays to outside collection agencies to collect unpaid amounts from customers. The
299 portion of these expenses identified by the Commission as supply-related in ICC Docket
300 Nos. 21-0367 and 22-0302² are shown in ComEd Ex. 2.01.

301 Q. **Did ComEd allocate the administrative and operational costs other than the Energy**
302 **Acquisition Department costs between Rider PE, Rate BESH, and Rate RTOUPP for**
303 **the Reconciliation Period?**

304 A. Yes.

305 Q. **How did ComEd allocate the administrative and operational costs other than the**
306 **Energy Acquisition Department costs that you describe above between Rider PE,**
307 **Rate BESH, and Rate RTOUPP during the Reconciliation Period?**

308 A. Information Technology Systems Costs were directly charged to Rider PE and Rider
309 RTOUPP, as appropriate, as those costs were incurred. The PJM Credit Costs were
310 allocated between Rider PE, Rate BESH, and Rate RTOUPP on a monthly load-weighted
311 basis during the Reconciliation Period. The IPA Fees and ICC Procurement Monitor Costs

² See *Commonwealth Edison Co.*, ICC Docket No. 21-0367, Final Order (Dec. 1, 2021) at 10; *Commonwealth Edison Co.*, ICC Docket No. 22-0302, Final Order (Nov. 17, 2022) at 11.

312 were all directly charged to the fixed-price customers as these were costs incurred
313 procuring supply for these customers during the Reconciliation Period. The Procurement
314 Plan and Reconciliation Proceeding Costs were allocated equally to the fixed-price
315 customers, hourly-priced customers, and TOU customers. Supply-Related Administrative
316 Costs identified in ICC Docket Nos. 21-0367 and 22-0302 were allocated across ComEd's
317 seven (7) supply tariffs³ in proportion to the internal administrative and operational costs
318 for Energy Acquisition that I describe above. Finally, the Customer Care and Collection
319 Agency Costs attributable to supply in ICC Docket Nos. 21-0367 and 22-0302 were
320 allocated based on the average monthly customers served under Rider PE, Rate BESH, and
321 Rate RTOUPP.⁴

322 **III. REASONABLENESS OF THE ADMINISTRATIVE AND OPERATIONAL**
323 **COSTS**

324 Q. **Do you have an opinion about whether ComEd's internal administrative and**
325 **operational costs associated with the procurement of electric power and energy for**
326 **retail customers and served under Rider PE, Rate BESH, and Rate RTOUPP for the**
327 **Reconciliation Period, which are reflected in ComEd Ex. 2.01, were reasonable and**
328 **should be recoverable?**

329 A. Yes. I conclude that these costs, which are reflected in ComEd Ex. 2.01, were reasonable
330 and should be recoverable.

³ ComEd's seven (7) supply tariffs include Rider PE, Rate BESH, and Rider RTOUPP implicated in this Reconciliation, as well as Rider REA, Rider ZEA, Rider CFRA, and Rider CTS.

⁴ Allocation between applicable supply tariffs is based on the average monthly customers served under Rate BES (2,952,226) and Rate BESH (49,643) as provided in 2021 ILCC Form 21 Page 9, Line 21, Column (b) & Column (c). For Rate RTOUPP, the average monthly customers is approximately 1,900.

331 Q. **Why do you reach that conclusion?**

332 A. As described above, all these costs related to the operation of ComEd's Energy Acquisition
333 Department. The functions performed by the Energy Acquisition Department were all
334 necessary to procure the electric power and energy to serve Rider PE, Rate BESH, and
335 Rate RTOUPP customers. The staff that the Energy Acquisition Department employed
336 were needed to perform these procurement functions. The salaries of the staff were set on
337 a competitive basis and utilized the same salary structure that was used throughout ComEd,
338 and they were reasonable in amount. The administrative costs associated with operating
339 the department were also reasonable in amount. The manner in which ComEd charged
340 these costs between Rider PE, Rate BESH, and Rate RTOUPP was also fair and reasonable.

341 Q. **Do you have an opinion about whether the other administrative and operational costs**
342 **associated with the procurement of electric power and energy for retail customers**
343 **and served under Rider PE, Rate BESH, and Rate RTOUPP for the Reconciliation**
344 **Period, which are reflected in ComEd Ex. 2.01, were reasonable and should be**
345 **recoverable?**

346 A. Yes. I conclude that these costs, which are reflected in ComEd Ex. 2.01, were reasonable
347 and should be recoverable.

348 Q. **Why do you reach that conclusion?**

349 A. The administrative and operational costs other than the Energy Acquisition Department
350 costs that ComEd incurred to obtain products or services needed by the Energy Acquisition
351 Department to perform its procurement-related functions during the Reconciliation Period
352 that ComEd recovered from retail customers were necessary to procure the electric power

353 and energy to serve ComEd's fixed-price, hourly-priced, and TOU customers. More
354 specifically, the administrative and operational costs other than the Energy Acquisition
355 Department costs, described above, all fall within one of three categories: (1) costs incurred
356 in procuring power and energy for fixed price customers under the provisions of Rate BES
357 – Basic Electric Service ("Rate BES"), including the costs to develop, implement, and
358 comply with any relevant Procurement Plan, as described in Rider PE; (2) costs incurred
359 in procuring electric power and energy for hourly-priced customers under the provisions
360 of Rate BESH; and (3) costs incurred in procuring electric power and energy for TOU
361 customers under the provisions of Rate RTOUPP.

362 Q. **Is there any other basis for the recovery of the administrative and operational costs**
363 **associated with the procurement of electric power and energy for retail customers**
364 **and served under Rider PE, Rate BESH, and Rate RTOUPP for the Reconciliation**
365 **Period, which are reflected in ComEd Ex. 2.01?**

366 A. Yes. I am advised by ComEd's counsel that it is ComEd's legal position that the PUA and
367 ComEd's tariffs specifically provide that a utility shall recover its costs of procuring
368 electric power and energy, including the costs incurred by the utility in procuring a supply
369 of electric power and energy, any just and reasonable costs that the utility incurs in
370 arranging and providing for the supply of electric power and energy, all reasonable costs

371 incurred to implement and comply with any Procurement Plan, any fees assessed by the
372 IPA, and any costs associated with balancing load,⁵

373 **Q. How does the amount of administrative and operational costs that ComEd recovered**
374 **from customers during the Reconciliation Period compare to the amount that was**
375 **recovered in the prior period of June 1, 2021 through May 31, 2022?**

376 **A.** In the prior period (June 1, 2021, through May 31, 2022), ComEd recovered approximately
377 \$25.0 million in administrative and operational costs. In the Reconciliation Period
378 examined in this docket, the amount recovered from customers was approximately \$30.4
379 million in administrative and operational costs. Excluding the increase of approximately
380 \$5,031,900 in Customer Care and Collection Agency Costs allocated to supply in ICC
381 Docket Nos. 21-0367 and 22-0302, and a decrease of approximately \$122,812 in the
382 portion of ComEd's Administrative Costs allocated to supply in ICC Docket Nos. 21-0367
383 and 22-0302, the difference from the prior period is an increase of approximately \$250,000.
384 This \$250,000 difference is primarily due to: increases in IPA Fees and ICC Procurement
385 Monitor Costs (approximately \$214,000), PJM Credit Costs (approximately \$140,000),
386 Procurement Plan and Reconciliation Proceedings Costs (approximately \$129,000), and
387 Information Technology Systems Costs (approximately \$94,000), which were partially
388 offset by a decrease in the internal administrative and operational costs related to the
389 procurement-related functions of ComEd's Energy Acquisition Department

⁵ See Rider PE, ILL. C. C. No. 10, 2nd Revised Sheet No. 311, section on Purpose; 3rd Revised Sheet Nos. 313 and 314, section on Procurement Obligation; 4th Revised Sheet No. 317, section on Purchased Electricity Price; Rate BESH, ILL. C. C. No. 10, 10th Revised Sheet No. 36 and 4th Revised Sheet No. 37, section on Miscellaneous Procurement Components Charge; 4th Revised Sheet No. 38 and 1st Revised Sheet No. 39, section on Hourly Purchased Electricity Adjustment Factor; and 8th Revised Sheet No. 46 and 3rd Revised Sheet No. 46.1, section on Miscellaneous General Provisions.

390 (approximately \$327,000). Note that the sum of these costs may not exactly equal the total
391 due to rounding.

392 **IV. COMPLIANCE WITH THE PROCUREMENT PLAN**

393 **Q. Was ComEd in compliance with the 2022 Procurement Plan during the**
394 **Reconciliation Period?**

395 **A.** Yes. During the Reconciliation Period, ComEd complied with the 2022 Procurement Plan
396 approved by the Commission in ICC Docket No. 21-0717.

397 **Q. What were the key components of the 2022 Procurement Plan?**

398 **A.** The key components of the 2022 Procurement Plan were (1) identification of pre-existing
399 contracts for supply; and (2) the determination of the amounts and method for procuring
400 the residual requirements of energy, capacity, ancillary, and transmission services for the
401 eligible retail customers.

402 **Q. What are pre-existing contracts for supply in this context?**

403 **A.** Pre-existing contracts were contracts for energy, capacity, ancillary, or transmission
404 services that ComEd executed outside of the context of a Procurement Plan. During this
405 Reconciliation Period, there were no pre-existing contracts.

406 **Q. How did the 2022 Procurement Plan provide for the procurement of energy, capacity,**
407 **ancillary, and transmission services?**

408 **A.** The portion of the utility's load not supplied by pre-existing contracts was served pursuant
409 to the procurement of wholesale energy. To meet this requirement, the 2022 Procurement
410 Plan proposed the procurement of block energy-only products that varied monthly and by

411 on-peak and off-peak time periods. To balance the portion of the load served by existing
412 block energy products, the 2022 Procurement Plan proposed for ComEd to passively
413 procure and sell energy in the PJM administered energy markets. Similarly, the 2022
414 Procurement Plan proposed for ComEd to procure capacity, ancillary, and transmission
415 services from the relevant PJM administered markets. ICC Docket No. 21-0717.

416 Q. **How did ComEd comply with the procurement of the balancing energy, capacity,
417 ancillary, and transmission services portion of the 2022 Procurement Plan?**

418 A. ComEd acquired balancing energy, capacity, ancillary, and transmission services through
419 the relevant PJM markets. ComEd tracked that the appropriate amounts were obtained,
420 confirmed that the invoiced amounts were correct, and then processed payment for these
421 amounts.

422 Q. **Did ComEd participate in standard energy block procurement events, as
423 contemplated in the 2022 Procurement Plan?**

424 A. Yes. There were two standard energy block procurement events held for ComEd supplied
425 load in accordance with the IPA Procurement Plan, one in Spring 2022 and one in Fall
426 2022. Table 1 provides the procurement results for the procurement event from Spring
427 2022.

428

TABLE 1 – Procurement Results - Spring 2022

Spring 2022	ComEd Procured Amount		IPA Plan ⁶		Difference	
Month	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW
Jun-22	175	175	2,000	1,625	(1,825)	(1,450)
Jul-22	-	-	2,725	2,000	(2,725)	(2,000)
Aug-22	-	-	2,550	1,850	(2,550)	(1,850)
Sep-22	275	75	1,650	1,475	(1,375)	(1,400)
Oct-22	150	175	750	675	(600)	(500)
Nov-22	150	275	850	775	(700)	(500)
Dec-22	300	300	1,000	925	(700)	(625)
Jan-23	-	-	1,025	950	(1,025)	(950)
Feb-23	-	-	925	900	(925)	(900)
Mar-23	650	200	825	800	(175)	(600)
Apr-23	725	-	725	675	-	(675)
May-23	750	75	750	700	-	(625)
Jun-23	525	425	525	425	-	-
Jul-23	625	525	625	525	-	-
Aug-23	575	475	575	475	-	-
Sep-23	425	375	425	375	-	-
Oct-23	350	325	350	325	-	-
Nov-23	400	375	400	375	-	-

⁶ IPA's February 7, 2022 Final Plan with the updated load forecast provided to the IPA and ICC Staff on March 15, 2022.

Spring 2022	ComEd Procured Amount		IPA Plan ⁶		Difference	
	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW
Dec-23	475	425	475	425	-	-
Jan-24	475	450	475	450	-	-
Feb-24	450	425	450	425	-	-
Mar-24	375	375	375	375	-	-
Apr-24	325	325	325	325	-	-
May-24	350	325	350	325	-	-
Jun-24	400	350	400	350	-	-
Jul-24	550	425	550	425	-	-
Aug-24	500	375	500	375	-	-
Sep-24	325	300	325	300	-	-
Oct-24	250	200	250	200	-	-
Nov-24	275	250	275	250	-	-
Dec-24	350	325	350	325	-	-
Jan-25	375	325	375	325	-	-
Feb-25	325	300	325	300	-	-
Mar-25	275	250	275	250	-	-
Apr-25	225	200	225	200	-	-
May-25	250	200	250	200	-	-

429 Table 2 provides the procurement results for the procurement event from Fall 2022.

430 **TABLE 2 – Procurement Results – Fall 2022**

Fall 2022 Month	ComEd Procured Amount		IPA Plan ⁷		Difference	
	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW
Jun-22	-	-	-	-	-	-
Jul-22	-	-	-	-	-	-
Aug-22	-	-	-	-	-	-
Sep-22	-	-	-	-	-	-
Oct-22	1,250	1,075	1,250	1,075	-	-
Nov-22	1,425	1,150	1,425	1,150	-	-
Dec-22	1,525	1,375	1,525	1,375	-	-
Jan-23	1,900	1,725	1,900	1,725	-	-
Feb-23	1,775	1,650	1,775	1,650	-	-
Mar-23	875	650	875	1,250	-	(600)
Apr-23	600	950	600	1,250	-	(300)
May-23	625	850	625	1,175	-	(325)
Jun-23	500	400	500	400	-	-
Jul-23	600	525	600	525	-	-
Aug-23	575	500	575	500	-	-
Sep-23	400	375	400	375	-	-

⁷ IPA's February 7, 2022 Final Plan with the revised load forecast provided to the IPA and ICC Staff on July 15, 2022.

Fall 2022	ComEd Procured Amount		IPA Plan ⁷		Difference	
Month	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW
Oct-23	350	325	350	325	-	-
Nov-23	400	350	400	350	-	-
Dec-23	450	400	450	400	-	-
Jan-24	475	425	500	450	(25)	(25)
Feb-24	450	425	450	425	-	-
Mar-24	375	375	400	375	(25)	-
Apr-24	325	300	325	300	-	-
May-24	350	300	350	300	-	-
Jun-24	325	250	425	325	(100)	(75)
Jul-24	425	400	525	450	(100)	(50)
Aug-24	450	400	500	400	(50)	-
Sep-24	275	200	350	275	(75)	(75)
Oct-24	275	225	275	225	-	-
Nov-24	300	225	300	225	-	-
Dec-24	350	250	375	325	(25)	(75)
Jan-25	350	325	350	325	-	-
Feb-25	350	325	350	325	-	-
Mar-25	275	200	275	250	-	(50)
Apr-25	225	200	225	200	-	-
May-25	225	225	225	225	-	-

431 Q. Did either the Spring 2022 or the Fall 2022 procurement events fulfill the targeted
432 supply quantities for ComEd?

433 A. No, both procurement events procured only a portion of the targeted supply for ComEd as
434 demonstrated in the on-peak and off-peak columns under “Difference” in Tables 1 and 2
435 above. Since the Spring 2022 procurement event did not procure all targeted quantities, in
436 accordance with Section 16-111.5 of the IPA Act, the Procurement Administrator (National
437 Economic Research Associates (“NERA”)), the Procurement Monitor (Bates White, LLC),
438 and the ICC Staff met within 10 days of the April 18 bid day for the Spring 2022
439 procurement event to analyze the potential causes of the unfilled targets and to determine
440 whether to hold a supplemental procurement event within 90 days to target any unfilled
441 quantities. The parties determined that a supplemental procurement event would be held
442 on May 20, 2022, to target any unfilled quantities for the months of June 2022 to September
443 2022. Any unfilled quantities in months beyond September 2022 were added to
444 procurement targets for the Fall 2022 procurement event.

445 Table 3 below displays the results of the Supplemental Spring 2022 procurement
446 event which also procured only a portion of the targeted supply for ComEd. The unfilled
447 quantities for the months of June 2022 through May 2023 not procured from either the
448 Supplemental Spring 2022 or the Fall 2022 procurement events were ultimately fulfilled
449 as balancing energy purchased directly from PJM administered energy markets. The
450 remaining unfilled quantities in months beyond May 2023 from the Fall 2022 procurement
451 event were to be addressed in the procurement targets of the applicable 2023 and 2024 IPA
452 Procurement Plans.

453 **TABLE 3 – Procurement Results – Supplemental Spring 2022**

Supplemental Spring 2022 Month	ComEd Procured Amount		IPA Plan ⁸		Difference	
	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW	On Peak MW	Off Peak MW
Jun-22	1,475	1,450	1,825	1,450	(350)	-
Jul-22	1,550	1,725	2,725	2,000	(1,175)	(275)
Aug-22	1,725	1,725	2,550	1,850	(825)	(125)
Sep-22	1,375	1,400	1,375	1,400	-	-

454 Q. **What was the process during the Reconciliation Period by which ComEd made and**
455 **received payments to and from the contractual counter-parties and PJM for**
456 **purchases and sales consistent with the ICC-approved IPA Procurement Plan?**

457 A. For the contracts under which deliveries were required, ComEd confirmed delivery through
458 the PJM scheduling process at least one month prior to when energy began flowing for
459 each month of the term. ComEd acquired balancing energy, capacity, and ancillary
460 services through the relevant PJM markets. ComEd tracked that the appropriate amounts
461 were obtained, confirmed that invoiced amounts correctly reflected the prices and
462 quantities in the Commission-approved contracts, and then processed payment.

463 Q. **Does that conclude your direct testimony?**

464 A. Yes.

⁸ IPA's February 7, 2022 Final Plan with the revised load forecast provided to the IPA on April 27, 2022.



VIA OVERNIGHT DELIVERY

November 27, 2023

Ms. Stephanie Cook
Chief Clerk
Illinois Commerce Commission
527 E. Capitol Avenue
Springfield, IL 62701

Subject: Rider PE, Rate BESH and Rate RTOUPP Cost Recovery Review and Supplemental Report

Dear Ms. Cook:

Commonwealth Edison Company (ComEd) submits for filing, for informational purposes, the 2023 ComEd Rider Purchased Electricity, Rate Basic Electric Service Hourly Pricing and Rate Time of Use Pricing Pilot Review report as provided for in Rider PE – Purchased Electricity ("Rider PE"), Rate BESH – Basic Electric Service Hourly Pricing ("Rate BESH"), and Rate RTOUPP – Rate Residential Time of Use Pricing Pilot ("Rate RTOUPP") as well as a Supplemental Report Relating to the 2023 ComEd Purchased Electricity, Rate Basic Electric Service Hourly and Rate Time of Use Pricing Pilot Cost Recovery Review that provides additional information related to the proceedings required under Rider PE, Rate BESH and Rate RTOUPP.

Electronic copies of this transmittal letter and reports are being sent to Dr. James Zolnierok (Bureau Chief), Mr. Torsten Clausen (Director: Policy Division), Ms. Tanya Capellan (Director: Office of Retail Market Development), Ms. Gina Tuminello (Assistant: Office of Retail Market Development), Ms. Rebecca West (Market Associate: Office of Retail Market Development), Ms. Rochelle Phipps (Assistant Director: Financial Analysis Division) and Ms. Bonita A. Pearce (Accountant: Accounting Department).

Sincerely,

John L. Leick
Senior Manager Retail Rates
ComEd
(779) 231-2375

cc:

J. Zolnierok
T. Clausen
T. Capellan
G. Tuminello
R. Phipps
B. Pearce
R. West

2024CRDICCCEAI 0000052

VERIFICATION

Under penalties as provided by law pursuant to Section 1-109 of the Code of Civil Procedure, I certify that the statements set forth in this instrument are true and correct, except as to matters therein stated to be on information and belief and as to such matters I certify as aforesaid that I verily believe the same to be true:

1. I, Jason M. Decker, am Vice President of Regulatory Policy and Strategy for Commonwealth Edison Company. My business address is 10 S. Dearborn Street, Chicago, Illinois 60603.
2. I have read the foregoing *2023 ComEd Rider Purchased Electricity, Rate Basic Electric Service Hourly Pricing, and Rate Time of Use Pricing Pilot Review Report*, prepared by Exelon Audit Services, and am familiar with the facts stated therein.
3. The facts stated therein are true and correct to the best of my knowledge and belief.


Jason M. Decker



2023 ComEd Rider PE Purchased
Electricity, Rate BESH Basic
Electric Service Hourly Pricing,
and Rate RTOUPP Residential
Time of Use Pricing Pilot Review

November 17, 2023

Exelon Audit Services

This report is confidential and furnished solely for the information and use by Management and the Board of Directors of Exelon and its subsidiaries, and is not to be used for any other purposes.

2024CRDICC AI 0000054



AUDIT REPORT

November 17, 2023

To: Steven J. Cichocki, Director of Accounting, ComEd

Executive Summary

Exelon Audit Services (EAS) performed an audit of the controls surrounding compliance with the requirements of ComEd Rider PE (Purchased Electricity), Rate BESH (Basic Electric Service Hourly Pricing, and Rate RTOUPP (Residential Time of Use Pricing Pilot). The audit was conducted as part of the EAS 2023 risk-based audit plan, in accordance with the International Standards for the Professional Practice of Internal Auditing. The audit included a review of costs and customer billing for the rider's defined annual delivery period June 1, 2022, through May 31, 2023.

The results of the audit indicate that the process and general control environment for compliance with the requirements and provisions of Rider PE, Rate BESH, and Rate RTOUPP for the delivery period of June 1, 2022, through May 31, 2023, as defined in the scope section of this report, are **Effective**. No findings were identified.

EAS appreciates the assistance of ComEd Regulatory, Retail Rates, Energy Acquisition and Accounting personnel in the completion of this review.

Savana Latimore, Manager, EAS

CC:

David Glockner
David M Diaz
Cheryl Crumpton
Robert Aiken
Lewis Binswanger
Jason Decker
Emma Salustro
Ben Levinsky
Brad Perkins
John Leick
Heather Hopkins
Molly Charles

Michael Tonkovic
Albert (AJ) Griffith
Marzena Walker
Christopher Roberts
Matthew Weaver
Karen Klein
Dan Brotzman
Jennifer Everett
Karen Hotem
Janice Suphakan



AUDIT REPORT

Background

The purpose of Rider PE (Purchased Electricity) is to allow ComEd to recover the costs related to procuring power and energy that are incurred pursuant to the ICC-approved procurement plan through a formula rate or charge with no mark-up or return on the price paid by ComEd for the supply, plus any reasonable costs ComEd incurred in arranging and providing for the supply of electric power and energy pursuant to Section 16-111.5 of Public Utilities Act (Act) and pursuant to Section 1-75 of the Illinois Power Agency Act. The Purchased Electricity Adjustment (PEA) Factor is a unit credit or charge that periodically equalizes applicable revenues from retail customers taking service under Rate BES (Basic Electric Service) and expenses incurred by ComEd in the procurement of electric power and energy, ensuring that ComEd does not over or under recover its costs related to procurement of electric power and energy for its retail customers "due to changes in customer usage and demand patterns". ILL. C. C. No. 10, 1st Revised Sheet No. 312.

Rate BESH (Basic Electric Service Hourly) is a tariff applicable to retail customers to which ComEd provides bundled electric service and to which the Competitively Declared Customer Group applies (i.e., those retail customer determined to have electric power and energy requirements of at least 100 kW). The Hourly Purchased Electricity Adjustment (HPEA) Factor is applied to these customers. HPEA is a unit credit or charge that periodically equalizes applicable revenues and expenses incurred by ComEd in the procurement of electric power and energy, ensuring that ComEd does not over or under recover costs related to the procurement of electric power and energy for its retail customers.

Rate RTOUPP (Residential Time of Use Pricing Pilot) is a tariff applicable to a limited number of retail customers who meet the criteria identified in Rate RTOUPP (ILL. C. C. No. 10, 8th Revised Sheet No. 27). The purpose of the Rate RTOUPP tariff is to determine if an elective time of use residential rate option provides retail customers with a supply rate option that (a) encourages less electricity usage, or a shift in usage, from periods when electricity prices are typically higher, (b) encourages less electricity during peak demands, (c) encourages electric vehicle owners to charge their vehicles in the early morning when prices are typically lower, and (d) increases customers' satisfaction with a new supply rate option. The RTOU Purchased Electricity Adjustment (RTOU PEA) Factor periodically equalizes the revenues from retail customers receiving electric service for electric power and energy procured for them by ComEd and the expenses incurred by ComEd related to the procurement of such electric power and energy as provided in the Monthly Charges section of the tariff.

Rider PE, Rate BESH and Rate RTOUPP requires ComEd to provide an annual audit of costs and recoveries for the previous PJM Planning Year to the Illinois Commerce Commission (ICC). The audit report must be submitted with sixty (60) calendar days after the end of the effective period associated with the May determination period of such PJM Planning Year. As such, the report must be issued by November 30. Additionally, ComEd submits monthly informational filings due by the 20th of every month for all three related



AUDIT REPORT

adjustment factors: PEA, HPEA and RTOU PEA. Therefore, due to the related adjustment factors, timing of reporting, and efficiency, this Audit is performed as one review.

Areas in Scope

The following areas were specifically included in the scope of our review, as required by Rider PE, Rate BESH, and Rate RTOUPP:

- Costs recovered pursuant to Rider PE, Rate BESH, and Rate RTOUPP to verify that such costs are recovered only pursuant to this/these rider/tariffs and to confirm that any such costs are not also being recovered inappropriately through charges imposed under other riders/tariffs;
- Charges and adjustments determined pursuant to Rider PE, Rate BESH, and Rate RTOUPP that are included in retail customers' bills for electric service and provided in the rider/tariffs to verify that such charges and adjustments are properly applied;
- Revenues resulting from the application of Rider PE, Rate BESH, and Rate RTOUPP to verify that such revenues are correctly stated;
- Internal administrative and operational costs associated with the procurement of electric power and energy for retail customers served hereunder Rider PE, Rate BESH, and Rate RTOUPP to verify that such costs are reasonable;
- ComEd's costs of implementing or complying with the procurement plan approved by the ICC, including any fees assessed by the IPA, costs associated with load balancing, and contingency plan costs for Rider PE; and
- ComEd's costs of working capital associated with expenditures for electric power and energy supply to ensure such costs were determined in a manner consistent with the methodology used to determine costs of working capital approved by the ICC in its order in the then most recent rate or Rate Delivery Service Pricing and Performance (DSPP) annual update case, or as otherwise provided by law, as applicable, using the cost of capital established by the ICC in its order in such most recent case or as otherwise provided by law, as applicable.

EAS also considered the design and operating effectiveness of the following Key Financial Controls (KFCs) and relied on the testing performed as part of the 2022 Sarbanes Oxley compliance procedures specific to these controls:

- **E.REG.02.01 Regulatory Matters Review** – On a quarterly basis prior to the quarter-end financial close, Accounting meets with key stakeholders to discuss regulatory matters that could have accounting implications, including various inputs included in the formula rate true-up calculations. If the key stakeholders indicate that certain regulatory matters may change/occur after the quarterly meeting, Accounting will follow-up with the key stakeholders to ensure that any necessary adjustments are recorded for the quarter-end financial close. Key stakeholders include: Regulatory, Financial Planning & Analysis, Tax, External Financial Reporting, Legal, and Energy Acquisition.



AUDIT REPORT

- **E.REG.02.02 Conformance Memo** - When a new material regulatory asset/regulatory liability (RA/RL) is required to be accounted for per the guidelines in ASC 980, the control performer prepares an accounting conformance memo documenting the new RA/RL and the conclusions to support the creation of the new RA/RL. When revisions to existing tariffs are filed with the ICC, and such revisions result in accounting or reporting changes, the control performer prepares a memo documenting any accounting or reporting changes. Approval is denoted via sign-off on the conformance memo. Additionally, the Regulatory organization reviews all conformance memos to ensure consistency with regulatory orders/tariffs.
- **E.REG.02.12 Rider/Tracker Mechanisms Neutralization Review** – On a monthly basis, the Accounting Senior Manager (or above) reviews the over/under recovery calculation for material tracker mechanisms for accuracy and reasonableness.
- **E.REG.03.05 Tariff Calculation and Review** – After Retail Rates personnel develop retail tariffs or update existing tariffs, peer reviews are performed to verify accuracy of the calculation and signify approval. This process involves verifying use of correct input data and correct application of spreadsheet formula. This process is referred to as "Referencing."
- **E.REG.03.11 Rate/Rider Recalculation** – Customer Projects recalculates bills for rate classes/riders using actual monthly usage from production to determine accuracy of system generated bills. Discrepancies are investigated/resolved. Customer Projects Lead reviews a sample of recalculations to determine effectiveness.

Results

Based on testing performed by EAS, no audit findings were noted. As such, there are no management action plans required as a result of this audit.



Supplemental Report Relating to the
2023 ComEd Rider Purchased Electricity,
Rate Basic Electric Service Hourly and
Rate Time of Use Pricing Pilot
Cost Recovery Review

November 27, 2023

COMMONWEALTH EDISON COMPANY

INTRODUCTION

The Supplemental Report Relating to the 2023 ComEd Rider Purchased Electricity, Rate Basic Electric Service Hourly and Rate Time of Use Pricing Pilot Cost Recovery Review (Supplemental Report) is submitted by Commonwealth Edison Company (ComEd) to the Illinois Commerce Commission (ICC) as a voluntary supplemental informational filing. This Supplemental Report serves three purposes:

- This Supplemental Report provides additional information relating to the subject matter of the internal audit report entitled "2023 ComEd Rider PE Purchased Electricity, Rate BESH Basic Electric Service Hourly Pricing, and Rate RTOUPP Residential Time of Use Pricing Pilot Review" (EAS Report) dated November 17,

2024CRDICCCEAI 0000059

2023, that has been prepared by Exelon Audit Services (EAS) and that is being submitted simultaneously herewith by ComEd to the ICC as a required informational filing under provisions of three ComEd tariffs approved by the ICC, *i.e.*, Rider PE – Purchased Electricity, 2nd Revised Sheet No. 311, *et seq.*, Ill. C. C. No. 10 (Rider PE); Rate BESH – Basic Electric Service Hourly Pricing, 3rd Revised Sheet No. 29, *et seq.*, Ill. C. C. No. 10 (Rate BESH); and Rate RTOUPP – Residential Time of Use Pricing Pilot, 8th Revised Sheet No. 27, *et seq.*, Ill. C. C. No. 10 (Rate RTOUPP).

- This Supplemental Report summarizes the monthly process that ComEd followed in order to implement the applicable provisions of those tariffs and includes a schedule showing cumulative totals of incremental expenses, revenues, and recoveries associated with Rider PE, Rate BESH, and Rate RTOUPP relating to the period June 1, 2022, through May 31, 2023 (referred to below as the “current audit period” or the “current reconciliation period”), as explained further below.
- This Supplemental Report provides information regarding ComEd’s understanding of, and recommendations relating to, the appropriate scope and nature of the related ICC proceedings provided for in those three tariffs.

LEGAL AND STATUTORY REQUIREMENTS

Legal Authority

Section 16-111.5 of the Illinois Public Utilities Act (Act), 220 ILCS 5/16-111.5, entitled “Provisions relating to procurement”, sets forth a number of provisions relating to the procurement of electric power and energy and the recovery of the costs of that procurement. Section 16-111.5(l) states in part:

The tariffs [providing for the recovery of costs of procuring electric power and energy under Section 16-111.5] shall include a formula rate or charge designed to pass through both the costs incurred by the utility in procuring a supply of electric power and energy for the applicable customer classes with no mark-up or return on the price paid by the utility for that supply, plus any just and reasonable costs that the utility incurs in arranging and providing for the supply of electric power and energy. The formula rate or charge shall also contain provisions that ensure that its application does not result in over or under recovery due to changes in customer usage and demand patterns, and that provide for the correction, on at least an annual basis, of any accounting errors that may occur. **** All such costs shall be deemed to have been prudently incurred. ****

(emphasis added.)

Rider PE – Scope of Proceeding

In accordance with Section 16-111.5(l) of the Act, 3rd Revised Sheet No. 329 of Rider PE provides for an ICC proceeding relating to the Purchased Electricity Adjustments (PEAs) as to the current reconciliation period stating in part as follows:

Each year no earlier than ninety (90) calendar days after the end of the effective period associated with the May determination period of such year, a proceeding must commence in accordance with Section 16-111.5(l) of the Act to "provide for the correction, on at least an annual basis, of any accounting errors that may occur" in the application of the provisions of this rider.

(Emphasis added.) The Act does not provide for review of the prudence of the PEAs.

However, unlike with the PEAs, the tariff (also on 3rd Revised Sheet No. 329) permits the ICC, if it wishes, to review the reasonableness of ComEd's applicable internal administrative and operational costs stating in part as follows:

Such proceeding may also provide for the determination of the reasonableness of the Company's internal administrative and operational costs associated with the procurement of electric power and energy pursuant to Section 16-111.5 of the Act and other costs of implementing or complying with the procurement plan approved by the ICC to the extent that they are properly reviewable in such proceeding pursuant to Section 16-111.5(l) of the Act.

Rate BESH – Scope of Proceeding

Similarly, although the language is not identical, 7th Revised Sheet No. 46 of Rate BESH provides for an ICC proceeding relating to the Hourly Purchased Electricity Adjustments (HPEAs) as to the current reconciliation period stating in part as follows:

Each year beginning in 2009, no earlier than ninety (90) calendar days after the end of the effective period associated with the May determination period of a PJM Planning Year, a proceeding must commence to provide for the correction of any errors that may have occurred in the application of the provisions of this tariff.

The Act does not provide for review of the prudence of the HPEAs.

Again however, unlike with the HPEAs, the tariff (also on 7th Revised Sheet No. 46) permits the ICC, if it wishes, to review the reasonableness of ComEd's applicable internal administrative and operational costs stating in part as follows:

Any such proceeding may also provide for the determination of the reasonableness of the Company's internal administrative and operational costs associated with the procurement of electric power and energy for retail customers served hereunder.

Rate RTOUPP – Scope of Proceeding

Similarly, although the language is not identical, 1st Revised Sheet No. 28.16 of Rate RTOUPP provides for an ICC proceeding relating to the Residential Time of Use (RTOU) Purchased Electricity Adjustment (PEA) as to the current reconciliation period stating in part as follows:

Each year beginning in 2021, if sufficient data exists, no earlier than ninety (90) calendar days after the end of the effective period associated with the May determination period of a PJM Planning Year and concurrent with the annual reconciliation filings for Rate BESH and Rider PE, a proceeding must commence to provide for the correction of any errors that may have occurred in the application of the provisions of this tariff.

The Act does not provide for review of the prudence of the RTOU PEAs.

Again however, unlike with the RTOU PEAs, the tariff (also on 1st Revised Sheet No. 28.16) permits the ICC, if it wishes, to review the reasonableness of ComEd's applicable internal administrative and operational costs stating in part as follows:

Any such proceeding may also provide for the determination of the reasonableness of the Company's internal administrative and operational costs associated with the procurement of electric power and energy for retail customers served hereunder.

Internal Audit – Scope of Proceedings

The 2023 ComEd Rider Purchased Electricity, Rate Basic Electric Service Hourly Pricing, and Rate Residential Time of Use Pricing Pilot Review, prepared by EAS, (EAS Report) as described further therein, relates to three sets of charges/credits: (1) PEAs charged/credited to applicable customers under Rider PE; (2) HPEAs charged/credited to applicable customers under Rate BESH; (3) RTOU PEAs charged/credited to applicable customers under Rate RTOUPP for service provided from June 1, 2022, through May 31, 2023.

PEAs under Rider PE were designed and applied to service provided in the current reconciliation period to ensure that ComEd neither over nor under recovered its costs of procuring full requirements electric supply for retail customers for whom it procures such supply. (See 1st Revised Sheet No. 324 of Rider PE).

The 3rd Revised Sheet No. 329 of Rider PE, as specified in further detail therein, required that ComEd conduct and submit to the ICC a report on an internal audit relating to the PEAs for the current reconciliation period. That tariff sheet lists six areas of inquiry.

Similarly, HPEAs under Rate BESH were designed and applied to service provided in the current reconciliation period to ensure that ComEd neither over nor under recovered its costs of procuring full requirements electric supply for retail customers for whom it procures such supply. See 3rd Revised Sheet No. 37 of Rate BESH.

The 7th Revised Sheet No. 45 of Rate BESH, as specified in further detail therein, required that ComEd conduct and submit to the ICC a report on an internal audit relating to the HPEAs for the current reconciliation period. That tariff sheet lists five areas of inquiry.

The RTOU PEAs under Rate RTOUPP were designed and applied to service provided in the current reconciliation period to ensure that ComEd neither over nor under recovered its costs of procuring full requirements electric supply for retail customers for whom it procures such supply. See 1st Revised Sheet No. 28.9 of Rate RTOUPP.

The 1st Revised Sheet No. 28.15 of Rate RTOUPP, as specified in further detail therein, required that ComEd conduct and submit to the ICC a report on an internal audit relating to the RTOU PEAs for the current reconciliation period. That tariff sheet lists five areas of inquiry.

ComEd's Accounting function developed and implemented processes for the calculation and application of PEAs, HPEAs and RTOU PEAs for the current reconciliation period. The processes were tested and then put into effect, and they have been reviewed over time.

The EAS Report, as set forth in more detail therein, reports on EAS' independent review of ComEd's PEAs, HPEAs and RTOU PEAs and the underlying processes. In accordance with the three tariffs, the EAS Report is being submitted with verification from an officer of ComEd, Jason Decker, ComEd Vice President of Regulatory Policy, and Strategy.

Summary of Recommended Proceedings

ComEd understands and agrees that the ICC is required to open proceedings, preferably consolidated proceedings, for Rider PE, Rate BESH, and Rate RTOUPP regarding whether there were any accounting errors in the calculation and application of the PEAs, the HPEAs and RTOU PEAs as to the current reconciliation period. ComEd also understands and agrees that the ICC is not required, but may, under the three tariffs, include in such proceedings a review of the reasonableness of ComEd's applicable internal administrative and operational costs. ComEd also believes that the proceedings

should be conducted in an efficient manner that does not result in unnecessary burdens on the ICC, Staff, ComEd or any other person or entity.

ComEd respectfully submits that the submission of the verified EAS Report, standing alone, appropriately, and reasonably supports ICC findings that the PEAs, HPEAs and RTOU PEAs as to the current reconciliation period did not incorporate or reflect any accounting errors and, if the ICC wishes to address the subject, that ComEd's applicable internal administrative and operational costs were reasonable. ComEd understands that the ICC's Staff may wish to serve appropriate discovery or conduct other appropriate inquiry of ComEd to verify whether the PEAs, HPEAs and RTOU PEAs as to the current reconciliation period suffered from any accounting errors. ComEd welcomes the review with full cooperation.

ComEd believes that the above recommendations as to the scope of the proceedings are consistent with the ICC Orders Commencing Reconciliation Proceedings in ICC Docket No. 10-0275 (April 7, 2010), ICC Docket No. 11-0357 (April 15, 2011), ICC Docket No. 12-0549 (October 3, 2012), ICC Docket No. 13-0528 (September 18, 2013), ICC Docket No. 14-0569 (September 18, 2014), ICC Docket No. 15-0535 (September 22, 2015), ICC Docket No. 16-0455 (September 28, 2016), ICC Docket No. 17-0396 (September 27, 2017), ICC Docket Nos. 18-1539 and 19-0031 (cons) (September 24, 2018), ICC Docket No. 20-0133 (February 5, 2020), ICC Docket No. 21-0094 (February 4, 2021), and ICC Docket No. 22-0104 (February 3, 2022).

THE INTERNAL AUDIT REPORT

The EAS Report (on page 3, *et seq.*) reflects the areas of inquiry provided for in the three tariffs on 3rd Revised Sheet No. 329, 7th Revised Sheet No. 45, and 1st Revised Sheet No. 28.15.

In brief, the EAS Report provides independent confirmation of the correctness of the PEAs, HPEAs and RTOU PEAs applied as to the current reconciliation period. It should be noted that the EAS procedures employed in conducting the analysis summarized in the EAS Report include comparing non-general ledger data and computations based therein with general ledger data and computations based thereon. ComEd's general ledger is its official books and records.

It should be noted that EAS' review included review of the reasonableness of ComEd's applicable internal administrative and operational costs, as indicated on page 4 of the EAS Report.

OPERATION OF THE TARIFFS

ComEd notes that it has submitted monthly informational filings to the ICC regarding the activity in its PEAs, HPEAs and RTOU PEAs for the duration of the current reconciliation period. Those monthly filings demonstrate how the tariffs have been implemented.

Included as Appendix I to this Supplemental Report is a summary schedule showing cumulative totals of incremental expenses, revenues and recoveries associated with Rider PE, Rate BESH, and Rate RTOUPP as to the period June 1, 2022, through May 31, 2023.

As noted in Appendix I, as of May 31, 2023, ComEd had total accrued expenses of \$3,013,944,826; total accrued revenues of \$3,025,874,336; total recoveries of \$37,205,588 and total interest of (\$2,653). These totals are separated into Fixed, Hourly, and Time of Use segments in Appendix I. The result is a regulatory asset on ComEd's general ledger of \$9,721,601 as of May 31, 2023.

APPENDIX I

COMMONWEALTH EDISON COMPANY

Rider PE, Rate BESH, and Rate RTOUPP
Cumulative Totals of Incremental Expenses, Revenues, and Recoveries
June 1, 2022, Through May 31, 2023

Line No.		Flood Rider PE	Hourly Rate BESH	Time of Use Rate RTOUPP	Total
1	Total Reg Asset (Liability) – May 31, 2022 (A)	\$ 51,327,188	\$ 7,469,775	\$ 62,389	\$ 58,859,352
2	Adjustment to Customer Care and Collections Agency Costs (B)	14,445	(30,412)	15,967	-
3	Total Revised Reg Asset (Liability) – May 31, 2022 (line 1 plus line 2) (C)	\$ 51,341,633	\$ 7,439,363	\$ 78,356	\$ 58,859,352
4	Accrued Expenses	2,666,270,071	346,205,030	1,469,725	3,013,944,826
5	Accrued Revenues	2,668,554,904	355,763,979	1,555,453	3,025,874,336
6	Net (Over) Under Recovery (line 4 minus line 5)	\$ (2,284,833)	\$ (9,558,949)	\$ (85,728)	\$ (11,929,510)
7	Regulatory Asset (Liability) (line 3 plus line 6)	49,056,800	(2,119,586)	(7,372)	46,929,842
8	Recoveries (Refunds)	28,365,967	8,816,224	23,397	37,205,588
9	Interest	70,796	(73,220)	(229)	(2,653)
10	Total Reg. Asset (Liability) – May 31, 2023 (line 7 minus line 8 plus line 9) (D)	\$ 29,761,629	\$ (11,099,030)	\$ (30,998)	\$ 9,721,601

Notes:

(A) Agrees to ComEd Ex. 1.01 of ComEd's Direct Testimony in ICC Docket 23-0064 for the June 1, 2021 through May 31, 2022 determination period filed with the ICC on November 16, 2022.

(B) Includes Adjustment to Customer Care and Collection Agency Costs in ComEd Ex. 1.02 of ComEd's Direct Testimony ICC Docket 23-0064 for period June 1, 2021 thru May 31, 2022.

Customer Care and Collection Agency Costs Per 2022 ComEd Supplemental Report	\$	22,597,327	\$	365,507	\$	-	\$	22,962,834
Updated Customer Care and Collection Agency Costs	\$	22,611,772	\$	335,095	\$	15,967	\$	22,962,834
	\$	14,445	\$	(30,412)	\$	15,967	\$	-

(C) Agrees to ComEd Ex. 1.02 of ComEd's Direct Testimony ICC Docket 23-0064 June 1, 2021 through May 31, 2022 determination period filed with the ICC on July 18, 2023.

(D) The reconciliation period under ICC Docket No. 23-0064 (June 2021-May 2022) is open and any adjustments resulting from this proceeding may impact the regulatory asset/(liability) balances included in this annual report.

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.11:

In Docket 24-0378 ComEd asserted that shared distribution lines (over 4kV) and secondary voltage distribution lines are used to provide delivery service and to not implicate supply services. (ComEd Ex. 5.0,30.) Please explain why these lines do not imply supply services being used.

RESPONSE:

Shared distribution lines (over 4kV) and secondary voltage distribution lines are part of ComEd's distribution system providing Delivery services to customers and remain unchanged if they serve 100% of ComEd-supplied customers or 100% of RES-supplied customers and consequently should remain in Delivery rates because they have no sensitivity to customer Supply switching. Furthermore, these facilities and services are not provided by RESs and therefore do not represent a duplicative cost that is provided by both RESs and ComEd.

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.12:

Referring to the Final Order in Docket 24-0378, ComEd argued that ICEA/RESA's proposal would constitute rate shock for some ComEd customers, which is estimated at 2.55 cents/kWh for single family without electric space heating Rate BES customers and 19.77 cents/kWh for BESH customers. (ComEd Ex. 5.0, 32.) Please supply the analysis to support these calculations.

RESPONSE:

See the attachment labeled as RML 1.12_Attach 1 for the workpaper that computes the referenced amounts and was previously provided in ICC Docket No. 24-0378 as "Leick WP 16 - ICEA RESA Cents per kWh Impact.xlsx" as the supporting workpaper for Leick Reb., ComEd Ex. 5.0.

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 108 of 580

[illegible]

2024CRDICC AI 0000070

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025

REQUEST NO. RML 1.13:

In Docket 24-0378, REACTs advocated for a tracking proposal (Ex. 6.0, 23-24.) Please explain:

- a) How ComEd could track customer calls.
- b) Would tracking increase costs? If so, by approximately how much would costs increase?
- c) Would tracking help ComEd allocate costs better?
- d) Provide any supporting data and analysis used to answer questions above.

RESPONSE:

- a) ComEd could identify the customer as a ComEd supplied electric customer or a Retail Electric Supplied customer based upon their account number. This is not something asked today in the ComEd Interactive Virtual Assistant (IVA). While this data point may identify where the customer procures it's Supply, it will not provide any insight why the customer is calling. Another method might be for ComEd to update the IVA platform to include a question where the customer would need to identify if the reason for their call is Supply or Delivery service related. We feel this option would only confuse most customers who many not understand the difference between Distribution and Supply, and wouldn't likely produce reliable results. Ultimately, it may end up driving more call volume to our agents for an explanation on the questioning if their call is related to Supply or Delivery and increase average call handling time. Finally, as explained in Ron Donovan's Surrebuttal Testimony in ICC Docket 14-0312 (ComEd Ex. 29.0, p 9-10, Lns 197-232), shifting the categorizing and tracking to the customer service representatives has challenges, including spending more time on calls to determine a subjective designation and categorizing multi-purpose calls that may span multiple Supply and Delivery topics.
- b) Yes. All of these approaches mentioned in subpart (a) would require changes to IT infrastructure, programming, and configuration and CSR training, which would increase costs. For example, the IVA platform that customers call into would need to be updated with the specific question if their reason for calling was related to a Supply or Delivery issue. However, without knowing exactly what changes are required, it is not possible to calculate the cost of any changes.
- c) See subpart (a). While costs could be better allocated between Supply and Delivery functions to the extent a customer called purely about Supply or Delivery and the purpose of the call is correctly identified and categorized, calls are not necessarily only about a Supply or Delivery issue, and determining the purpose of a call may be subjective.
- d) ComEd has not performed a specific analysis or calculated the potential costs for the tracking described.

2024CRDICCCEAI 0000071

ICC Information Request
Re: Docket No. 24-0378 Commonwealth Edison Company, Final Order
Customer Care Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Commerce Commission ("STAFF") Data Requests
RML 1.01 - RML 1.13
Date Received: March 11, 2025
Date Served: April 11, 2025
Date Supplemental Response Served: May 20, 2025

REQUEST NO. RML 1.02:

Staff understands the genesis of the current analysis utilized by ComEd referenced in RML 1.01 was a response to the shortfalls identified utilizing the switching or allocation studies. Please confirm Staff's understanding is correct and:

- a) Provide an updated switching and alternative analysis for comparison purposes to the current model being used.
- b) Identify and discuss the relative strengths and weaknesses that may be found in the CCSA, switching study and the allocation study, and their underlying mechanics and/or calculations as used for allocation of Customer Care Costs.
- c) Explain whether ComEd has considered other methods to allocate billing calculation costs that may have been more relevant than either the CCSA, switching study or the allocation study and describe those methods.

SUPPLEMENTAL RESPONSE:

In ICC Docket No. 10-0467 and ICC Docket No. 14-0314, ComEd completed and filed the initial switching study ("2010 Switching Study") and updated switching study ("2014 Switching Study"). The 2010 and 2014 Switching Studies are designed to determine if customer care costs are sensitive to customers switching to Retail Electric Supplier ("RES") supply and whether some of these costs are inherently related to delivery service that is provided to **all** customers or supply service that is provided to only bundled service customers or RES supplied service. ComEd's 2010 and 2014 Switching Studies used the same methodology to examine whether customer care costs are sensitive to customers switching from ComEd supply to a RES supply.

ComEd understands this request to be asking for an update of that analysis. Please see RML 1.02_Attach 01, which provides the 2025 Switching Study. The 2025 Switching Study provides the requested update to the 2014 Switching Study and uses the same methodology as the 2010 and 2014 Switching Studies.

In addition, ComEd understands the request to seek an “alternative analysis.” Using the same methodology for the Alternative Study introduced in 2014, given that the 2025 Switching Study shows that there are no areas in which a decrease would result from more customers switching from ComEd supply to a RES, there was no basis for an Alternative Study to allocate costs to supply.

RESPONSE:

As a general response to the question and statement that “Staff understands the genesis of the current analysis utilized by ComEd in RML 1.01 was a response to the shortfalls identified utilizing the switching or allocation studies,” it is ComEd’s position that the Switching Study presented in ICC Docket No. 10-0467 and ICC Docket No. 14-0312 is the best tool to assess whether a certain level of Customer Care Costs change due to customers switching suppliers, however, the Commission did not adopt the Switching Study and adopted a hybrid Alternative Study. Moving Delivery costs to Supply should receive careful consideration related to why costs should be allocated and how much cost, and the Commission adopted an approach they found to be reasonable and the fairest to ComEd and RES Supply customers.

- a) Updating the switching study will require coordination with multiple departments. ComEd will provide a supplemental response to this data request, including an updated Switching Study and alternative analysis, by early May 2025.
- b) The Customer Care Cost Allocation Study or CCSA is a hybrid of the Switching and Allocation studies and looks at the specific Customer Care Costs that were identified as sensitive to changes in the level of customer switching, which were the Customer Care Costs, and quantifies the portion of costs to be allocated to ComEd’s Supply function using the total embedded costs for the Customer Care Center as the pool of costs to be allocated. The underlying mechanics for the CCSA were included in ICC Docket No. 24-0478, Leick Reb., ComEd Ex. 5.0 at 35:662 - 43:789. The exhibit and description can be found in the attachment labeled as RML 1.01_Attach 1.

A strength of the CCSA is that it limits the allocation to an area of cost that has been shown to actually be impacted based on the Switching Study - the Customer Care Center. While ideally, an actual avoided cost amount would be used to allocate amounts to Supply, the calculation for the allocation used in the CCSA, based off of granular contact center information and appropriate allocation factors produce an acceptable amount to allocate to Supply.

The Switching Study examines whether the customer service costs are sensitive to customers switching from ComEd Supply to RES Supply to determine what costs, if any, are directly related to ComEd’s Delivery service. This approach is designed to show what ComEd costs, if any, would be eliminated or increased at different switching levels. The underlying mechanics for the Switching Study were described in ICC Docket No. 14-0312, Donovan Dir., ComEd Ex. 7.0, p 39-44. The study results were included as

ComEd Ex. 7.05 in Docket 14-0312, which is provided in the attachment labeled as RML 1.02_Attach 1. A strength of the Switching Study is that it determines how Customer Care Costs would *actually* change, due to customers switching suppliers. The Switching Study also recognizes that ComEd is the default provider that must stand ready to serve customers that have chosen to receive Supply service from a RES.

The Allocation Study seeks to determine what portion of Customer Care Costs are related to Delivery service and what portion is related to Supply service by applying allocation factors that are developed to approximate the relative contribution of each service function to the costs in question. The underlying mechanics for the Allocation Study were described in ICC Docket 14-0312, Donovan Dir., ComEd Ex. 7.0, p 40-43. The study results were included as ComEd Ex. 7.04 in Docket 14-0312, which is provided in the attachment labeled as RML 1.02_Attach 2. A weakness of the Allocation Study is that it assumes that all of ComEd's customer service costs are variable in nature. It also assumes that some Customer Care Costs across the board are attributable to Delivery service and some are not. Also, while the Allocation Study apportions a certain percentage of customer care costs to the ComEd Supply function, there is no corresponding allocation of costs from the Delivery function to a RES Supply function for those customer care activities that ComEd undertakes, which are related to electric supply provided by RESs. In the event that ComEd's Customer Care Costs are not considered to be common costs that ComEd incurs on behalf of all its approximately 4.1 million (meter) customers, and are instead allocated on the basis of an assumption that some Customer Care Costs are associated just with customers receiving electric supply service from ComEd, then it is reasonable to assume that some Customer Care Costs are associated with just customers receiving electric supply service from RESs.

- c) ComEd understands this subpart to be asking if ComEd evaluated including other costs that may not be included in the Customer Care Costs that are currently being allocated in the CCSA.

No, ComEd has not considered including other costs outside of the Customer Care Costs since the Commission provided directives on the methodology.

Leading up to the Commission's directive for the change in allocating Customer Care Costs to Supply in ICC Docket 14-0312, consistent with the statute, the Commission approved ComEd's allocation of Delivery-related expenses to Delivery rates in ComEd's first post-Restructuring Act rate case addressing Delivery service charges for all customers, which assigned customer care costs to the Delivery service revenue requirement. See *Commonwealth Edison Co.*, ICC Docket No. 01-0423 (Interim Order April 1, 2002) at 62-63; *Commonwealth Edison Co.*, ICC Docket No. 01-0423 (final Order March 28, 2003) at 71-72. Since that time and in subsequent proceedings including ICC Docket 05-0597, ICC Docket 07-0528/07-0531 (cons.), ICC Docket 07-0566, ICC Docket 08-0532, ICC Docket 10-0467, ICC Docket 14-0312 and ICC Docket 24-0387, additional costs for allocation have been proposed and discussed in those dockets, however, there was no Commission order to expand the scope of the costs.

In the Final Order of ICC Docket 10-0487, the Commission stated: "The Commission concludes, based upon the evidence presented, that ComEd analyzed the correct pool of costs in the "Switching Study," except, as is provided herein regarding "Direct O&M Costs v. Total Costs," which is set forth directly below." Subsequently, ComEd did include the indirect costs.

2025 Switching Study

May 2025

I. OVERVIEW

This 2025 Switching Study (or “Study”) is being provided in response to a request from the Staff of the Illinois Commerce Commission (“Commission” or “ICC”).

In ICC Docket No. 10-0467 and ICC Docket No. 14-0314, ComEd completed and filed the initial switching study (“2010 Switching Study”) and updated switching study (“2014 Switching Study”). The switching studies are designed to determine which, if any, customer care (“Customer Care”) costs are sensitive to customers switching to Retail Electric Supplier (“RES”) supply and whether some of these costs are inherently related to delivery service that is provided to all customers or supply service that is provided to only bundled service customers or RES supplied service. ComEd’s 2010 and 2014 Switching Studies used the same methodology to examine whether Customer Care costs are sensitive to customers switching from ComEd supply to a RES supply.

ComEd reviewed costs as of December 31, 2024 for the 2025 Switching Study. The 2025 Switching Study uses the same methodology as the 2010 and 2014 Switching Studies. The current switching level from ComEd supply to RES supply is 23%. To develop the 2025 Switching Study, ComEd examined two scenarios, in which the switching levels were set at 1% and 100% of ComEd customers taking RES supply. Personnel from the thirteen ComEd departments reviewed their activities to determine what ComEd costs, if any, would decrease or increase, in the two different scenarios. Although switching levels of 1% or 100% are not occurring now, and are not expected to occur in the near future, analyzing the impact on Customer Care costs at these extreme switching levels illustrates the potential longer-term impacts of both cost increases and decreases related to customer switching.

The 2025 Switching Study determined that ComEd’s Customer Care costs do not generally change based on the levels of customers receiving supply service from ComEd. In 2024, ComEd incurred \$239 million of Customer Care costs. In the 1% scenario (i.e., 1% of ComEd customers switch to a RES) costs in the Billing, Electric Supplier Services and Green Power Connection departments would be impacted and would *decrease* by an estimated \$2.3 million, \$0.8 million, and \$0.1 million, respectively (which in total is approximately 1% of the 2024 total costs). In the 100% scenario (i.e., all ComEd customers switch to a RES), the costs in those same departments would be impacted and would *increase* by an estimated \$7.3 million, \$1.7 million, and \$1 million, respectively (which in total is approximately 4% of the 2024 total costs). In other words, ComEd Customer Care costs are generally steady and do not vary much based on the levels of customers receiving supply service from ComEd. Furthermore, costs for three departments would actually *increase* as customers switch to a RES, which would support costs being allocated to RES supply.

Table 1 below summarizes the results of the 2025 Switching Study.

Table 1: Summary of 2025 Switching Study Results

Customer Switching Study/Impact on Costs For the Year Ending December 31, 2024				
Commonwealth Edison Company				
Switching Study Results				
Line No.	Department / Activity (a)	Costs at current switching level of 23% (b)	(Decreased)/Incr eased Costs at 1% Switching (c)	(Decreased)/Incr eased Costs at 100% Switching (d)
1	Metering Services (1)	\$ 16,223,048	\$ -	\$ -
2	Advertising (1)	-		
3	Subtotal for costs solely related to Delivery Service	16,223,048		
4	Field and Meter Services	10,547,557	-	-
5	Billing	15,593,531	(2,253,624)	7,282,140
6	Customer Contact Center	55,819,863	-	-
7	Large Customer Services	9,673,539	-	-
8	Revenue Management	43,881,706	-	-
9	Revenue Protection (AMI Ops & AMI Analytics)	402,992	-	-
10	Demand Response & Dynamic Pricing	9,038,443	-	-
11	Electric Supplier Services (2)	1,838,327	(827,991)	1,712,692
12	Market Research	2,530,143	-	-
13	Information Technology	60,039,381		
14	Support Services	7,887,990	-	-
15	Customer Relations	1,176,147	-	-
16	Green Power Connection	1,217,798	(119,000)	976,740
17	Other (3)	3,519,779	-	-
18	Total Costs Analyzed	\$ 223,167,195	\$ (3,200,615)	\$ 9,971,572
19	Amounts Not Analyzed (4)	\$ 532,324		
20	Grand Total of Study	\$ 239,922,568	\$ (3,200,615)	\$ 9,971,572
(1) These costs were not further analyzed because the departments / activities relate solely to ComEd's distribution service. (2) EDI costs for ESSD are charged to FERC 920 (3) Other includes costs of the External Affairs, Safety and Training and Strategy and Support (4) Amounts not analyzed consisted of individual departments / activities that had costs below \$100,000. (5) Indirect overhead allocations of ~\$5M not included in baseline costs				

Note that the 2025 Switching Study focused solely on whether costs were impacted by customers switching from ComEd to RESs for supply. It did not examine the allocation of costs to RESs, and whether the current allocation is reasonable.

II. COSTS ANALYZED IN 2025 SWITCHING STUDY

ComEd reviewed costs as of December 31, 2024 for the 2025 Switching Study. ComEd identified the costs to be reviewed for the purposes of this Study as the 2024 operations and maintenance ("O&M") costs incurred by certain of its departments that provide customer care. The costs of these functions are, in most cases, recorded in the Customer section of the Uniform System of Accounts ("USOA") accounts on ComEd's general ledger in FERC accounts 901, 902 and 903. ComEd removed the portion of those costs that are directly related to delivery service (*e.g.*, meter reading). There are 13 primary departments involved in providing Customer Care functions: Field and Meter Services, Billing, Customer Contact Center, Large Customer Services, Revenue Management, Revenue Protection, Demand Response and Dynamic Pricing, Electric Supplier Services, Market Research, Information Technology, Support Services, Customer Relations, Green Power Connection, and Other. These departments are explained in more detail in the following sub-sections of the 2025 Switching Study.

ComEd also identified two categories of Customer Care costs – Metering Services¹ and Advertising² – that are not analyzed in the Study because they relate to ComEd's role as a delivery service provider and will continue to be provided regardless of the level of switching from ComEd to a RES.

A. Field and Meter Services

The Field and Meter Services department is responsible for all aspects of installation, investigation, replacement, testing, disconnection and reconnection of meters for all ComEd's customers.

For the 2025 Switching Study, ComEd's Field and Meter Services department reviewed approximately \$10.5 million in costs. The costs of providing Metering Services, described in footnote 1, are related to ComEd's provision of delivery service and are directly allocated to delivery service. They were therefore excluded from this analysis.

The activities of the Field and Meter Services department are directly related to those of the Revenue Management department. The Field and Meter Services department determined that ComEd's activities relating to metering services, disconnection of meters for nonpayment, as well as

¹ Metering Services includes meter reading, meter equipment installation, exchange and removal, and other services described in ComEd's Rate MSPS – Metering Services Provider Service ("Rate MSPS"). See ILL. C. C. No. 10, Sheet Nos. 96 and 97. These costs were removed from the 2025 Switching Study because ComEd will continue to install, exchange, and remove meters and continue to read meters for the purpose of billing electricity supply and delivery charges regardless of customers' electricity suppliers and also to provide metering data to RESs.

² Advertising is a ComEd department that provides instructional information to customers on outages and storm restorations, electric safety tips, and conservation of energy in print advertising, radio, newspapers, and billboards. These costs were excluded from the Study because, consistent with regulatory requirements, all advertising relates to ComEd's role as a delivery service provider and will continue regardless of the level of switching.

reconnection of meters, will continue at the same rate regardless of the level of switching, and thus ComEd would continue to bear the same costs that it does today. Like the activities related to credit and collections, along with disconnections, the activities of the Field and Meter Services department will not be affected as switching volumes change.

B. Billing

The ComEd Billing department focuses on resolving billing issues. These issues primarily include delayed bills, manual bills, customer requests related to potential billing issues, and processing field activities. Additionally, Billing Operations partners with Customer Operations to maintain timely and accurate billing for ComEd's customers and suppliers.

For the 2025 Switching Study, ComEd's Billing department reviewed approximately \$15.6 million of its costs. These costs support core responsibilities such as calculating delivery service charges, addressing customer inquiries, and processing field activities applicable to all customers.

In addition to core activities, the Billing department also supports responsibilities specific to certain customer groups, such as customers with alternative suppliers. The technical structure and operational requirements specific to alternative suppliers introduce additional technical complexity and resource efficiency burdens for ComEd. This is evident when comparing the percentage of customers on ARES supply vs. the percentage of ARES accounts processed by the back-office billing team.

With respect to switching, since ARES-supplied customers have increased complexity, there is a direct correlation between switching and the billing department's costs. Line 5 of Table 1 reflects the anticipated change in Billing costs of switching at 1% and 100% based on current work volumes.

C. Customer Contact Center

The Customer Contact Center handles a wide variety of general customer inquiries, such as storm and emergency restoration calls, moving and relocation, credit activities, and questions related to activities of the Field and Meter Services (including meter reading) and Billing departments. The Customer Contact Center handles these inquiries through multiple channels (*i.e.*, inbound telephone calls, web-related communications, and written correspondence). The Customer Contact Center is primarily comprised of the operation of the call center floor staffed by Customer Service Representatives ("CSRs") for the purpose of answering calls and customer correspondence. This team is supported by a Resource Management group. The Resource Management group develops operating plans, handles long range planning, forecasting, and real-time call volume management, manages the budget, implements quality management, and creates and administers training for the CSRs.

In connection with the 2025 Switching Study, ComEd's Customer Contact Center reviewed approximately \$55.8 million of ComEd's O&M costs, which included labor costs related to salaries, overtime pay, other premiums (CSR meal stipends for agents working remotely and part-time CSRs working more than 32 hours but less than 40 hours), and staff augmentation. Most non-labor costs reviewed included contracting services, IT software licenses, and meals for CSRs working overtime.

ComEd analyzed the customer calls that the Customer Contact Center handled in 2024, which related to a variety of customer concerns including, but not limited to, storm and emergency restorations and moving and relocation. Those types of calls relate to ComEd's delivery service, and are not related to customer switching. However, ComEd also examined data relating to billing inquiries, including account balance inquiries, payment arrangements, and payment verifications, for the various historical levels of switching. See Table 2 below. ComEd found that the act of a customer switching to RES supplier did not correlate to an increase or decrease in the number of bill balance and payment-related customer calls received. Therefore, no impact to Customer Contact Center costs because of switching was identified.

Moreover, there has been no demonstrated correlation between switching and the volume of billing-related calls. Billing-related call volumes have fluctuated between 1.6 million and 1.8 million per year for the last five years, meaning calls related to billing have both increased and decreased in years when switching increased. Similarly, customer call volume has both increased and decreased in years switching decreased.

Table 2 below demonstrates that there is no direct correlation between call volume of billing-related calls and the percentage of customers receiving RES service. Table 2 provides the number of billing-related and other delivery service type calls handled by CSRs each year and the percentage of customers receiving service from a RES. In 2019 and 2022, there was a decrease in the percentage of customers with a RES, yet the number of billing-related calls increased. In 2024, the percentage of customers with a RES increased, but the number of billing related calls decreased.

Table 2 – CSR-Handled Call Volumes and Percentage of Customers Receiving RES Service

	2024	2023	2022	2021	2020	2019	2018
Percentage of Customers Receiving RES Service	22.9%	22.3%	19.8%	23.6%	26.0%	30.9%	33.9%
Handled CSR Call Volume	2,825,805	3,049,547	2,976,530	3,089,978	3,372,743	4,164,830	4,457,877
Billing	1,752,537	1,881,672	1,766,677	1,673,819	1,785,657	2,366,038	2,227,968
Care	14,940	31,138	40,912	51,212	43,877	65,536	71,889
Customer Choice	39,525	27,008	12,241	20,855	22,003	32,062	34,125
Moving	608,634	690,133	742,408	842,830	838,415	1,008,537	1,133,633
Other	98,236	72,316	65,562	108,305	97,316	106,893	488,486
Outage	351,953	386,480	354,710	394,917	620,875	651,774	521,766
Total	2,825,805	3,049,547	2,976,530	3,089,978	3,372,743	4,164,830	4,457,877

D. Large Customer Services

Large Customer Services is a ComEd department that provides account management services for large customers, which are those customers having demands greater than 500 kW and multi-site customers like those that operate many locations under one parent company. The services provided include billing inquiries, customer collections, demand response, new service installation, and storm restoration or emergency support.

In connection with the 2025 Switching Study, ComEd's Large Customer Service department reviewed approximately \$9.7 million of costs, which were primarily related to labor for account management services.

The provision of electric power and energy supply to customers served by the Large Customer Services department (customers having demands of greater than 500 kW and multi-site customers like those that operate many locations under one parent company) has been declared competitive by operation of law. See 220 ILCS 5/16-113(f). Therefore, these customers receive their supply

services either from a RES or at the default hourly rate in accordance with Rate BESH – Basic Electric Service Hourly Pricing. Most of these customers receive supply from a RES. The Commission's Integrated Delivery Company Rules prohibit ComEd from attempting to obtain or retain customers on default hourly supply. As such, ComEd, including through its Large Customer Service representatives, does not discuss RES-pricing related issues, and ComEd does not incur time, effort, or costs related to customer switching and RES services in that respect.

For those topics that Large Customer Services representatives can, and do, discuss with the customer – such as billing inquiries, customer collections, demand response, new service installation, and storm restoration or emergency support – ComEd concludes there is no reduction in the activities or costs of this department due to changes in switching levels because providing the services related to these issues is not dependent on the supplier choice.

E. Revenue Management

The Revenue Management department is responsible for managing the portfolio of ComEd's receivables, including credit disconnections and collection policies and procedures, as well as managing ComEd's payment processing vendor, which includes activities such as opening mail, capturing an electronic image of the payment, and processing payments to associated accounts within CC&B. In addition, Revenue Management also manages the relationship with the vendor that is responsible for bill and correspondence printing and mailing.

In connection with the Switching Study, ComEd's Revenue Management department reviewed a total of approximately \$44 million related to its labor costs (includes salaries, overtime pay, and travel), payment processing vendor costs (includes credit card fees, collection vendor costs, and bill printing and mailing).

ComEd's activities relating to managing service receivables would continue in the same way regardless of the number of customers switching. ComEd's Revenue Management department incurs costs relating to the disconnection of customers who fall behind on their payments. ComEd estimates that the percentage of disconnections, and the corresponding costs, would remain steady regardless of the source of customers' supply. If customer switching decreased (and more customers stayed with ComEd for supply), ComEd would incur additional printing and mailing costs associated with the increase in single-bill option ("SBO") customer bills; however, this cost would be offset by the elimination of the SBO credit included on customer bills.

F. Revenue Protection

The Revenue Protection department focuses on investigating consumption on inactive meters, meter audits, stuck meters, and tampered meters, as well as back billing of customers. Most of the costs related to the Revenue Protection department are considered 100% metering, similar to Field and Meter Services.

In connection with the Switching Study, ComEd's Revenue Protection department reviewed a total of approximately \$0.4 million related to its costs of supplies and labor.

ComEd's Revenue Protection activities would continue regardless of the number of customers switching, and as a result, ComEd would continue to incur the same related costs. For example, monitoring and investigating consumption on inactive meters is not dependent on who is supplying the electricity.

G. Demand Response and Dynamic Pricing

The Demand Response and Dynamic Pricing department plans and implements programs that offer ComEd's customers ways to manage their energy use and lower their energy bills.

In connection with the 2025 Switching Study the Demand Response and Dynamic Pricing department reviewed a total of approximately \$9.0 million of departmental costs, including program administration costs, strategic planning costs, program measurement and verification costs, IT program system testing costs, and program material costs.

In 2024, ComEd's demand response programs were offered on a competitively neutral basis to all customers, regardless of the customer's supply provider. For example, the Peak Time Savings program is available to any residential retail customer with an advanced metering installation. The AC Cycling and Voluntary Load Reduction programs are not restricted to customers that obtain electric power and energy supply from ComEd. Consequently, there were no impacts to the associated costs when customers switched to RESs for the provision of such programs.

For dynamic pricing, ComEd would no longer have residential customers taking service under Residential Real Time Pricing at 100% RES switching, but current law requires ComEd to offer the rate and it would still have similar costs and be required to maintain the statutory and tariff-required reporting requirements. The Residential Time of Use Pricing Pilot ended in 2024 and would not be impacted with RES switching.

H. Electric Supplier Services Department

To support ComEd's role as an Electric Distribution Company ("EDC"), the Electricity Supplier Services Department ("ESSD"), which is a part of ComEd's Energy Acquisition department, maintains and manages ComEd's operating relationships with RESs that do business in ComEd's service territory. ESSD facilitates Electronic Data Interchange ("EDI") data transmittals to or from RESs, performs validation, processing, and communications tasks, and addresses questions on switching, each of which supports RESs (and Community Supply, as Community Supply entities also engage in customer enrollments) by ensuring customers are successfully switched in ComEd's billing system. ESSD also administers Rider PORCB – Purchase of Receivables with Consolidated Billing, under which RESs provide ComEd with supply charges to present on ComEd customer bills. Similarly, Energy Acquisition's Wholesale Settlement Operations, Wholesale Markets and Development, and Wholesale Billing and Credit groups work with RESs and their supply customers to create and schedule customer load responsibilities in the PJM wholesale market, calculate customers' Peak Load Contribution and Network Service Peak Load Contribution values, reconcile and submit to PJM the reconciliation of scheduled loads to actual meter readings, and ensure the accurate allocation of PJM costs in the ComEd Zone.

ComEd reviewed \$1.8 million of departmental costs for the 2025 Switching Study. Except for costs directly charged to the supply function, Energy Acquisition's costs, including ESSD costs, are delivery costs, and not supply costs. ComEd provides these delivery services to support its customers so they have an opportunity to switch to a supplier. The services also provide RESs with education on ComEd's rates and provide RESs with a single point of contact for any data issues, clarifications on rate applications and general support for RES activities.

Some of the services provided by the ESSD department use EDI transactions to send and receive data electronically to RESs and ComEd incurs costs for each EDI transaction processed. As it relates

to customer switching, EDI transactions are used by ComEd to send switching, billing, and usage information to every RES daily for each of their supply customers, and to receive enrollment and data requests from RESs. ComEd does not use these EDI transactions for billing customers taking supply from ComEd. If 100% of customers switched to a RES, ComEd would have to pay an external vendor to handle the processing of additional EDI transactions and there would be an estimated increase in costs of \$1.7 million. If only 1% of customers switched to a RES, there would be fewer EDI transactions and costs would decrease by an estimated \$0.8 million.

I. Market Research

ComEd's Market Research department plans and implements ComEd's marketing research projects, including data analysis, report preparation, and vendor and internal client management activities. ComEd also contracts with market research firms to purchase syndicated research reports, conduct a variety of information gathering regarding satisfaction with ComEd's performance and services, and inform various customer-facing business initiatives.

In connection with the 2025 Switching Study, approximately \$2.5 million of Market Research department costs were reviewed. These costs include labor, contracting, and software licensing costs.

Market research conducted by ComEd to monitor customer satisfaction or support its customers is done irrespective of whether they are provided with supply service from a RES or from ComEd. Therefore, there is no impact from switching.

J. Information Technology

Exelon Business Services Company provides centrally managed IT support for all Exelon operating companies, including ComEd.

In connection with the 2025 Switching Study, approximately \$60 million of IT service costs billed to ComEd, including ComEd's share of Exelon-wide projects and ComEd-specific projects were reviewed. These projects include labor costs, contracting costs, hardware costs and software costs. In addition, other IT costs were reviewed, such as ComEd's telephony usage, ComEd's cellular usage, ComEd's audio/visual usage, and ComEd's share of software license costs.

For the IT costs allocated to ComEd, there would be no cost reduction at any level of switching because the IT equipment and services used to provide reliable electric service and related programs must be maintained at current levels regardless of the number of customers with a RES.

K. Support Services

Support Services (also known as Customer Strategy & Governance) is a centralized group that drives and aligns ComEd toward excellence by supporting strategies in an integrated manner. The Strategy and Governance team develops strategies for Customer Operations to achieve business objectives while ensuring efficiency, alignment, accountability, and transparency. The Program/Project Management team coordinates and facilitates the management of life-cycle and strategic projects/programs that affect ComEd Customer IT platforms. The Data Analytics team uses data analytics to develop insights, generate new ideas, and innovate fresh yet practical solutions to address challenges.

In connection with the 2025 Switching Study, ComEd's Support Services area reviewed a total of approximately \$7.9 million of costs.

No costs were identified that would be impacted by switching within Support Services (Customer Strategy & Governance). As mentioned earlier, Support Services (Customer Strategy & Governance) is a centralized team that provides support to the entire Customer Operations organization and does not engage in any activities related to switching, nor would it be impacted by switching.

L. Customer Relations

The Customer Relations department responds to and resolves customer complaints received through the ICC, Better Business Bureau, Citizens Utility Board, Illinois Attorney General, social media, and requests sent to ComEd executives, regardless of the customer's supplier. They provide root cause and process improvement information to ComEd through their trend analysis work.

In connection with the 2025 Switching Study, ComEd's Customer Relations department reviewed approximately \$1.2 million of department costs.

No impact to Customer Relations was found by switching. ComEd's activities relating to answering and addressing customer complaints will continue regardless of the number of customers switching.

M. Green Power Connection

The Green Power Connection ("GPC") team provides information to customers that have or are considering installing solar and helps address customer concerns during the interconnection and billing process. The GPC team helps customers make informed decisions about solar options, assists net metering customers with billing and technical inquiries, and provides each customer with a single point of contact from ComEd. GPC handles complex customer inquiries through multiple channels, including calls, emails, and voicemails.

In connection with the 2025 Switching Study, ComEd reviewed approximately \$1.2 million of department costs.

In 2024, approximately 30% of the customer inquiries handled by the GPC team came from customers with RES suppliers. Customers with RES supply service who contact the GPC team primarily inquire about billing issues related to their net metering credits and the way the RES is handling those credits. The GPC team also handles customer inquiries about ComEd-offered rebates with rate requirements that require participation in a time-variant rate and can result in customers switching suppliers to a RES with a time-variant rate, or away from RES supply (if they cannot find a satisfactory RES time-variant rate). These calls can be complex due to variations in the net metering structure, rate plans that can vary by RES, and associated billing process applied by each RES – and consequently calls related to RES net metering applications often require additional time and coordination by the GPC team to resolve.

If the switching rate were to decrease to 1%, it would not result in any significant reduction in associated department costs. ComEd's current resource plan prioritizes the handling of customer inquiries over other back-office activities (including, but not limited to, maintaining internal tools and systems, updating customer-facing educational material, supporting community outreach events, improving internal processes, updating employee training material, and conducting operational reporting/analyses). Any back-office tasks that are deferred under the current switching rate would

simply be reprioritized. For this scenario however, an assumption was made that \$119,000 in costs for one contractor would be avoided as complex customer inquiries would be expected to decrease (all else being equal).

However, if the switching rate were to rise to 100%, an increase in associated department costs of approximately \$0.98 million is forecasted. This amount corresponds to approximately six additional full-time equivalent resources who would be needed to support the increase in inquiries from customers with RES suppliers and the additional time needed to resolve RES-related net metering issues as discussed above.

N. Other

The “Other” category includes \$3.5 million in costs related to Safety and Training, External Affairs and the Strategy and Support areas. These areas do not perform activities that would be impacted by customers switching to a RES, so there is no change in either the 1% or 100% scenario.

III. CONCLUSION

The 2025 Switching Study demonstrates that ComEd’s Customer Care costs do not generally change based on the levels of customers receiving supply service from ComEd. More specifically, of the total \$239 million of Customer Care costs incurred by ComEd in 2024, it is estimated there would be a total *decrease* of \$3.2 million of costs in three departments, which is approximately 1% of the total costs, at the 1% switching level. At the 100% switching level, it is estimated there would be a total *increase* of \$10 million of costs across the same three departments, which is approximately 4% of the total costs.

Note that the 2025 Switching Study did not analyze costs for an allocation to RESs, or RES-supplied customers, for any increased costs that might result from customers switching to a RES or for costs currently incurred that may be directly attributable to RES-supplied customers (e.g. EDI, billing costs and Green Power Connect costs). A separate analysis would be needed to determine which costs are primarily driven by RESs or RES-supplied customers. If costs currently being allocated to Delivery Service are to be directly allocated to Supply Services, then some of these costs would necessarily need to be allocated to RESs.

Illinois Competitive Energy Association and Retail Energy Supply Association
("ICEA-RESA") Responses to Commonwealth Edison Company's ("ComEd")
First Set of Questions to ICEA-RESA

ICC Investigation on Supply-Delivery Cost Allocation

July 18, 2025

- 1.01 Does ICEA-RESA agree that based on the updated Switching Study findings that since there is no longer a forecasted reduction in Call Center costs with increased switching to 100% of ComEd customers on Retail Electric Supplier (RES) supply, then there should not be an allocation of Call Center costs to the ComEd supply rates? If the answer is "No", please explain in detail why not and provide any work papers.

ICEA-RESA RESPONSE

No. ICEA-RESA disagrees with the results of the Switching Study for several reasons. First, the proper basis for allocation of call center costs is the subject of the calls, not whether switching correlates to cost increases or decreases. This is consistent with the embedded cost of service approach ComEd generally takes with its costs. Second, because ICEA-RESA witness Dr. Leonardo Giacchino is of the opinion that there is no scientific basis to reach the conclusions drawn by ComEd from the study. For example, the Switching Study concludes that "there is no direct correlation between call volume of billing-related calls and the percentage of customers receiving RES service" (page 5). The Switching Study evidently reached that conclusion by looking at the direction of calls handled and the percentage of customers receiving RES service for 2019, 2022 and 2024 only, while ignoring the other years in its data set. There is no statistical analysis showing that there is in fact no correlation. When using statistical analysis on the data set presented by the study, there is a correlation and it is significant, as shown below.

SUMMARY OUTPUT

Regression Statistics	
Multiple R	0.935228191
R Square	0.87465177
Adjusted R Square	0.849582124
Standard Error	246822.0854
Observations	7

ANOVA					
	df	SS	MS	F	Significance F
Regression	1	2.12547E+12	2.12E+12	34.88887597	0.001980069
Residual	5	3.04606E+11	6.09E+10		
Total	6	2.43008E+12			

	Coefficients	Standard Error	t Stat	P-value	Lower 95%	Upper 95%	Lower 95.0%	Upper 95.0%
Intercept	429280.0347	514786.9061	0.833899	0.442341476	-894021.8355	1752581.905	-894021.8355	1752581.905
Percentage of Customers Receiving RES Service	11501291.08	1947166.575	5.906681	0.001980069	6495940.047	16506642.1	6495940.047	16506642.1

Conclusion

There is a significant positive relationship between the Handled CSR Call Volume and the percentage of customers receiving RES service. In statistical terms, $r(5) = 0.935228191$, $p < 0.002$

When performing correlation analysis, the correlation coefficient is the same as the Multiple R in a Regression and it is considered significant (that one variable is correlated with the other) if the probability that the variable does not impact the other is lower than 5%. In the calculation using ComEd's data, the probability is less than 0.2%, which strongly implies that the percentage of customers receiving RES service does impact the number of calls.

- 1.02 Does ICEA-RESA agree that based on the updated Switching Study findings that since there are increased costs associated with the Electric Supplier Service Department (ESSD), Billing and Green Power Connect with increased switching to 100% Retail Electric Supplier (RES) supply, then there should be an allocation of those department costs to Retail Electric Suppliers (RESs) or RES-supplied customers? If ICEA-RESA does not agree, please explain in detail why not and provide any work papers.

ICEA-RESA RESPONSE

No. The Switching Study says at the beginning of page 3 that “It did not examine the allocation of costs to RES, and whether the current allocation is reasonable.” Only after examination of the current allocation of costs by ComEd could the findings of an Updated Switching Study be used to decide to allocate costs or not from certain departments to RESs.

Responding further, the Switching Study misstates ComEd’s own tariffs and the law. Section 16-107.6(c)(2) provides that “Any distributed generation device that is compensated for storage in this subsection (2) before the threshold date shall participate in a peak time rebate program, hourly pricing program, or time-of-use rate program offered by the applicable electric utility.” (220 ILCS 5/16-107.6(c)(2).) In addition, ComEd’s Rider DG Rebate states that “the retail customer serviced by any Distributed Electric Renewable Generating Facility that is associated with an Energy Storage Facility for which a Resource 2B Rebate is received must take service under a QUP and remain on a QUP for the life of the Energy Storage Facility,” where a QUP is “a utility-offered product, related to either energy supply or the delivery of such energy supply which utilizes a time-variant pricing structure whereby a retail customer is charged at a higher volumetric rate during certain designated times, typically when system demand is high, and is charged at a lower volumetric rate during other designated times, typically when system demand is low.” However, the Switching Study states that: “The GPC team also handles customer inquiries about ComEd-offered rebates with rate requirements that require participation in a time-variant rate and can result in customers switching suppliers to a RES with a time-variant rate, or away from RES supply (if they cannot find a satisfactory RES time-variant rate).” (RML 1.02 SUPP_Attach 1 at 9.) ICEA and RESA are unaware of any other solar-related obligation that requires a time-variant rate. In other words, questions about ComEd’s 2B rebate are about a ComEd supply rate—not RES products and services as incorrectly suggested by the Switching Study.

- 1.03 In reference to the CCSA provided as ComEd Ex. 5.06 which allocates Call Center costs to ComEd supply rates:
- a. Does ICEA-RESA agree that RES-supplied customers use ComEd's Call Center?
 - b. If ComEd continues to allocate a portion of the Call Center costs to ComEd supply customers, should a portion of the Call Center costs be allocated to Retail Electric Suppliers (RESs) or RES-supplied customers? Why or why not.
 - i. If ICEA-RESA agrees that a portion should be assigned to RESs or RES-supplied customers, how does ICEA-RESA recommend those costs be assigned to and recovered from RESs or RES-supplied customers.

ICEA-RESA RESPONSE

- a. Yes. Responding further, ICEA and RESA note that RES-supplied customers continue to take delivery service as well.
- b. ComEd Ex. 5.06 does not provide a methodology to allocate a portion of the Call Center costs from ComEd supply customers to RESs. However, ICEA and RESA do not agree that costs should be allocated to ARES or ARES-supplied customers (except in their capacity as delivery customers). ICEA and RESA are unable to address specific costs or allocations without more information.

- 1.04 Does ICEA-RESA still support their methodology for allocating delivery costs to supply as described in Giacchino Rebuttal, ICEA-RESA Ex. 5.0 and the supporting work-paper provided in ICEA-RESA Ex. 5.01?
- a. If the answer to the question above is yes, referring to ICEA-RESA Ex. 5.01, which used ComEd's Embedded Cost of Service Study (ECOSS) for its analysis, please list each sub-function from ComEd's ECOSS included in ICEA-RESA Ex. 5.01 that assigns a portion of the current delivery costs to ComEd supply rates. A summary of ComEd's ECOSS sub-functions is provided as Table 1 below for convenience.
 - b. For each sub-function listed in the response to subpart (a) above, please provide the following: (i) the amount of costs to be allocated to ComEd supply rates (ii) a detailed description on why it is appropriate to allocate those costs to ComEd supply rates (iii) the share of the sub-function costs that should be allocated to Retail Electric Suppliers (RESs) or RES-supplied customers (iv) a detailed description on why it is appropriate to allocate those costs to RESs or RES-supplied customers and (v) if no costs are identified to be allocated to RESs or RES-supplied customers for each sub-function, a detailed description of why none of the cost should be allocated to RESs or RES-supplied customers but a portion of the costs should be allocated to ComEd supply rates.

Table 1: ECOSS Distribution Sub-Functions
HV Electric Service Stations (“ESS”)
HV Distribution Substations
HV Distribution Lines
Shared Distribution Substations
Secondary Voltage Distribution Substations
Shared Distribution Lines
Secondary Voltage Distribution Lines
Primary Voltage Transformers
Secondary Voltage Transformers
Service Connections
Customer Installations Other
Fixture-Included Lighting (“FIL”)
Metering Service
Indirect Uncollectibles
Billing Computation and Data
Bill Issue and Processing
Customer Service and Information
Revenue Related

- c. For each of the costs described in subpart b., explain how much of the costs are related to RES-supplied customers and how those costs for RES supplied customers should be allocated to and recovered from RESs or RES supplied customers.

ICEA-RESA RESPONSE

Yes. Consequently, all of the answers to this request for information are contained in Dr. Giacchino's direct and rebuttal testimony and exhibits. However, to provide further information, please see the answers below.

- a. Please refer to ICEA-RESA Ex. 2.03, which is Dr. Giacchino's model based upon ComEd's data request response ICEA-COMED 1.02_Attach3. Within Dr. Giacchino's model, please run each of the alternatives in cell C7 of Tab "Menu". The results for each alternative by sub-function from Table 1 are found in different Tabs. For the "Total as Filed by ComEd," please refer to Tab "Sch 2a Allocation;" for "RTOD Customers," please refer to Tab "Sch 2a Allocation v 1;" for "Taking Hourly Price Service from ComEd," please refer to Tab "Sch 2a Allocation v 2;" for "Taking Fixed Price Supply Service from ComEd," please refer to Tab "Sch 2a Allocation v 3;" and for "Taking Supply Service from a Retail Electric Supplier (RES)," please refer to Tab "Sch 2a Allocation v 4."
- b. Dr. Giacchino has already explained in detail in his Testimony and Rebuttal Testimony how he improved Functionalization and he added to ComEd's model the Tabs "Allocators" and "Allocator Framework" to do so. The results shown in the Tabs cited in response 1.04(a) above is the result from ComEd's own calculations after adding the improvements and corrections proposed by Dr. Giacchino.
- c. Tab "Sch 2a Allocation v 4" include those costs. As Dr. Giacchino stated "While at the overall level show in Table 3a the unit costs look reasonable, for each category of costs there is variation around the average that for some customer classes may be seen as too wide. After a thorough analysis of the allocation of costs by ComEd to each customer class, Dr. Giacchino concludes that there is a certain bias against residential classes in the methodology. For example, when dealing with billing costs, the ComEd model uses number of customers to allocate costs instead of revenues or kWh or a combination of all of those factors. Choosing number of customers allocate the most costs to residential customer classes and the least to other customer classes. A simple change in the model to switch the allocator for billing costs change dramatically the cost per kWh for the Taking Hourly Price Service From ComEd customers. If this bias were to be eliminated, several changes in the allocation factors should be implemented and would eliminate the variation in unit costs for different categories. Dr. Giacchino did not make this change in his model, but if the Commission or other stakeholders were concerned about rate shock, this approach would (prior to any other mitigants that the Commission may impose) mitigate rate shock" (ICEA-RESA Ex. 5.0 at 8:126-9:141 (emphasis added)). Only after correcting all of the problems in ComEd's allocation process that Dr. Giacchino identified in his testimony can this question be answered.

Information Request
Re: ICC Docket No. 24-0378 Commonwealth Edison Company, Final Order
Supply-Delivery Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Competitive Energy Association and Retail Energy Supply Association
("ICEA-RESA") Information Requests
ICEA-RESA 1.01 – ICEA-RESA 1.08
Date Received: April 30, 2025
Date Served: June 2, 2025

Given that there are three separate steps in the allocation of costs for rate-making, being Functionalization (allocation between regulated and unregulated functions), Classification (allocation into fixed, variable and customer costs) and Allocation (allocation to customer classes), please answer the following questions:

REQUEST NO. ICEA-RESA 1.01:

Please refer to ComEd Ex. 2.01 in ICC Docket No. 24-0378. Please confirm that there is another model which feeds results into ComEd Ex. 2.01, where the results are amounts specific to regulated functions? Please provide the model or if there is no model please identify the source(s) of data in ComEd Ex. 2.01.

RESPONSE:

ComEd confirms there are other work papers that are inputs to ComEd's ECOS model. ComEd Ex. 2.01 is the ECOS for 2026 used as the base case ECOS for the Rate Design Investigation filing (ICC Docket No. 24-0378). See the attachment labeled as ICEA-RESA 1.01_Attach 1. The 2026 base ECOS was approved in ComEd's Multi Year Rate Plan (MRP) (Docket Nos. 22-0486/23-0055 (Cons.)) The supporting work papers were included in the MRP docket as ComEd Exs. 17.06, 17.07, 17.08, 17.11 (2026 version), and 17.14. The Excel version of the files are provided as attachments labeled as ICEA-RESA 1.01_Attach 2 through 6.

Base 2026 ECOS
TAB: Titles

STATE OF ILLINOIS
ILLINOIS COMMERCE COMMISSION

COMMONWEALTH EDISON COMPANY

2026 REFILED GRID PLAN - BASE ECOS
EMBEDDED COST OF SERVICE STUDY

Base 2026 ECOS
TAB: Titles

Schedule 1a
FUNCTIONALIZATION

[illegible]

[illegible]

Base 2026 ECOSS
TAB: Titles

Schedule 1b
FUNCTIONALIZATION FACTOR

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523
--	---	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

Base 2026 ECOS
TAB: Titles

Schedule 2a
ALLOCATION

[illegible]

Table with multiple columns and rows, containing various data points and headers. The table is oriented horizontally on the page.

Account	2019		2018		2017		2016		2015		2014		2013		2012		2011		2010		2009		2008		2007		2006		2005		2004		2003		2002		2001		2000		1999		1998		1997		1996		1995		1994		1993		1992		1991		1990		1989		1988		1987		1986		1985		1984		1983		1982		1981		1980		1979		1978		1977		1976		1975		1974		1973		1972		1971		1970		1969		1968		1967		1966		1965		1964		1963		1962		1961		1960		1959		1958		1957		1956		1955		1954		1953		1952		1951		1950		1949		1948		1947		1946		1945		1944		1943		1942		1941		1940		1939		1938		1937		1936		1935		1934		1933		1932		1931		1930		1929		1928		1927		1926		1925		1924		1923		1922		1921		1920		1919		1918		1917		1916		1915		1914		1913		1912		1911		1910		1909		1908		1907		1906		1905		1904		1903		1902		1901		1900		1899		1898		1897		1896		1895		1894		1893		1892		1891		1890		1889		1888		1887		1886		1885		1884		1883		1882		1881		1880		1879		1878		1877		1876		1875		1874		1873		1872		1871		1870		1869		1868		1867		1866		1865		1864		1863		1862		1861		1860		1859		1858		1857		1856		1855		1854		1853		1852		1851		1850		1849		1848		1847		1846		1845		1844		1843		1842		1841		1840		1839		1838		1837		1836		1835		1834		1833		1832		1831		1830		1829		1828		1827		1826		1825		1824		1823		1822		1821		1820		1819		1818		1817		1816		1815		1814		1813		1812		1811		1810		1809		1808		1807		1806		1805		1804		1803		1802		1801		1800		1799		1798		1797		1796		1795		1794		1793		1792		1791		1790		1789		1788		1787		1786		1785		1784		1783		1782		1781		1780		1779		1778		1777		1776		1775		1774		1773		1772		1771		1770		1769		1768		1767		1766		1765		1764		1763		1762		1761		1760		1759		1758		1757		1756		1755		1754		1753		1752		1751		1750		1749		1748		1747		1746		1745		1744		1743		1742		1741		1740		1739		1738		1737		1736		1735		1734		1733		1732		1731		1730		1729		1728		1727		1726		1725		1724		1723		1722		1721		1720		1719		1718		1717		1716		1715		1714		1713		1712		1711		1710		1709		1708		1707		1706		1705		1704		1703		1702		1701		1700		1699		1698		1697		1696		1695		1694		1693		1692		1691		1690		1689		1688		1687		1686		1685		1684		1683		1682		1681		16	
---------	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	------	--	----	--

Base 2026 ECOS
TAB: Titles

Schedule 2b
ALLOCATION FACTORS

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 146 of 580

[illegible]

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 147 of 580

Base 2024 ECODE
TMR: Sub 2b Educational Factors

[illegible]

Base 2026 ECOSS
TAB: Titles

Schedule 3
ECOSS COMPARISON

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 149 of 580

Base 2026 ECOS\$
TAB: Sch 3 ECOS\$ Compare

Commonwealth Edison Company The Comparison of Delivery Service Cost of Service 2025 RATES UPDATED IN THE REFILED GRID PLAN vs. 2025 RATES UPDATED IN THE REFILED GRID PLAN (Base ECOS\$)				
Delivery Class/Subclass	Cost of Delivery Service (\$1,000's)			
	2025 RATES - UPDATED IN THE REFILED GRID PLAN	2025 RATES - UPDATED IN THE REFILED GRID PLAN (Base ECOS\$)	Difference	Percent Change
	(A)	(B)	(C) = (B) - (A)	(D) = (C) / (A)
Residential Service				
Single Family Without Electric Space Heat	1,546,039	1,432,879	66,867	4.34%
Multi Family Without Electric Space Heat	401,838	415,594	13,778	3.43%
Single Family With Electric Space Heat	26,718	26,718	999	3.69%
Multi Family With Electric Space Heat	87,863	70,268	2,288	3.38%
Nonresidential	2,041,517	2,125,256	83,732	4.10%
Nonresidential Service				
Small Plant	25,077	24,823	(255)	-1.02%
Small Load (0 to 100 kW)	498,089	508,428	10,743	2.16%
Medium Load (Over 100 to 400 kW)	317,968	308,757	10,761	3.39%
Large Load (Over 400 to 1,000 kW)	253,949	262,779	8,436	3.32%
Very Large Load (Over 1,000 to 10,000 kW)	426,463	449,021	11,564	3.11%
Extra Large Load (Over 10,000 kW)	66,939	63,436	2,500	3.00%
High Voltage (Up to 10,000 kV)	4,417	4,417	0	0.00%
High Voltage (Over 10,000 kV)	37,040	36,406	(640)	-1.73%
Electric	8,451	8,305	146	1.62%
Nonresidential (No Lighting)	1,652,954	1,704,585	51,596	3.12%
Utility Service				
Electric Included Lighting	22,748	23,314	564	2.48%
Street Lighting - Non Alley Drive to Down	3,662	3,627	185	4.50%
Street Lighting - Alley Drive to Down	159	160	3	1.89%
Street Lighting - Overhead Lighting	1,780	1,880	80	4.50%
Lighting	26,349	29,375	707	2.71%
Total	3,722,861	3,868,982	136,121	3.66%

Base 2026 ECOS
TAB: Titles

Work Papers

Commonwealth Edison Company		Base 2026 ECOSS
Alley Lights Adjustment for The City of Chicago and Suburban Lights		TAB: Alley D to D Adj
Item	Source	Amount
Suburban Alley Lighting	From Suburb Alley Light Tab, line 14	\$38
Chicago Alley Lighting	From Chicago Method Alley Lighting Tab, line 14	\$66,542
Total Using City or Chicago Method		\$66,580
ComEd Secondary Cost in ECOSS		
Alley Secondary Distribution Lines Costs in ECOSS	From this ECOSS Model, Sch. 2a, line 209	\$133,765
ComEd Service Drop Cost in ECOSS		
Alley Services Costs in ECOSS	From this ECOSS Model, Sch. 2a, line 212	\$528,073
Alley Secondary Distributions Adjustment ⁽¹⁾		\$67,195
Alley Services Adjustment ⁽¹⁾		\$528,073
Total Alley Dusk to Dawn Adjustment		\$595,258
Notes:		
(1) Estimated Number of Connections	77,091 City Alley Lights	
	62 Suburban Alley Lights	
	13,239 City Controllers	
	78,900 Estimated Suburban Controllers	
	3,500 Suburban Metered Locations	

Base 2026 ECOSS
TAB: Alley D to D Adj

172,792 Estimated Total Connections

(2) This amount is transferred in this ECOSS Model, Sch. 2a, line 228.
(3) This amount is transferred in this ECOSS Model, Sch. 2a, line 230.

Commonwealth Edison Company		Base 2026 ECOS
Non Alley Lights Adjustment for The City of Chicago Lights		TAB: Non Alley D to D Adj
Estimated Actual Cost of Arterial and Residential Dusk to Dawn Lighting		
Item	Source	Amount
Arterial and Residential Dusk to Dawn Lighting	From Chicago Method D to D Lighting Tab, line 14	\$139,200
Total Using City of Chicago Method		\$139,200
ComEd Secondary Cost in ECOS		
Secondary Distribution Lines Costs in ECOS	From this ECOS Model, Sch. 2a, line 209	\$1,357,381
City Percent of Non Alley Lighting	ComEd 2014 Billed kWhs Data	73%
City Cost of Secondary Distribution Lines from ECOS	Total x City Percent	\$996,563
ComEd Service Drop Cost in ECOS		
Services Costs in ECOS	From this ECOS Model, Sch. 2a, line 212	\$654,600
Percent of Service Connections to City Controllers	Estimated Percent of Service Connections to City Controllers ⁽¹⁾	14%
City Non Alley Light Share of Services from ECOS	Total x Percent of Service Connections to City Controllers	\$91,644
Non Alley Secondary Distribution Adjustment ⁽²⁾		\$857,363

Base 2026 ECOSS
TAB: Non Alley D to D Adj

Non Alley Services Adjustment ⁽²⁾	\$91,644
Non Alley Total Chicago Dusk to Dawn Adjustment	\$949,007

Notes:

(1) Estimated Number of Connections		
	77,091	City Alley Lights
	62	Suburban Alley Lights
	13,239	City Controllers
	78,900	Estimated Suburban Controllers
	3,500	Suburban Metered Locations
	172,792	Estimated Total Connections
	95,639	Non Alley Total Connections
		14% Percent of Connections are to City of Chicago Controllers for Non Alley Lighting

(2) This amount is transferred in this ECOSS Model, Sch. 2a, line 224.
(3) This amount is transferred in this ECOSS Model, Sch. 2a, line 226.

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 155 of 580

Commonwealth Edison Company Base 2026 ECOS
 TAB: Chicago Method Alley Lighting
 Secondary Voltage Line Cost for City of Chicago Alley Dusk to Dawn Street Lighting

Item	Source	Amount	Computation
1 Cost per Foot of Wire	ComEd Plant Data Inside Chicago	\$3.29	
2 Total Number of Alley Lights	Provided from Billing System	77,091	
3 Total Feet	109 feet per alley light	8,402,919	109 * Line 2
4 Total Cost	Feet x Cost/Foot	\$27,645,603.51	Line 1 * Line 3
5 Apply a 2% Use Factor	City Initial Brief, page 22 in Docket No. 10-0467	\$552,912.07	0.02 * Line 4
6 Add a 5.88% factor to account for Intangible and General Plant	City Ex. 1.0, p 57, in Docket No. 10-0467	\$585,418.56	(1+0.0588) * Line 5
7 Accumulated Depreciation and ADIT Pct	City - Secondary	48.6%	
8 Rate Base (Total Cost x (1-Acc Dep & ADIT))	Cost x (1-Acc Dep & ADIT)	\$300,905.14	Line 6 * (1 - Line 7)
9 Rate Base and Gross Up Percent	From this ECOS Model, 2a, line 123	9.59%	
10 Return on Rate Base	Rate Base x Gross Up	\$28,862.04	Line 6 * Line 7
11 Depreciation Percent	City Ex. 1.0, p 57, in Docket No. 10-0467	2.87%	
12 Depreciation Expense	Cost x Dep Pct (line 5, X line 11)	\$15,868.58	Line 5 * Line 11
13 Add a 3.73% factor to account for O&M	City Ex. 1.0, p 57, in Docket No. 10-0467	\$21,811.20	0.0373 * Line 6

Base 2026 ECOS
TAB: Chicago Method Alley Lighting

14 City Alley Lighting Using City of Chicago Method ⁽¹⁾	Dep + Return on Rate Base	\$66,542	Line 10 + Line 12 + Line 13
--	---------------------------	----------	-----------------------------

Note:
(1) Transferred to the Alley D to D Adj Tab

December 2021 Snapshot of Chicago Dusk to Dawn Lights	
77,091	Alley Lights
269,939	Non Alley Lights
347,030	Total
77.8%	Percent Non Alley

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 157 of 580

Commonwealth Edison Company Base 2026 ECOS
 TAB: Chicago Method D to D Lighting
 Secondary Voltage Line Cost for City of Chicago Non Alley Dusk to Dawn Street Lighting

Item	Source	Amount	Computation
1 Cost per Foot of Wire	ComEd Plant Data Inside Chicago	\$2.48	
2 Total Number Controllers	Provided by City of Chicago	13,239	
3 Total Feet	113 feet per controller	1,425,156	113 * Line 2
4 Total Cost	Feet x Cost/Foot	\$3,534,386.88	Line 1 * Line 3
5 Apply a 33% Use Factor	City Ex. 1.0, p 57, in Docket No. 10-0467	\$1,166,347.67	0.33 * Line 4
6 Add a 5.88% factor to account for Intangible and General Plant	City Ex. 1.0, p 57, in Docket No. 10-0467	\$1,234,928.91	(1+0.0588) * Line 5
7 Accumulated Depreciation and ADIT Pct	City - Secondary	48.6%	
8 Rate Base (Total Cost x (1-Acc Dep & ADIT))	Cost x (1-Acc Dep & ADIT)	\$634,753.46	Line 5 * (1 - Line 7)
9 Rate Base and Gross Up Percent	From this ECOS Model, 2a, line 123	9.40%	
10 Return on Rate Base	Rate Base x Gross Up	\$59,662.61	Line 8 * Line 9
11 Depreciation Percent	City Ex. 1.0 in Docket No. 10-0467	2.87%	
12 Depreciation Expense	Cost x Dep Pct (line 5 X line 11)	\$33,474.18	Line 5 * Line 11
13 Add a 3.73% factor to account for O&M	City Ex. 1.0, p 57, in Docket No. 10-0467	\$46,062.85	0.0373 * Line 6

Base 2026 ECOSS
TAB: Chicago Method D to D Lighting

14	Total Using City of Chicago Method(1)	Dep + Return on Rate Base	\$139,200	Line 10 + Line 12 + Line 13
----	---------------------------------------	---------------------------	-----------	-----------------------------

Note:
(1) Transferred to the Non Alley D to D Adj Tab

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 159 of 580

Commonwealth Edison Company
Base 2026 ECOSS
TAB: Suburb Alley Lighting
Secondary Voltage Line Cost for Suburban Alley Dusk to Dawn Street Lighting

Item	Source	Amount	Computation
1 Cost per Foot of Wire	ComEd Plant Data Outside Chicago	\$2.33	
2 Total Number of Alley Lights	Provided from Survey	62	
3 Total Feet	109 feet per alley light	6,758	109 * Line 2
4 Total Cost	Feet x Cost/Foot	\$15,746.14	Line 1 * Line 3
5 Apply a 2% Use Factor	City Initial Brief, page 22 in Docket No. 10-0467	\$314.92	0.02 * Line 4
6 Add a 5.88% factor to account for Intangible and General Plant	City Ex. 1.0, p 57, in Docket No. 10-0467	\$333.44	(1+0.0588) * Line 5
7 Accumulated Depreciation and ADIT Pct	City - Secondary	48.6%	
8 Rate Base (Total Cost x (1-Acc Dep & ADIT)	Cost x (1-Acc Dep & ADIT)	\$171.39	Line 6 * (1 - Line 7)
9 Rate Base and Gross Up Percent	From this ECOSS Model, 2a, line 123	9.59%	
10 Return on Rate Base	Rate Base x Gross Up	\$16.44	Line 6 * Line 7
11 Depreciation Percent	City Ex. 1.0, p 57, in Docket No. 10-0467	2.87%	
12 Depreciation Expense	Cost x Dep Pct (line 5. X line 11)	\$9.04	Line 5 * Line 11

Base 2026 ECOSS
TAB: Suburb Alley Lighting

13 Add a 3.73% factor to account for O&M	City Ex. 1.0, p 57, in Docket No. 10-0467	\$12.42	0.0373 * Line 6
14 Suburban Alley Lighting Using City of Chicago Method ⁽¹⁾	Dep + Return on Rate Base	\$38	Line 10 + Line 12 + Line 13

Note:
(1) Transferred to the Alley D to D Adj Tab

December 2020 Snapshot of Suburban Unmetered Dusk to Dawn Lights
62 Alley Lights
157,800 Non Alley Lights

157,862 Total
100.0% Percent Non Alley

78,900 Estimated Number of Connections for Suburban Non Alley Lights
Using an Average of 2 per Connection (St Light database has
an average of 1.8 lights outside Chicago per CIMS entries)

3,500 Number of Meters in the Dusk to Dawn Delivery Class Outside Chicago

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 161 of 580

Base 2026 ECOS\$
TAB: WP High Voltage HV PS Split

High Voltage Delivery Class	Allocation	Up to 10,000 kW Total ⁽¹⁾	Up to 10,000 kW 60 kV and Above Service Points a	Up to 10,000 kW Primary Voltage Service Points b	Up to 10,000 kW Secondary Voltage Service Points c	Over 10,000 kW Total ⁽¹⁾	Over 10,000 kW 60 kV and Above Service Points d	Over 10,000 kW Primary Voltage Service Points e	Over 10,000 kW Secondary Voltage Service Points f	Primary Voltage Service Points g = b + d + e	Secondary Voltage Service Points h = c + f
Distribution Facilities Costs											
High Voltage SCS	HV Class	\$1,961,838	\$1,961,838	\$0	\$0	\$17,461,945	\$17,461,945	\$0	\$0	\$0	\$0
High Voltage Dist. Substations	CP 69kV & below	\$276,472	\$155,184	\$105,198	\$12,093	\$1,110,811	\$389,832	\$690,080	\$26,388	\$788,870	\$47,487
High Voltage Dist. Lines	CP ALL	\$267,483	\$212,657	\$54,826	\$0	\$6,610,108	\$6,179,877	\$439,739	\$11,178	\$625,108	\$16,369
Shared Distribution Substations (Over 60kV-4 kV		\$641	\$0	\$716	\$86	\$0	\$0	\$6,688	\$214	\$6,110	\$676
Shared Distribution Substations (Over 40kV-60kV		\$13,927	\$0	\$13,927	\$4,426	\$89,218	\$0	\$6,014	\$6,204	\$94,008	\$5,529
Secondary Voltage Dist. Substations	CP 60kV	\$0	\$0	\$0	\$0	\$12,877	\$0	\$0	\$0	\$12,877	\$0
Shared Distribution Lines (24 or Below 60kV-4 kV		\$18,789	\$0	\$17,849	\$2,240	\$122,037	\$0	\$116,124	\$8,873	\$134,263	\$6,614
Shared Distribution Lines (Over 40kV	CP 40kV	\$76,127	\$0	\$68,813	\$7,314	\$2,394,422	\$0	\$2,059,822	\$206,760	\$2,494,003	\$126,134
Secondary Voltage Dist. Lines	NCP 60kV LINE	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Primary Voltage Transformers	NCP 60kV TR	\$7,288	\$0	\$7,288	\$0	\$24,124	\$0	\$24,124	\$0	\$54,123	\$0
Secondary Voltage Transformers	NCP 60kV	\$66,342	\$0	\$66,342	\$0	\$66,342	\$0	\$66,342	\$0	\$66,342	\$0
Total prior to the allocation of distribution related uncertainties and revenue related costs	NCP 60kV	\$1,588,142	\$1,362,687	\$465,461	\$127,205	\$26,788,128	\$22,244,265	\$6,108,187	\$288,823	\$17,114,643	\$456,855
Revenue Related (Distribution)		\$12,000,000	\$12,177,777	\$7,110,000	\$1,000,000	\$166,400,000	\$168,120,000	\$12,000,000	\$2,000,000	\$162,120,000	\$6,100,000
Total Distribution Facilities Costs, including Transformer Costs		\$1,599,944	\$1,444,462	\$466,571	\$1,000,000	\$26,954,528	\$23,364,265	\$6,108,400	\$290,823	\$17,396,476	\$462,955
Transformer Costs		\$1,664,095	\$7,143			\$17,333,312	\$24,117			\$22,260	
Other Distribution Facilities Costs		\$279,315	\$661,032			\$4,721,914	\$6,081,083			\$6,023,216	
Allocation Factors⁽²⁾											
CP 69kV & below		12,120	6,978	4,612	530	46,802	17,090	30,278	1,352		
CP ALL		17,860	\$2,091	4,612	530	\$69,012	\$75,165	30,278	1,352		
CP 60kV		5,142	-	4,012	530	21,830	-	30,278	1,352		
NCP 60kV TR		2,052	-	1,268	1,761	1,175	-	4,261	7,090		
CP 40kV		5,145	-	4,012	530	21,830	-	30,278	1,352		

Notes:
(1) The distribution facilities costs are from Sch. 2a, Rows 241-251, of the ECOS\$ Model
(2) From Sch. 2b, Rows 4, 10, 13, 16, 18, 27, 28, 29 and 31 of the ECOS\$ Model

Page 162 of 580
Tab: WSP Investment Schedule - WSP

Category	Item	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100																							
Investment	WSP Investment	1000000	2000000	3000000	4000000	5000000	6000000	7000000	8000000	9000000	10000000	11000000	12000000	13000000	14000000	15000000	16000000	17000000	18000000	19000000	20000000	21000000	22000000	23000000	24000000	25000000	26000000	27000000	28000000	29000000	30000000	31000000	32000000	33000000	34000000	35000000	36000000	37000000	38000000	39000000	40000000	41000000	42000000	43000000	44000000	45000000	46000000	47000000	48000000	49000000	50000000	51000000	52000000	53000000	54000000	55000000	56000000	57000000	58000000	59000000	60000000	61000000	62000000	63000000	64000000	65000000	66000000	67000000	68000000	69000000	70000000	71000000	72000000	73000000	74000000	75000000	76000000	77000000	78000000	79000000	80000000	81000000	82000000	83000000	84000000	85000000	86000000	87000000	88000000	89000000	90000000	91000000	92000000	93000000	94000000	95000000	96000000	97000000	98000000	99000000	100000000

Docket No. 23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 1 of 31

Commonwealth Edison Company
Multi-Year Rate Plan 2024-2027
Billing Determinant Forecast
Documentation

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 2 of 31

Table of Contents

1	Forecast Models Overview	3
1.1	General Discussion of Method	3
2	Data Inputs and Model Variables	5
2.1	Data Inputs and Sources	5
2.2	Billing Determinants.....	5
2.3	Weather Data and Variables.....	5
2.4	Economic Variables and Economic Outlook	6
2.5	Energy Efficiency Variable.....	7
2.6	COVID-19 Variable.....	10
2.7	Binary Variables.....	11
2.8	Out-of-Model Adjustments	11
2.8.1	Rooftop Solar	11
2.8.2	Community Solar.....	16
2.8.3	Electric Vehicles.....	18
3	ComEd Forecast Models	20
3.1	Residential Forecast Models	20
3.1.1	Sales & Customers	20
3.2	Small C&I Forecast Models.....	21
3.2.1	Sales & Customers	21
3.2.2	Demand.....	22
3.3	Large C&I Forecast Models.....	22
3.3.1	Sales & Customers	22
3.3.2	Demand	23
3.4	Railroad Forecast Models	23
3.4.1	Sales and Customers	23
3.4.2	Demand	23
3.5	Streetlight Forecast Models.....	24
3.5.1	Sales and Customers	24
3.6	Delivery Service Class Forecasts.....	24
3.7	Zonal Forecasts	25
3.8	NSPL Forecasts	25
4	ComEd MRP Forecast.....	26
4.1	Results	26

Page 2 of 31

2024DCAI 0000034

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 3 of 31

4.1.1	ComEd Billing Determinants Summary	26
4.1.2	Delivery Service Class Sales Forecast.....	27
4.1.3	Delivery Service Class Customer Forecast.....	28
4.1.4	Delivery Service Class Billed Demand Forecast	30
5	Summary/Conclusion.....	31

1 Forecast Models Overview

1.1 General Discussion of Method

Commonwealth Edison Company ("the Company" or "ComEd") uses knowledge of economics, econometrics, understanding of electricity consumption and experience to model forecasts of billing determinants. There are three types of billing determinants that the Company forecasts: billed energy, billed demand and number of customers. The choice of method stems from the purpose of the forecasting exercise. The main goal in forecasting is to produce a reasonable outlook for the specified forecasting period. At the same time, the forecast needs to be prepared using reasonable assumptions based on basic economic theory and appropriate econometric tools. The goal of forecasting is to make sure the models perform within an acceptable range guided by the data and industry standards to produce forecasts within a reasonable range based on recent historical trends, the drivers of these historical trends, and expectations of how these trends and drivers may change in the future.

The choices the Company makes should be a healthy balance between theory and practice, leveraging the Company's experience to develop models and forecasts that have the best chance of being true. The methods used by the Company should also be within electric utility industry practices. . ComEd's forecasts are prepared by the Exelon Load Forecasting team that forecasts energy, customers and demand for the largest combined service territory in the U.S. by number of customers. ComEd's industry standard approaches are derived from the team's 50 years of experience in billing determinant forecasting. The Exelon Load Forecasting team collaborates to carefully review and evaluate each territory's load forecast, the underlying forecast assumptions and share best practices while considering differences at the jurisdictional level due to system specifics and regional economic differences across the six Exelon Utilities.

Generally, there are factors that impact the consumption of electricity, such as economics. These factors are sometimes called drivers since they are assumed to drive sales of electricity. Basic economic theory holds that the consumption of goods (such as electricity) typically depends on the state of the economy. Therefore, by using information on how economics has historically impacted electricity consumption, a forecaster can estimate a relationship between sales and economics and extend it into the future to predict future levels of sales. This describes a general approach on the example of economics, but it can be applied to any other billing determinant driver.

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 4 of 31

For the number of customers, the primary driver is the number of households in the area and overall economic activity. In general, as the number of households increases the number of customers is also expected to increase. In terms of sales, the most impactful drivers are weather, economic activity, energy efficiency ("EE") programs, solar adoption, and electric vehicle adoption. During atypical times like the recent COVID-19 pandemic new drivers may be introduced to reflect their impact on sales. Economic activity drivers are typically economic data that measure overall economic conditions in the area such as gross metro product ("GMP"), levels of total nonfarm employment and number of households. Lastly, billed demand is closely tied to energy sales and follows similar patterns, and so similar sales drivers are used to forecast billed demand.

Once historical data for the underlying billing determinants and their drivers are collected, a forecaster can use econometric/statistical tools to estimate the historical relationship between them. The whole process of identifying drivers, collecting data, estimating relationships, and testing is called modeling. A final model will consist of a set of drivers that explains underlying billing determinants according to theoretical assumptions about their impacts and statistical results. A forecaster with an understanding of basic econometrics, knowledge of electric utility load patterns, and experience in forecasting will be able to understand and estimate relationships between historical billing determinants and their drivers.

Once the relationships between billing determinants and their drivers are estimated, a forecaster can apply these relationships to the forecasted driver values and prepare the billing determinants for the forecast period. In a very simplified form, an illustration of the formula is below:

$$Billing\ Determinant = R_1D_1 + R_2D_2 + \dots + R_nD_n + \varepsilon,$$

where R is the estimated historical relationship with driver D , n is the number of estimated relationships/drivers, and ε is an error term. An error term (ε) is needed to capture any unknown or unobserved drivers since it is not possible to explain variances in billing determinants with absolute certainty. The above formula provides an example of how estimated relationships can be used to prepare the forecast as long as the future values of the drivers (D) are available.

The Company uses basic econometric regression analysis to estimate billing determinant relationships with certain drivers. A simple econometric regression is the approach of forming a relationship between the billing determinant (dependent variable) and the drivers (independent variables) through the application of statistical methods. Regression analysis allows the Company to check whether billing determinants have any relational response to an assumed driver. Using econometric tools is an empirical step of modeling where assumptions on drivers and their impacts are tested to produce reasonable results based on statistical measures. Evaluation of regression results for reasonableness is based on a knowledge of statistics, econometrics, experience, and information on the specific data.

The Company incorporates Out-of-Model adjustments ("OMAs") for some of its drivers. They are applied to the billing determinant forecasts after a forecast is conducted in a model based on the estimated driver relationships. In other words, the OMA procedure is the last step

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 5 of 31

before the final forecasts are put together. OMAs are used when empirical results do not produce statistically reasonable results. For example, the electric vehicle ("EV") and solar PV impact on sales have been very small historically and the regression models do not recognize their impact well. However, based on projections from the Exelon Strategy team, the EV and solar PV impact will be growing significantly in the future so it is likely they will be a larger driver on energy and demand in the long-term. Therefore, the Company uses an OMA to reflect the future EV and solar PV impact in the forecasts of sales. The OMA approach is a common practice and widely used across the industry and at other Exelon utilities.

2 Data Inputs and Model Variables

2.1 Data Inputs and Sources

Data inputs for ComEd billing determinant models are received from within the Company and from external vendors. This includes billed energy, billed demand, customer counts, economic drivers, weather, energy efficiency, solar PV, electric vehicles, and customer mobility (COVID-19). Below outlines the sources for the data used in the models.

- Billing Determinants: Billed Energy, Billed Demand, Customer Counts: ComEd Revenue Accounting/Retail Rates teams
- Economic Drivers: MSA¹ Level Data; IHS Markit
- Weather: O'Hare Airport Weather Station
- Energy Efficiency: ComEd Energy Efficiency Team
- Solar: Exelon Strategy Team
- Electric Vehicles: Exelon Strategy Team
- Customer Mobility (COVID-19): Institute of Health Metrics & Evaluation (IHME)

2.2 Billing Determinants

Historical billing determinants are the key input for the forecasting models. The Company maintains billing determinants for kilowatt-hour ("kWh") sales, customers (count of accounts) and demand (kW) by revenue class and delivery service class from billing records. For model estimation purposes, the Company generally used historical billing determinants from January 2008 through May 2022².

2.3 Weather Data and Variables

¹ ComEd service territory data from IHS includes Chicago-Naperville-Arlington Heights (Division of Chicago MSA), Elgin, IL (Division of Chicago MSA), Lake County-Kenosha County, IL-WI (Division of Chicago MSA), Kankakee, IL and Rockford, IL.

² Most recent month of billing determinant history is used at the time of the forecasting

Weather is a significant factor that explains fluctuations in sales across months, seasons, and years. The weather data for ComEd is represented by the weather data measured at O'Hare Airport, a weather station of the National Oceanic and Atmospheric ("NOAA"), and sourced from DTN. Primary data for building models is dry bulb temperature and humidity. ComEd's sales and demand models use two weather variables: Heating Degree Days ("HDD") and Cooling Degree Days incorporating humidity ("TDD"). HDD measures Heating Degree Days based on dry bulb temperature, while TDD measures Cooling Degree Days based on dry bulb temperature and incorporating humidity. The TDD variable includes both temperature and humidity giving it more explanatory power. Actual weather data used for the models goes through May 2022. Forecasted weather is assumed to be normal and is based on a rolling 30-year average. This forecast utilizes average weather experienced from 1992-2021 to define normal weather.

2.4 Economic Variables and Economic Outlook

Economic data is sourced from IHS Markit which collects historical data from government sources and provides forecasts for international, U.S., state, and metropolitan statistical areas ("MSA"). For the ComEd service territory, MSA level economic data are used which includes divisions of the Chicago MSA as well as the Kankakee, IL and Rockford, IL MSAs. The Company evaluates a total of six economic variables to explain energy, demand and customers. These variables are gross domestic product ("GDP"), gross metro product ("GMP"), manufacturing employment, non-manufacturing employment, households, and an average monthly bill, which is a measurement of a typical household electric bill in real terms. The May 2022 economic vintage was used for the ComEd forecast covering the 2024-2027 MRP period.

Table 4.6 shows annual GDP, GMP, manufacturing employment, non-manufacturing employment and households with historical and forecasted year over year growth. Compounding annual growth rates ("CAGR") for the historical (2017-2019) period and the 2021-2023 and 2024-2027 periods are calculated to show the changes of the underlying economics used in the models.

Table 4.6: Economic Drivers and Year over Year Change

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 7 of 31

Year	GDP	YOY % Change GDP	GMP	YOY % Change GMP	Manuf Emp	YOY % Change Manuf Emp	Non-Manuf Emp	YOY % Change Non- Manuf Emp	Households	YOY % Change Households
2008	15,647		549		470		3,976		3,381,024	
2009	15,222	-2.7%	530	-3.5%	414	-11.9%	3,795	-5.9%	3,384,239	0.1%
2010	15,593	2.4%	537	1.3%	402	-2.9%	3,764	-0.8%	3,382,264	-0.1%
2011	15,812	1.4%	546	1.7%	409	1.9%	3,813	1.3%	3,385,649	0.1%
2012	16,141	2.1%	559	2.3%	411	1.0%	3,879	1.7%	3,419,860	1.0%
2013	16,392	1.6%	559	0.1%	412	0.3%	3,949	1.8%	3,443,610	0.7%
2014	16,773	2.3%	571	2.1%	412	0.0%	4,019	1.7%	3,454,791	0.3%
2015	17,236	2.8%	585	2.4%	416	1.1%	4,101	2.0%	3,484,736	0.9%
2016	17,525	1.7%	587	0.3%	416	-0.1%	4,163	1.5%	3,510,360	0.7%
2017	17,933	2.3%	596	1.5%	417	0.3%	4,200	0.9%	3,523,604	0.4%
2018	18,446	2.9%	611	2.0%	424	1.7%	4,232	0.8%	3,565,765	1.2%
2019	18,870	2.3%	617	1.0%	424	-0.2%	4,257	0.6%	3,585,388	0.6%
2020	18,224	-3.4%	583	-5.6%	402	-5.1%	3,938	-7.5%	3,564,701	-0.6%
2021	19,258	5.7%	614	5.3%	401	-0.1%	4,032	2.3%	3,589,130	0.7%
2022	19,728	2.4%	627	2.2%	416	3.7%	4,203	4.2%	3,600,942	0.3%
2023	20,199	2.4%	638	1.8%	419	0.7%	4,219	0.4%	3,605,805	0.1%
2024	20,687	2.4%	649	1.6%	420	0.3%	4,207	-0.3%	3,615,749	-0.3%
2025	21,158	2.3%	658	1.4%	419	-0.3%	4,204	-0.1%	3,627,388	0.3%
2026	21,696	2.5%	669	1.8%	417	-0.5%	4,223	0.4%	3,640,416	0.4%
2027	22,260	2.6%	683	2.1%	416	-0.2%	4,263	0.9%	3,655,406	0.4%
2016-2019		2.5%		1.7%		0.6%		0.7%		0.7%
2020-2023		3.5%		3.1%		1.4%		2.3%		0.4%
2024-2027		2.5%		1.7%		-0.3%		0.4%		0.4%

GDP/GMP: Millions \$

Employment: Thousands

2.5 Energy Efficiency Variable

EE data used in the forecast models reflect energy savings from both Company and external EE programs, and also includes behavioral programs like the ComEd Home Energy Report. The EE data are provided to the Load Forecasting team by the Company's Energy Efficiency team and reflect cumulative EE savings over time. Energy savings targets for Company EE programs are based on cumulative persisting annual savings ("CPAS"), which is defined as the total electric energy savings in a given year from measures installed in that year or in previous years, but no earlier than January 1, 2012, that are still operational and providing savings in that year because the measures have not yet reached the end of their useful lives.

The EE savings data is broken out by revenue class (Residential, Small C&I, Large C&I and Streetlight) and used directly in the aforementioned revenue class sales models as well as Small C&I and Large C&I billed demand models as independent variables. Given the size and long history of ComEd EE programs, the models have strong statistical relationships with an energy efficiency series and does well to explain the general decline in energy and demand observed over the last decade. Residential cumulative EE savings is expected to increase 0.1% per year from 2024-2027, while Small C&I and Large C&I cumulative EE savings are expected to increase

3.9% and 1.4% per year, respectively, over that same period. Streetlight cumulative EE savings is expected to increase 1.1% per year from 2024-2027. Figures 4.7 below highlight the historical and forecasted cumulative annual savings by revenue class:

Figure 4.7a: Cumulative Residential Energy Efficiency Savings



Figure 4.7b: Cumulative Small C&I Energy Efficiency Savings

Docket No.23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 9 of 31




Figure 4.7c: Cumulative Large C&I Energy Efficiency Savings





Figure 4.7c: Cumulative Streetlight Energy Efficiency Savings



2.6 COVID-19 Variable

In March 2020, states across the country issued a “Stay at Home” order in response to the COVID-19 pandemic. This impacted usage by significantly reducing Commercial and Industrial sales as businesses shutdown and increasing Residential sales as work activity rapidly shifted from the office to the home. The Company includes a COVID-19 variable directly into the sales models as an independent variable to capture this impact. It is included in the Residential, Small C&I, Large C&I and Railroad econometric sales models. The COVID-19 variable is represented by average customer mobility in Illinois. Data is from the Institute of Health Metrics and Evaluation (“IHME”) which uses cell phone data to track an individual’s movement and compare it to a pre-COVID baseline. The data represents a percentage-based deviation from pre-COVID levels (0 on y-axis in figure below). The COVID-19 recovery pattern is based on service territory employment returning to pre-pandemic levels. The COVID-19 variable incorporates a level of “new normal” based on the impacts of COVID-19. In some cases, if a statistically significant fit could not be found with mobility, the Company utilized simple binary/shift variables for periods beginning in 2020 to help explain variances from the pandemic in the billing determinants. Figure 4.8 shown below highlights the pattern in mobility:


Figure 4.8: Illinois Average Mobility

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 11 of 31



2.7 Binary Variables

Most models contain a number of monthly binary variables. A binary variable in the Company's regressions is a categorical variable that takes a value of one for a specified period or date and zero, otherwise. It is an "indicator" variable that is used to mark off certain observations based on a specified criterion. Binary variables are best described as variables that take the value of 0 or 1 to indicate the absence or presence of some categorical effect that might be expected to shift the outcome. An example of binary variables used regularly in the Company's models are monthly (January-December) binary variables used to help explain non-weather related patterns in the billing determinants from month to month or season to season.

2.8 Out-of-Model Adjustments

When certain load impacts cannot be econometrically modeled through the inclusion of independent variables, the Company uses Out-of-Model Adjustments (OMAs) to reflect these impacts on load. These adjustments are impacts from electric vehicles, solar PV and professional judgement.

2.8.1 Rooftop Solar

The impacts of rooftop solar on load are incorporated into the forecast through OMAs. Solar OMAs are used to account for the estimated reduction of sales from installed rooftop solar on a Residential and Small/Large Commercial & Industrial basis. Community solar, while a significant portion of the total solar PV on the system, is not assumed to impact load (billed

Page 11 of 31

2024DCAI 0000043

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 12 of 31

energy/demand) at the revenue class level due to being "outside-the-meter" while rooftop solar is considered "behind-the-meter" and thus a direct reduction to the billed energy and demand at the home or business. Community solar however does impact the Company's projections for energy and peak demand of the ComEd Zone which is discussed in more detail in section 2.8.2 and 3.7. Current estimates for Residential rooftop solar generation in 2022 are about 330 GWh which represents about 1% of annual Residential energy sales but expected to reach roughly 3% by 2027. Small C&I and Large C&I rooftop solar generation is estimated around 148 GWh each in 2022 which represents approximately 0.5% of their annual energy sales and expected to increase to about 1.2% by 2027.

Forecasted energy sales and demand are adjusted by subtracting expected new rooftop solar generation/capacity based on Solar PV forecasts from the Exelon Strategy team. The Solar PV forecast is constructed using a System Dynamics model with various inputs to project future growth of rooftop installations. The two main inputs to their solar PV System Dynamics model are actual rooftop installations sourced from the Company's Net Metering program data and the economics of adopting solar. The inputs to quantify the economics of adopting solar can be divided into subcategories including: bill impacts as a solar vs. non-solar customer, costs of installation, customer growth and segmentation (i.e. number of single-family vs. multi-family homes), and current legislation and policy (i.e. Renewable Energy Credits (SREC) and tax credits). Before an updated solar PV forecast is incorporated as an OMA in the final billing determinant forecast, ComEd utilizes a popular industry tool called PVWatts Calculator from the National Renewable Energy Laboratory ("NREL") which helps convert an annual forecast to monthly, hourly and on/off-peak periods. PVWatts also adds a level of precision in the final billing determinant forecast with respect to the weather as it considers the impact of weather experienced throughout the year on solar generation in the ComEd service territory. Figures 4.9 below highlight the historical and forecasted rooftop solar capacity and generation by revenue class:

Docket No.23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 13 of 31

Figure 4.9a: Residential Rooftop Solar Capacity





Figure 4.9b: Residential Rooftop Solar Generation



Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 14 of 31

Figure 4.9c: Small C&I Rooftop Solar Capacity





Figure 4.9d: Small C&I Rooftop Solar Generation



Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 15 of 31

Figure 4.9e: Large C&I Rooftop Solar Capacity





Figure 4.9f: Large C&I Rooftop Solar Generation

Docket No. 23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 16 of 31



2.8.2 Community Solar

The impacts of community solar on sales are incorporated into the forecast through OMAs. As mentioned in section 2.8.1, community solar is only a reduction to sales at the Zone level. Due to the nature of community solar projects being "outside-the-meter," the revenue class billing determinants are not reduced by community solar but do reduce the Company's forecasts for Zone sales. Thus, the Zone energy and peak demand forecasts are reduced by both rooftop and community solar projections. Figures 4.10 below highlight the historical and forecasted community solar capacity and generation:

Figure 4.10e: Community Solar Capacity

Docket No.23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 17 of 31





Figure 4.10b: Community Solar Generation

Docket No.23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 18 of 31



2.8.3 Electric Vehicles

The impacts of Electric Vehicles ("EV") on sales are incorporated into the forecast through OMAs. Forecasted energy sales and demand are adjusted by adding expected new Battery Electric Vehicle ("BEV") and Plug-In Hybrid Vehicle ("PHEV") sales in the ComEd service territory. There is a relatively small sales impact historically that does not go back far enough to be included into forecasts econometrically. The ComEd EV forecast is prepared by the Exelon Strategy team and is based on a System Dynamics model with various inputs to project future sales of EV. These inputs include: historical adoption for BEV, PHEV, and Gas combustion vehicles, technology improvements (i.e. fuel efficiency, range, battery capacity, etc.), charging infrastructure, electricity pricing, legislation and policy, etc. The EV forecast is further broken down into Residential and Commercial EV sales to incorporate into the Residential and Small C&I billed energy and demand forecasts by adding expected new BEV and PHEV sales into the underlying modeled forecast.

Current estimates for Residential electric vehicle energy sales in 2022 are about 100 GWh which represents roughly 0.4% of annual Residential energy sales but projected to reach 480 GWh or 1.8% by 2027. Commercial electric vehicle energy sales in 2022 is estimated to be around 35 GWh which represents just 0.1% of annual Small C&I energy sales but projected to reach 160 GWh or about 0.6% by 2027. Figures 4.11 highlight the historical and forecasted number of EV and associated Residential and Commercial energy sales:

Docket No.23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 19 of 31

Figure 4.11a: Total Electric Vehicles (BEV and PHEV)




Figure 4.11b: Residential EV Charging Sales (BEV and PHEV)





Figure 4.11c: Commercial EV Charging Sales (BEV and PHEV)



3 ComEd Forecast Models

3.1 Residential Forecast Models

3.1.1 Sales & Customers

The Residential class is comprised of approximately 3.7 million customers. The Residential billed energy forecast is based on a monthly econometric model with the dependent variable specified as electric usage per customer per day. The independent variables included in the model are monthly binaries, seasonal HDD and TDD, energy efficiency, an average real monthly bill, mobility and a shift-plus binary variable for periods after 2017. Weather variables based on Residential weather splines capture seasonal weather variations on Residential energy sales. The EE variable is used to account for the significant decline in customer use over time largely driven by energy efficiency gains. A pricing component is included in the model as a 12-month moving average customer bill amount in real terms as higher bills tend to drive lower usage and vice-versa. The mobility variable is included to help capture the COVID-19 pandemic

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 21 of 31

impact as less mobility drives higher usage at the home. The shift-plus binary variable for periods after 2017 is included to help capture a slight downward trend in usage starting in 2018 that is not attributed to energy efficiency. The model is estimated over the January 2008 - May 2022 period using an ordinary least squares ("OLS") regression.

The Residential energy model has an Adjusted R-Squared of 0.994, meaning the model can explain over 99% of the historical monthly variance in Residential energy going back to 2008. The model's Mean Absolute Percent Error ("MAPE") is 1.27%, meaning on average the model's prediction has a monthly variance of 1.27% in absolute terms compared to the actual Residential energy.

The Residential customer forecast is based on a year-over-year growth analysis of historical customer growth. Residential customer growth has historically moved fairly closely to growth in the number of households in the ComEd service territory. From 2016-2019 ComEd Residential customers grew approximately 0.8% per year while households over that same period grew 0.7% per year. Household projections are sourced from IHS Markit and help guide predictions for Residential customer growth in the future.

3.2 Small C&I Forecast Models

3.2.1 Sales & Customers

The Small C&I class is comprised of approximately 390,000 customers. The Small C&I billed energy forecast is based on a monthly econometric model with the dependent variable specified as electric usage per day. The independent variables included in the model are monthly binaries, HDD and TDD, a TDD trend, economics, a delayed bill variable, energy efficiency and mobility. Weather variables based on Small C&I weather splines capture weather variations and trends on Small C&I sales. The economic variable is a composite variable that combines non-manufacturing employment and GMP for the ComEd service territory into a single variable. These are weighted in the composite variable based on their individual coefficients evaluated in the model. The delayed bill variable captures historical monthly variances due to delays in billing customers. The EE variable is used to account for the decline in customer use over time from growing EE savings in C&I classes. The mobility variable is included to help capture the COVID-19 pandemic impact as less mobility drives lower usage at the business. The model is estimated over the January 2008 - May 2022 period using an OLS regression.

The Small C&I energy model has an Adjusted R-Squared of 0.968, meaning the model can explain almost 97% of the historical monthly variance in Small C&I energy going back to 2008. The model's MAPE is 1.16%, meaning on average the model's prediction has a monthly variance of 1.16% in absolute terms compared to the actual Small C&I energy.

The Small C&I customer forecast is based on a year-over-year growth analysis of historical customer growth. Small C&I customer growth has been consistent with Residential customer growth historically. Typically, more Residential customers brings more businesses to an area and thus the forecasts are evaluated together and compared against household

projections. From 2016-2019 ComEd Small C&I customers grew approximately 1% per year while Residential customers grew 0.8%.

3.2.2 Demand

The Small C&I billed demand forecast is based on a monthly econometric model with the dependent variable specified as total demand. The independent variables included in the model are monthly binaries, HDD and TDD, economics, energy efficiency and binary variables. Weather variables based on Small C&I weather splines capture monthly weather variations for summer months and seasonal weather variations for spring and fall on Small C&I demand. The economic variable is the same composite variable used in the Small C&I billed energy model. The EE variable is used to account for the decline in customer demand over time from growing EE savings in C&I classes. Two year-month binary variables for May and June 2020 are used to smooth out variances in those periods from COVID-19 impacts. The model is estimated over the January 2008 - December 2021 period using an OLS regression.

The Small C&I demand model has an Adjusted R-Squared of 0.974, meaning the model can explain over 97% of the historical monthly variance in Small C&I demand going back to 2008. The model's MAPE is 1.01%, meaning on average the model's prediction has a monthly variance of 1.01% in absolute terms compared to the actual Small C&I demand.

3.3 Large C&I Forecast Models

3.3.1 Sales & Customers

The Large C&I class is comprised of approximately 1,900 customers. The Large C&I billed energy forecast is based on a monthly econometric model with the dependent variable specified as usage per day. The independent variables included in the model are monthly binaries, HDD and TDD, economics, a delayed bill variable, energy efficiency and mobility. Weather variables based on Large C&I weather splines capture weather variations on Large C&I sales. The economic variable is a composite variable that combines manufacturing employment and GMP for the ComEd service territory as well as GDP into a single variable. These are weighted in the composite variable based on their individual coefficients evaluated in the model. The delayed bill variable captures historical monthly variances due to delays in billing customers. The EE variable is used to account for the decline in customer use over time from growing EE savings in C&I classes. The mobility variable is included to help capture the COVID-19 pandemic impact as less mobility drives lower usage at the business. The model is estimated over the December 2007 - May 2022 period using an OLS regression.

The Large C&I energy model has an Adjusted R-Squared of 0.854, meaning the model can explain over 85% of the historical monthly variance in Large C&I energy going back to 2008. The model's Mean Absolute Percent Error (MAPE) is 2.15%, meaning on average the model's prediction has a monthly variance of 2.15% in absolute terms compared to the actual Large C&I energy.

Docket No.23- _____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page **23** of **31**

The Large C&I customer forecast is based on a year-over-year growth analysis of historical customer growth. Large C&I customer growth is not tied to a specific economic metric, however economic projections for the service territory are considered in the evaluation of the forecast. The class typically hovers around 2,000 customers historically.

3.3.2 Demand

The Large C&I billed demand forecast is based on a monthly econometric model with the dependent variable specified as total demand. The independent variables included in the model are monthly binaries, HDD and TDD, economics, energy efficiency and a shift-plus binary variable. Weather variables based on Large C&I weather splines capture monthly weather variations for summer months and seasonal weather variations for spring and fall on Large C&I demand. The economic variable is the same composite variable used in the Large C&I billed energy model. The EE variable is used to account for the decline in customer demand over time from growing EE savings in C&I classes. The shift-plus binary variable is used to capture the lower demands observed in 2020 forward from COVID-19 impacts. The model is estimated over the January 2012 - December 2021 period using an OLS regression.

The Large C&I demand model has an Adjusted R-Squared of 0.918, meaning the model can explain over 91% of the historical monthly variance in Large C&I demand going back to 2012. The model's MAPE is 1.23%, meaning on average the model's prediction has a monthly variance of 1.23% in absolute terms compared to the actual Large C&I demand.

3.4 Railroad Forecast Models

3.4.1 Sales and Customers

The Railroad class is comprised of 2 customers - Chicago Transit Authority and Metra. The Railroad billed energy forecast is based on a monthly econometric model with the dependent variable specified as usage per day. The independent variables included in the model are monthly binaries, HDD, an HDD trend, economics, and shift-plus binary variables. Weather variables based on Railroad weather splines capture weather variations and trends in heating months on Railroad sales. The economic variable is non-manufacturing employment for the ComEd service territory. The shift-plus binary variables are included to help capture variations over those periods as well as the COVID-19 pandemic impact to usage from 2020 forward. The model is estimated over the April 2007 - May 2022 period using an OLS regression.

The number of Railroad customers are not forecasted as there are only two customers in the service territory - the Chicago Transit Authority and Metra.

3.4.2 Demand

Page **23** of **31**

2024DCAI 0000055

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 24 of 31

The Railroad billed demand forecast is based on a monthly econometric model with the dependent variable specified as total demand. The independent variables included in the model are monthly binaries, HDD, economics, a time trend and shift-plus binary variables. Weather variables based on Railroad weather splines capture weather variations and trends in heating months on Railroad demand. The economic variable is non-manufacturing employment for the ComEd service territory. The time trend variable is included to capture the overall decline in Railroad demand observed over time. The shift-plus binary variables are included to help capture variations over those periods as well as the COVID-19 pandemic impact to usage from 2020 forward. The model is estimated over the April 2007 - May 2022 period using an OLS regression.

The Railroad demand model has an Adjusted R-Squared of 0.911, meaning the model can explain over 91% of the historical monthly variance in Railroad demand going back to 2008. The model's MAPE is 2.96%, meaning on average the model's prediction has a monthly variance of 2.96% in absolute terms compared to the actual Railroad demand.

3.5 Streetlight Forecast Models

3.5.1 Sales and Customers

The Streetlight class is comprised of approximately 6,800 customers. The Streetlight billed energy forecast is based on a monthly econometric model with the dependent variable specified as usage per day. The independent variables included in the model are monthly binaries, delayed bills, energy efficiency and a shift-plus binary variable. Lighting classes are not considered to be weather-sensitive and thus weather variables are not utilized. The delayed bill variable captures historical monthly variances due to delays in billing customers. The EE variable is used to account for the decline in customer use over time from EE savings in lighting. The shift-plus binary variable is included to help capture variations over those periods. The model is estimated over the January 2006 - May 2022 period using an ordinary least squares OLS regression.

The Streetlight customer forecast is based on a year-over-year growth analysis of historical customer growth.

3.6 Delivery Service Class Forecasts

Forecasts are constructed at the revenue class level and then divided into delivery service classes using an allocation process. The allocation process is similar across billing determinants, where individual delivery service classes are evaluated as a percentage of their total revenue class based on recent history and projections for the future. Allocations for billed energy, demand and customers are carefully evaluated and adjusted to reflect recent trends and changes in delivery service class share across the revenue classes (Residential, Small C&I, Large

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 25 of 31

C&I and Streetlight. Note: Railroad does not have delivery service classes). Delivery service class forecast results can be found in more detail in sections 4.1.2-4.1.4.

3.7 Zonal Forecasts

Forecasts for Zonal energy are based on a monthly econometric model with the dependent variable specified as total Zonal energy. The independent variables included in the model are monthly binaries, a weekend/holiday variable, HDD and TDD, economics and energy efficiency. Weather variables based on Zonal weather splines capture seasonal weather variations on Zonal sales. The weekend/holiday variable is included to capture the generally lower Zonal usage on weekends and holidays. The economic variable is a composite variable that combines total nonfarm employment, households and GMP for the ComEd service territory as well as GDP into a single variable. These are weighted in the composite variable based on their individual coefficients evaluated in the model. The EE variable is used to account for the significant decline in Zonal usage over time largely driven by energy efficiency gains. The model is estimated over the December 2007 - May 2022 period using an OLS regression. The final Zonal energy forecast includes adjustments for rooftop/community solar and electric vehicle charging sales and made via OMAs to account for these driver impacts on Zonal usage.

Forecasts for Zonal peak demand are constructed using an historical load factor approach where Zonal energy and demand are evaluated together. The Zonal peak demand forecast is based on the Zonal energy model described above where a projected load factor is applied to the modeled Zonal energy to derive a single hourly system peak demand. Adjustments for rooftop/community solar and electric vehicle charging sales are made via OMAs to account for these driver impacts on the Zonal peak. Assumptions around peak timing as it compares to peak solar and EV output are also considered when making OMAs for Zonal peak forecasts. Zonal peak demand forecasts are based on a 50/50 weather-normal scenario using the average weather experienced from 1992-2021.

3.8 NSPL Forecasts

Forecasts for Network Service Peak Load contributions ("NSPL") are based on the Zonal peak demand forecast described above in section 3.7. The forecasted Zonal peak demand is divided into delivery service class shares using an allocation process. The allocation process uses historical delivery service class NSPL, which is sourced from the ComEd Energy Acquisition team, to calculate an average annual percentage share. The delivery service class percentage share is multiplied by the Zonal peak forecast and then divided by that delivery service class's forecasted average customer count over the June-August period for each forecast year to calculate an average annual MW/customer. The average annual MW/customer is then multiplied by the delivery service class's customer forecast for each month of the forecast period to produce monthly delivery service class NSPL. The NSPL forecast is based on a 50/50 weather-normal scenario using the average weather experienced from 1992-2021.

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 26 of 31

4 ComEd MRP Forecast

Prior sections above describe the models, data inputs and transformation, and any adjustments made outside of the models. Below, discusses the results of the billing determinants and compares 2024-2027 trends relative to pre-COVID trends.

4.1 Results

ComEd total billed energy sales are projected to decline (0.1%) annually over the 2024-2027 period versus the pre-COVID pace (2016-2019) of approximately (0.4%) on a weather-normal basis. The 2024-2027 sales decline is driven by economic and customer growth (increasing sales) offset by continued adoption of energy efficiency (lowering sales). Compared to pre-COVID trends, similar economic growth (GMP forecasted to grow 1.7% per year from 2024-2027) is expected while customer growth slows from 0.8% per year pre-COVID to 0.4% over 2024-2027 consistent with household trends. This is offset by energy efficiency savings with impacts easing compared to pre-COVID impacts. All forecasted energy sales statistics noted in section 4 include a leap-year adjustment for 2024 which raises growth rates by approximately 0.1% over the forecast period.

4.1.1 ComEd Billing Determinants Summary

Residential billed energy growth is expected to increase a modest 0.1% annually from 2024-2027 versus pre-COVID declines of (0.4%) per year due to increases in electric vehicle adoption and less energy efficiency savings. **Customers** are expected to grow 0.4% per year from 2024-2027 versus 0.8% per year pre-COVID consistent with household growth projections of approximately 0.4% per year over that same period.

Small Commercial & Industrial billed energy sales are expected to decline (0.8%) annually over the 2024-2027 period consistent with pre-COVID declines of (0.8%) annually. Sales declines over the forecast period are driven by a weaker non-manufacturing employment outlook for the ComEd service territory as well as moderation in customer growth offset partially by less impact from energy efficiency savings versus pre-COVID levels. Non-manufacturing employment grew 0.7% per year from 2016-2019 and is expected to slow to 0.4% annually over 2024-2027. **Customers** are expected to grow 0.5% per year from 2024-2027 versus 1% annually pre-COVID consistent with slowing economic growth in the MRP period vs pre-COVID trends

Small Commercial & Industrial billed demand growth is consistent with the assumptions and expectations for billed energy sales over the 2024-2027 period. Billed demand is expected to decline (0.8%) annually over the forecast period.

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 27 of 31

Large Commercial & Industrial billed energy sales over 2024-2027 are expected to increase 0.5% annually compared to pre-COVID declines of (0.2%) annually. This is mostly driven by the extended COVID-19 recovery for this class after significant customer losses over 2020-2021. Billed energy levels are not expected to reach pre-COVID levels until 2025. **Customers** are expected be flat overall from 2024-2027 versus pre-COVID declines of (0.3%) annually as the class mostly recovers from COVID-19 driven customer losses over the next few years.

Large Commercial & Industrial billed demand growth is consistent with the assumptions and expectations for billed energy sales over the 2024-2027 period. Billed demand is expected to increase 0.3% annually over the forecast period.

Railroad billed energy sales are expected to increase slightly 0.1% annually over 2024-2027 as the class continues to recover from COVID-19 impacts. This is a modest growth expectation compared to pre-COVID growth of 0.8% annually but consistent with the slowing growth in non-manufacturing employment over 2024-2027 in the ComEd service territory.

Railroad billed demand growth is consistent with the assumptions and expectations for billed energy sales over the 2024-2027 period however billed demand is expected to decrease (0.2%) annually over the forecast period as the modest growth expectations for non-manufacturing employment is offset by expectations for lower demands as the class expands investments in energy efficiency.

Streetlight billed energy sales are expected to decline (0.7%) annually over 2024-2027 versus (6.6%) annually pre-COVID from less energy efficiency savings expected in the forecast period. **Customers** are expected to increase slightly about 0.1% annually over 2024-2027.

4.1.2 Delivery Service Class Sales Forecast

Docket No.23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page 28 of 31

Delivery Service Class	Sales Growth (%)				
	2024	2025	2026	2027	'24 - '27 CAGR
Single Family	1.2%	0.0%	0.0%	0.3%	0.1%
Multi-Family	1.7%	0.5%	0.5%	0.9%	0.6%
Single Family with Space Heat	0.7%	-0.8%	-0.6%	-0.9%	-0.8%
Multi-Family with Space Heat	0.8%	-0.8%	-0.6%	-0.9%	-0.8%
WattHour	-5.1%	-5.2%	-3.3%	-3.7%	-4.1%
0-100 kW	-0.6%	-1.6%	0.6%	-0.7%	-0.5%
100-400 kW	-1.0%	-1.9%	0.3%	-1.0%	-0.9%
400-1,000 kW	-1.1%	-2.0%	0.2%	-1.1%	-1.0%
1-10 MW	0.7%	-0.3%	1.3%	0.1%	0.4%
10 MW+	1.0%	0.0%	1.5%	0.4%	0.6%
High Voltage and 10,000 kW or Less	1.1%	0.0%	1.6%	0.4%	0.7%
High Voltage and > 10,000 kW	1.1%	0.0%	1.6%	0.5%	0.7%
Railroad	0.4%	-0.6%	0.4%	0.7%	0.1%
Dusk to Dawn Lighting	-1.6%	-0.7%	-1.0%	-1.0%	-0.9%
Fixture Included Lighting	-0.7%	-0.1%	-0.4%	-0.4%	-0.3%
General Lighting	-0.7%	-0.1%	-0.4%	-0.4%	-0.3%
Residential	1.2%	0.0%	0.0%	0.3%	0.1%
Small C&I	-0.9%	-1.8%	0.3%	-0.9%	-0.8%
Large C&I	0.8%	-0.2%	1.4%	0.3%	0.5%
C&I	-0.1%	-1.0%	0.9%	-0.3%	-0.2%

4.1.3 Delivery Service Class Customer Forecast

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 191 of 580

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 29 of 31

Delivery Service Class	Customer Growth (%)				
	2024	2025	2026	2027	'24 - '27 CAGR
Single Family	0.3%	0.3%	0.3%	0.3%	0.3%
Multi-Family	0.6%	0.6%	0.6%	0.6%	0.6%
Single Family with Space Heat	-0.1%	-0.1%	-0.1%	-0.1%	-0.1%
Multi-Family with Space Heat	0.0%	0.0%	0.0%	0.0%	0.0%
WattHour	-4.2%	-3.8%	-3.4%	-3.1%	-3.5%
0-100 kW	1.8%	1.6%	1.5%	1.4%	1.5%
100-400 kW	0.4%	0.4%	0.5%	0.5%	0.4%
400-1,000 kW	0.4%	0.4%	0.5%	0.5%	0.5%
1-10 MW	1.8%	0.7%	-0.3%	-0.3%	0.0%
10 MW+	0.0%	0.0%	0.0%	0.0%	0.0%
High Voltage and 10,000 kW or Less	3.4%	0.0%	0.0%	0.0%	0.0%
High Voltage and > 10,000 kW	0.0%	0.0%	0.0%	0.0%	0.0%
Railroad	0.0%	0.0%	0.0%	0.0%	0.0%
Dusk to Dawn Lighting	0.0%	0.0%	0.0%	0.0%	0.0%
Fixture Included Lighting	0.2%	0.1%	0.1%	0.1%	0.1%
General Lighting	0.0%	0.0%	0.0%	-0.1%	0.0%
Residential	0.4%	0.4%	0.4%	0.4%	0.4%
Small C&I	0.5%	0.5%	0.5%	0.5%	0.5%
Large C&I	1.8%	0.7%	-0.3%	-0.3%	0.0%
C&I	0.5%	0.5%	0.5%	0.5%	0.5%

Docket No.23-_____

ComEd Ex. 17.06

MRP 2024-2027 Billing Determinant Forecast Documentation

Page 30 of 31

4.1.4 Delivery Service Class Billed Demand Forecast

Delivery Service Class	Billed Demand Growth (%)				
	2024	2025	2026	2027	'24 - '27 CAGR
0-100 kW	-2.2%	-2.2%	0.8%	-0.9%	-0.8%
100-400 kW	-2.2%	-2.2%	0.8%	-0.9%	-0.8%
400-1,000 kW	-2.2%	-2.2%	0.8%	-0.9%	-0.8%
1-10 MW	-0.2%	-0.2%	1.1%	0.1%	0.3%
10 MW+	-0.2%	-0.2%	1.1%	0.1%	0.3%
High Voltage and 10,000 kW or Less	-0.2%	-0.2%	1.1%	0.1%	0.3%
High Voltage and > 10,000 kW	-0.2%	-0.2%	1.1%	0.1%	0.3%
Railroad	-0.2%	-0.2%	-0.2%	-0.2%	-0.2%
Small C&I	-2.2%	-2.2%	0.8%	-0.9%	-0.8%
Large C&I	-0.2%	-0.2%	1.1%	0.1%	0.3%
C&I	-1.4%	-1.4%	0.9%	-0.5%	-0.3%

Docket No.23-_____
ComEd Ex. 17.06
MRP 2024-2027 Billing Determinant Forecast Documentation
Page **31** of **31**

5 Summary/Conclusion

This documentation provides detailed explanations of ComEd's forecasting and modeling approach and underlying data inputs. The Company's industry standard methodology has supported the ComEd planning for many years and is appropriate for use in rate setting in MRP proceeds. The results described above present a reasonable MRP forecast covering 2024-2027 for use in ComEd planning acknowledging the history of ComEd billing determinants, changes due to the unprecedented impacts of COVID and reasonable MRP projections on clearly documented and transparent forecast assumptions.

Commonwealth Edison Company				Docket No.23-
Billing Units				ComEd Ex. 17.07
				Forecasted Billing Units
				Tab: Residential
Residential Delivery Service	2024 Forecasted Billing Units (1)	2025 Forecasted Billing Units (1)	2026 Forecasted Billing Units (1)	2027 Forecasted Billing Units (1)
Single Family Without Electric Space Heat				
Customer Charge	27,877,197	27,960,829	28,044,711	28,128,845
Standard Metering Service Charge	27,877,197	27,960,829	28,044,711	28,128,845
Distribution Facilities Charge (kWh)	20,055,740,094	20,002,249,942	19,999,831,970	20,066,400,213
Illinois Electricity Distribution Tax Charge (kWh)	20,055,740,094	20,002,249,942	19,999,831,970	20,066,400,213
Multi Family Without Electric Space Heat				
Customer Charge	14,602,157	14,689,771	14,777,909	14,866,575
Standard Metering Service Charge	14,602,157	14,689,771	14,777,909	14,866,575
Distribution Facilities Charge (kWh)	5,031,503,822	5,043,131,445	5,069,608,708	5,113,473,934
Illinois Electricity Distribution Tax Charge (kWh)	5,031,503,822	5,043,131,445	5,069,608,708	5,113,473,934
Single Family With Electric Space Heat				
Customer Charge	423,802	423,526	423,250	422,974
Standard Metering Service Charge	423,802	423,526	423,250	422,974
Distribution Facilities Charge (kWh)	674,744,649	667,354,357	663,052,043	656,980,973
Illinois Electricity Distribution Tax Charge (kWh)	674,744,649	667,354,357	663,052,043	656,980,973
Multi Family With Electric Space Heat				
Customer Charge	2,000,949	2,000,462	1,999,975	1,999,487
Standard Metering Service Charge	2,000,949	2,000,462	1,999,975	1,999,487
Distribution Facilities Charge (kWh)	1,578,936,429	1,561,991,266	1,551,959,797	1,537,313,815
Illinois Electricity Distribution Tax Charge (kWh)	1,578,936,429	1,561,991,266	1,551,959,797	1,537,313,815
Total Residential kWh	27,340,924,995	27,274,727,010	27,284,452,518	27,374,168,935
Residential Delivery Service Notes:				
(1) Based on historical billing units which do not include customer growth adjustment.				

Commonwealth Edison Company
Billing Units

Docket No.25
ComEd Ex. 17-27
Forecasted Billing Units
Tab: Nonresidential

Nonresidential Delivery Service	2024 Forecasted Billing Units (2)	2025 Forecasted Billing Units (2)	2026 Forecasted Billing Units (2)	2027 Forecasted Billing Units (2)
WATT-HOUR				
Customer Charge	920,712	900,022	880,220	861,882
Standard Metering Service Charge	955,772	950,012	885,232	841,992
Distribution Facilities Charge (kW)	238,894,287	210,792,151	200,652,571	289,511,997
Illinois Electricity Distribution Tax Charge (kW)	328,894,287	310,792,151	300,652,571	289,511,997
SMALL LOAD (0-200 kW)				
Customer Charge	1,181,885	1,006,497	1,081,815	1,711,246
Standard Metering Service Charge	1,261,885	1,006,497	1,081,815	1,711,246
Secondary Voltage Distribution Facilities Charge (kW)	32,285,527	31,382,588	31,640,293	31,397,897
Primary Voltage Distribution Facilities Charge (kW)	36,397	55,113	95,586	55,070
Primary Voltage Transformer Charge (kW)	18,524	18,122	18,205	16,149
Illinois Electricity Distribution Tax Charge (kW)	10,688,525,838	10,502,820,541	10,588,885,136	10,497,254,673
MEDIUM LOAD (Over 200 kW < 400 kW)				
Customer Charge	193,272	194,041	194,919	195,887
Standard Metering Service Charge	193,272	194,041	194,919	195,887
Secondary Voltage Distribution Facilities Charge (kW)	23,241,276	22,731,475	22,848,361	22,744,488
Primary Voltage Distribution Facilities Charge (kW)	490,171	480,717	476,264	476,382
Primary Voltage Transformer Charge (kW)	300,393	293,897	298,210	293,482
Illinois Electricity Distribution Tax Charge (kW)	9,247,702,746	9,046,564,596	9,071,793,039	9,980,313,938
LARGE LOAD (Over 400 kW < 1,000 kW)				
Customer Charge	47,128	47,268	47,576	47,779
Standard Metering Service Charge	47,128	47,268	47,576	47,779
Secondary Voltage Distribution Facilities Charge (kW)	18,115,128	17,813,591	18,086,161	17,895,381
Primary Voltage Distribution Facilities Charge (kW)	838,954	818,612	825,369	818,611
Primary Voltage Transformer Charge (kW)	683,722	594,693	598,129	594,576
Illinois Electricity Distribution Tax Charge (kW)	8,131,132,387	8,004,370,724	8,017,218,774	7,927,859,325
VERY LARGE LOAD (Over 1,000 kW < 10,000 kW)				
Customer Charge	21,981	22,113	22,942	21,974
Standard Metering Service Charge	21,981	22,113	22,942	21,974
Secondary Voltage Distribution Facilities Charge (kW)	28,126,824	28,097,773	28,373,098	28,410,448
Primary Voltage Distribution Facilities Charge (kW)	9,828,712	9,810,946	9,811,882	9,824,551
Primary Voltage Transformer Charge (kW)	5,121,074	5,141,627	5,185,985	5,203,223
Illinois Electricity Distribution Tax Charge (kW)	10,351,70,324	11,077,028,282	11,071,127,682	17,029,729,121
EXTRA LARGE LOAD (Over 10,000 kW)				
Customer Charge	528	528	528	528
Standard Metering Service Charge	528	528	528	528
Secondary Voltage Distribution Facilities Charge (kW)	2,297,128	2,293,024	2,317,279	2,300,497
Primary Voltage Distribution Facilities Charge (kW)	4,483,881	4,474,707	4,521,942	4,528,398
Primary Voltage Transformer Charge (kW)	1,548,186	1,540,002	1,558,279	1,560,482
Illinois Electricity Distribution Tax Charge (kW)	1,942,440,479	1,929,973,705	1,986,813,382	4,008,720,885
HIGH VOLTAGE (0)				
Customer Charge	1,176	1,176	1,176	1,176
Standard Metering Service Charge	1,176	1,176	1,176	1,176
Secondary Voltage Distribution Facilities Charge (kW)	30,150	30,089	30,388	30,429
Primary Voltage Distribution Facilities Charge (kW)	303,326	303,861	303,698	303,820
High Voltage Distribution Facilities Charge 0-10 MW (kW)	933,895	817,138	824,275	826,164
High Voltage Distribution Facilities Charge Over 10 MW (kW)	9,012,881	8,984,080	9,088,640	9,131,822
Primary Voltage Transformer Charge (kW)	40,845	40,802	41,294	41,352
High Voltage Transformer Charge 0-10 MW (kW)	180,168	184,761	188,184	189,421
High Voltage Transformer Charge Over 10 MW (kW)	8,404,688	8,391,139	8,458,811	8,467,711
Illinois Electricity Distribution Tax Charge (kW)	6,461,924,698	6,446,179,923	6,546,079,058	6,576,944,525
RAILROAD				
Customer Charge	24	24	24	24
Standard Metering Service Charge	24	24	24	24
Distribution Facilities Charge (kW)	1,118,722	1,116,494	1,114,261	1,112,023
Illinois Electricity Distribution Tax Charge (kW)	492,497,222	492,499,284	492,499,284	492,504,448
Total Nonresidential kWh	56,192,205,641	56,501,466,176	56,022,872,076	56,824,674,354

Nonresidential Delivery Service Notes:
(2) Based on forecasted billing units which do not include customer growth adjustment.

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 196 of 580

		2026 Forecasted Billing Units		2026 Forecasted Billing Units		2026 Forecasted Billing Units		2027 Forecasted Billing Units	
		Actual Number of Components	Weighted Number of Components for Allocation	Actual Number of Components	Weighted Number of Components for Allocation	Actual Number of Components	Weighted Number of Components for Allocation	Actual Number of Components	Weighted Number of Components for Allocation
Lighting Delivery Service (2)									
Fixture Included Lighting									
Public Street Lighting									
LED 40-60 Watt		1,286,400	1,286,712	1,286,400	1,286,712	1,286,400	1,286,712	1,286,400	1,286,712
LED 80-100 Watt		122,532	122,532	122,532	122,532	122,532	122,532	122,532	122,532
LED 80-119 Watt		26,736	61,836	26,736	61,836	26,736	61,836	26,736	61,836
LED 120-160 Watt (3,000 Lumens)		28,612	28,612	28,612	28,612	28,612	28,612	28,612	28,612
LED 120-160 Watt (3,000 Lumens)		2,544	13,152	2,544	13,152	2,544	13,152	2,544	13,152
LED Color Head 270-360 Watt		2,500	2,500	2,500	2,500	2,500	2,500	2,500	2,500
LED Flood 40-60 Watt		180	60,480	180	60,480	180	60,480	180	60,480
LED Access 40-60 Watt		96	12,096	96	12,096	96	12,096	96	12,096
MV - 100 Watt		3,180	0	3,180	0	3,180	0	3,180	0
MV - 175 Watt		42,384	0	42,384	0	42,384	0	42,384	0
MV - 250 Watt		4,360	0	4,360	0	4,360	0	4,360	0
MV - 400 Watt		7,080	0	7,080	0	7,080	0	7,080	0
HPS - 150 Watt		26	0	26	0	26	0	26	0
HPS - 100 Watt		26,424	0	26,424	0	26,424	0	26,424	0
HPS - 150 Watt		96,696	0	96,696	0	96,696	0	96,696	0
HPS - 250 Watt		28,008	0	28,008	0	28,008	0	28,008	0
HPS - 400 Watt		10,008	0	10,008	0	10,008	0	10,008	0
HPS - 1,000 Watt		72	0	72	0	72	0	72	0
All HPS and MV - Post Top		60,180	0	60,180	0	60,180	0	60,180	0
Equipment		12,168	0	12,168	0	12,168	0	12,168	0
Bracket < 8 ft		653,316	653,316	653,316	653,316	653,316	653,316	653,316	653,316
Bracket Over 8 ft		947,844	947,844	947,844	947,844	947,844	947,844	947,844	947,844
Private Outdoor Lighting									
LED 40-60 Watt		4,704	131,724	4,704	131,724	4,704	131,724	4,704	131,724
LED 80-100 Watt		2,932	2,932	2,932	2,932	2,932	2,932	2,932	2,932
LED 70-100 Watt (Flood)		4,968	172,644	4,968	172,644	4,968	172,644	4,968	172,644
LED 100-130 Watt (Flood)		10,272	10,272	10,272	10,272	10,272	10,272	10,272	10,272
MV - 175 Watt		97,320	0	97,320	0	97,320	0	97,320	0
MV - 400 Watt		26,204	0	26,204	0	26,204	0	26,204	0
HPS (Flood) - 100 Watt		24,336	0	24,336	0	24,336	0	24,336	0
HPS (Flood) - 250 Watt		118,864	0	118,864	0	118,864	0	118,864	0
HPS (Conv.) - 100 Watt		5,364	0	5,364	0	5,364	0	5,364	0
HPS (Conv.) - 100 Watt		17,160	0	17,160	0	17,160	0	17,160	0
Retro-reflective Distribution Tax Charge (RTR)		76,234,080	76,234,080	76,234,080	76,234,080	76,234,080	76,234,080	76,234,080	76,234,080
Dark to Dawn Lighting									
Standard Metering Service Charge Non-Ally (MW)		348,000,498	348,000,498	348,000,498	348,000,498	348,000,498	348,000,498	348,000,498	348,000,498
Standard Metering Service Charge Ally (MW)		23,543,852	23,543,852	23,543,852	23,543,852	23,543,852	23,543,852	23,543,852	23,543,852
Distribution Facilities Charge Non-Ally (MW)		348,000,498	348,000,498	348,000,498	348,000,498	348,000,498	348,000,498	348,000,498	348,000,498
Distribution Facilities Charge Ally (MW)		23,543,852	23,543,852	23,543,852	23,543,852	23,543,852	23,543,852	23,543,852	23,543,852
Retro-reflective Distribution Tax Charge (RTR)		371,550,350	371,550,350	371,550,350	371,550,350	371,550,350	371,550,350	371,550,350	371,550,350
General Lighting									
Standard Metering Service Charge (MW)		76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080
Distribution Facilities Charge (MW)		76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080
Retro-reflective Distribution Tax Charge (RTR)		76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080	76,288,080
Total Lighting kWh		524,071,280	524,071,280	519,858,336	519,858,336	515,646,812	515,646,812	511,436,104	511,436,104
Total Company kWh		84,147,024,718	84,147,024,718	83,948,083,521	83,948,083,521	83,823,071,209	83,823,071,209	83,700,279,372	83,700,279,372
Lighting Delivery Service Notes:									
(2) The component count was adjusted for the conversion of Mercury Vapor and High Pressure Sodium components to Light Emitting Diode (LED) Components.									

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 197 of 580

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Docket No. 23-_____
ComEd Ex. 17.08
Tab: 2024 WN CPs/NCPs

2018 Weather Normalized (3 to 4 PM)	CP-ALL	% of Total	NCP-69 KV	% of Total
Residential(1)	9,232,163	45.6%	10,513,387	48.7%
Nonresidential(2)	11,006,311	54.4%	11,070,467	51.3%
Total	20,238,474	100.0%	21,583,854	100.0%

	2024 Allocation CP-ALL ⁽¹⁾ 3 pm to 4 pm	% of Total	2024 Allocation NCP-69 KV ⁽²⁾	% of Total	Weather Normal CP-ALL 3 pm to 4 pm	% of Total	Weather Normal NCP-69 KV	% of Total
	(a)		(b)		(c)		(d)	
Single Family Without Electric Space Heat ⁽³⁾	7,701,468	38.3%	7,799,104	37.7%	7,476,428	36.9%	8,051,700	37.3%
Multi Family Without Electric Space Heat ⁽³⁾	1,491,418	7.4%	1,537,653	7.4%	1,447,838	7.2%	1,587,454	7.4%
Single Family With Electric Space Heat ⁽¹⁾	102,636	0.5%	241,285	1.2%	99,637	0.5%	249,100	1.2%
Multi Family With Electric Space Heat ⁽³⁾	214,529	1.1%	605,521	2.9%	208,260	1.0%	625,133	2.9%
Total Residential	9,510,051	47.3%	10,183,563	49.2%	9,232,163	45.6%	10,513,387	48.7%
Watt-Hour ⁽⁶⁾	62,107	0.3%	62,485	0.3%	64,724	0.32%	66,179	0.31%
Small Load (0 to 100 kW) ⁽⁶⁾	2,621,754	13.0%	2,665,729	12.9%	2,732,240	13.50%	2,823,336	13.08%
Medium Load (Over 100 to 400 kW) ⁽⁶⁾	2,099,701	10.4%	2,193,509	10.6%	2,188,187	10.8%	2,323,197	10.8%
Large Load (Over 400 to 1000 kW) ⁽⁶⁾	1,687,001	8.4%	1,759,879	8.5%	1,758,095	8.7%	1,863,929	8.6%
Very Large Load (Over 1,000 to 10,000 kW) ⁽⁶⁾	2,832,228	14.1%	2,943,857	14.2%	2,951,584	14.6%	3,117,378	14.4%
Extra Large Load (Over 10,000 kW) ⁽⁷⁾	580,248	2.9%	594,293	2.9%	580,248	2.9%	594,293	2.8%
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾	37,965	0.2%	7,944	0.0%	37,965	0.2%	7,944	0.0%
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾	608,012	3.0%	34,059	0.2%	608,012	3.0%	34,059	0.2%
Fixture-Included Lighting ⁽⁷⁾	200	0.0%	19,892	0.1%	200	0.0%	19,892	0.09%
Dark to Dawn Lighting ⁽⁷⁾	864	0.0%	96,143	0.5%	864	0.0%	96,143	0.45%
General Lighting ⁽⁷⁾	9,303	0.0%	9,303	0.0%	9,303	0.0%	9,303	0.0%
Railroad ⁽⁷⁾⁽⁹⁾	74,890	0.4%	114,814	0.6%	74,890	0.4%	114,814	0.5%
Nonresidential	10,614,273	52.7%	10,501,408	50.8%	11,006,312	54.4%	11,070,468	51.3%
Total	20,124,324	100.0%	20,684,971	100.0%	20,238,475	100.0%	21,583,855	100.0%

Docket No. 23-_____
ComEd Ex. 17.08
Tab: 2024 WN CPs/NCPs

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

	2024 Allocation		2024 Allocation		Weather Normal		Weather Normal	
	CP-ALL ^(b)	% of Total	NCP-69 KV ^(b)	% of Total	CP-ALL	% of Total	NCP-69 KV	% of Total
	3 pm to 4 pm				3 pm to 4 pm			
	(a)		(b)		(c)		(d)	
Secondary Voltage Service Points Only								
Small Load (0 to 100 kW) ^(a)	2,619,351		2,663,250		2,729,736		2,820,711	
Medium Load (Over 100 to 400 kW) ^(a)	2,075,015		2,168,216		2,162,461		2,296,408	
Large Load (Over 400 to 1000 kW) ^(a)	1,623,035		1,693,040		1,691,433		1,793,138	
Very Large Load (Over 1,000 to 10,000 kW)	2,176,899		2,240,916		2,268,638		2,373,406	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾	193,463		204,374		193,463		204,374	
High Voltage (Up to 10,000 kW) ^{(7)(b)}	530		1,754		530		1,754	
High Voltage (Over 10,000 kW) ^{(7)(b)}	1,552		2,795		1,552		2,795	
Primary Voltage Service Points with ComEd Transformers								
Small Load (0 to 100 kW) ⁽⁷⁾	721		1,020		751		1,081	
Medium Load (Over 100 to 400 kW) ^(a)	15,774		16,623		16,439		19,725	
Large Load (Over 400 to 1000 kW) ^(a)	28,701		31,652		29,911		33,523	
Very Large Load (Over 1,000 to 10,000 kW)	388,757		413,230		405,140		437,662	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾	137,671		141,383		137,671		141,383	
High Voltage (Up to 10,000 kW) ^{(7)(b)}	27		1,298		27		1,298	
High Voltage (Over 10,000 kW) ^{(7)(b)}	4,306		4,381		4,306		4,381	
High Voltage CP 69KV & below								
High Voltage (Up to 10,000 kW) ^{(7)(b)}	12,120				12,120			
High Voltage (Over 10,000 kW) ^{(7)(b)}	48,920				48,920			
CP < 69 kV								
High Voltage (Up to 10,000 kW) ^{(7)(b)}	5,142				5,142			
High Voltage (Over 10,000 kW) ^{(7)(b)}	31,830				31,830			

- Notes:
- All of the notes below are consistent with the allocation from the 2022 FRU (22-0302) work paper but with adjustments from the Watt-Hour/Small Load and Lighting Adjustments tabs.
- (1) The weather normal CP-ALL load is the sum of the residential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest single demand for each delivery class in 2021.
- (2) The weather normal CP-ALL load is the sum of the nonresidential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest individual customer class hourly loads in 2018 for the portion of the loads delivered at voltages below 69 kV.
- (3) The loads under column (a) are the hourly loads of individual classes on August 24, 2021 for the hour between 3 pm and 4 pm, reflecting ComEd's system peak hour from 2018.
- (4) The loads under column (b) are the highest individual customer class hourly loads in 2021 for the portion of the loads delivered at voltages below 69 kV.
- (5) The loads under columns (c) and (d) for the residential classes are determined by allocating the totals described in Note (1) to the classes based on the loads shown in columns (a) and (b), respectively.
- (6) The loads under columns (c) and (d) for the smaller nonresidential classes up to the Very Large Load are determined from total nonresidential described in Note (2) after removing the loads for the larger customer classes and lighting classes shown in columns (a) and (b) respectively, and allocating the rest to these smaller nonresidential classes based on the loads shown in columns (a) and (b), respectively.
- (7) The loads for these classes shown in columns (a) and (b) are the same as the loads for these classes shown in columns (c) and (d), respectively.
- (8) Loads presented do not include the Zero Standard Portion described in Rider ZSS - Zero Standard Service.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 200 of 580

Docket No. 23-_____

ComEd Ex. 17.08

Tab: 2024 NCP-SEC LINE

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Commonwealth Edison Company
The Determination of Non-coincident Demands by Customer Class
for Customers Taking Service at Secondary Voltages Distribution Lines (NCP-SEC LINE)

	Class Noncoincident Peak Demand for Load < 69 kV (NCP < 69 kV) in kW ⁽¹⁾	% of Customers Not Taking Service from Secondary Distribution Lines ⁽²⁾	% of Customers Taking Service from Secondary Distribution Lines	NCP-SEC LINE in kW ⁽²⁾
	(A)	(B)	(C) = 1 - (B)	(D) = (A) * (C)
<u>Residential</u>				
1 2024 Allocation	8,051,700	2.3%	97.7%	7,866,511
2 Multi Family Without Electric Space Heat	1,587,454	18.2%	81.8%	1,298,537
3 Single Family With Electric Space Heat	249,160	18.7%	81.3%	202,518
4 Multi Family With Electric Space Heat	625,133	18.2%	81.8%	511,359
Total Residential	10,513,387			9,878,925
<u>Nonresidential</u>				
5 Watt-Hour	66,179	6.5%	93.5%	61,877
6 Small Load (0 to 100 kW)	2,823,336	13.9%	86.1%	2,430,892
7 Medium Load (Over 100 to 400 kW)	2,323,197	83.8%	16.4%	381,004
8 Large Load (Over 400 to 1000 kW)	1,863,929	100.0%	0.0%	-
9 Very Large Load (Over 1,000 to 10,000 kW)	3,117,378	100.0%	0.0%	-
10 Extra Large Load (Over 10,000 kW)	594,293	100.0%	0.0%	-
11a. High Voltage Up to 10 MW	7,944	100.0%	0.0%	-
11b. High Voltage Over 10 MW	34,059	100.0%	0.0%	-
12 Fixture-Included Lighting	19,892	1.4%	98.6%	19,614
13 Dunk to Dawn Lighting	96,143	1.4%	98.6%	94,797
14 General Lighting	9,303	1.4%	98.6%	9,173
15 Railroad	114,814	100.0%	0.0%	-
Total Nonresidential	11,070,468			2,997,357
Total	21,583,855			12,876,282

Notes:

(1) Transferred from column (d) on the WN CPs/NCPs page.

(2) From a "Estimated Percent of Customers That Do Not Receive Service from the Secondary Distribution System" work paper.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 201 of 580

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Docket No. 23-_____
ComEd Ex. 17.08
Tab: 2025 WN CPs/NCPs

2018 Weather Normalized (3 to 4 PM)	CP-ALL	% of Total	NCP-69 KV	% of Total
Residential(1)	9,232,163	45.6%	10,513,387	48.7%
Nonresidential(2)	11,006,311	54.4%	11,070,467	51.3%
Total	20,238,474	100.0%	21,583,854	100.0%

	2025 Allocation CP-ALL ⁽¹⁾ 3 pm to 4 pm	% of Total	2025 Allocation NCP-69 KV ⁽²⁾	% of Total	Weather Normal CP-ALL 3 pm to 4 pm	% of Total	Weather Normal NCP-69 KV	% of Total
	(a)		(b)		(c)		(d)	
Single Family Without Electric Space Heat ⁽³⁾	7,701,468	38.3%	7,799,104	37.7%	7,476,428	36.9%	8,051,700	37.3%
Multi Family Without Electric Space Heat ⁽³⁾	1,491,418	7.4%	1,537,653	7.4%	1,447,838	7.2%	1,587,454	7.4%
Single Family With Electric Space Heat ⁽¹⁾	102,636	0.5%	241,285	1.2%	99,637	0.5%	249,100	1.2%
Multi Family With Electric Space Heat ⁽³⁾	214,529	1.1%	605,521	2.9%	208,260	1.0%	625,133	2.9%
Total Residential	9,510,051	47.3%	10,183,563	49.2%	9,232,163	45.6%	10,513,387	48.7%
Watt-Hour ⁽⁶⁾	59,388	0.3%	59,766	0.3%	61,890	0.31%	63,305	0.29%
Small Load (0 to 100 kW) ⁽⁶⁾	2,624,473	13.0%	2,668,448	12.9%	2,735,074	13.51%	2,826,477	13.10%
Medium Load (Over 100 to 400 kW) ⁽⁶⁾	2,099,701	10.4%	2,193,509	10.6%	2,188,187	10.8%	2,323,411	10.8%
Large Load (Over 400 to 1000 kW) ⁽⁶⁾	1,687,001	8.4%	1,759,879	8.5%	1,758,095	8.7%	1,864,101	8.6%
Very Large Load (Over 1,000 to 10,000 kW) ⁽⁶⁾	2,832,228	14.1%	2,943,357	14.2%	2,951,584	14.6%	3,117,666	14.4%
Extra Large Load (Over 10,000 kW) ⁽⁷⁾	580,248	2.9%	594,293	2.9%	580,248	2.9%	594,293	2.8%
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾	37,965	0.2%	7,944	0.0%	37,965	0.2%	7,944	0.0%
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾	608,012	3.0%	34,059	0.2%	608,012	3.0%	34,059	0.2%
Fixture-Included Lighting ⁽⁷⁾	200	0.0%	19,818	0.1%	200	0.0%	19,818	0.09%
Dark to Dawn Lighting ⁽⁷⁾	864	0.0%	95,274	0.5%	864	0.0%	95,274	0.44%
General Lighting ⁽⁷⁾	9,303	0.0%	9,303	0.0%	9,303	0.0%	9,303	0.0%
Railroad ⁽⁷⁾⁽⁹⁾	74,890	0.4%	114,814	0.6%	74,890	0.4%	114,814	0.5%
Nonresidential	10,614,273	52.7%	10,500,465	50.8%	11,006,312	54.4%	11,070,466	51.3%
Total	20,124,324	100.0%	20,684,028	100.0%	20,238,475	100.0%	21,583,853	100.0%

Docket No. 23-
ComEd Ex. 17.08
Tab: 2023 WN CPs/NCPs

The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)
Commonwealth Edison Company

2025 Allocation CP-ALL ^(b) 3 pm to 4 pm (a)		2025 Allocation NCP-69 KV ^(b) % of Total		Weather Normal CP-ALL 3 pm to 4 pm (c)		Weather Normal NCP-69 KV % of Total	
Secondary Voltage Service Points Only		(b)		(c)		(d)	
Small Load (0 to 100 kW) ^(a)		2,622,070		2,665,970		2,823,852	
Medium Load (Over 100 to 400 kW) ^(a)		2,075,015		2,162,461		2,296,620	
Large Load (Over 400 to 1000 kW) ^(a)		1,623,035		1,691,433		1,793,304	
Very Large Load (Over 1,000 to 10,000 kW)		2,176,899		2,240,916		2,373,626	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾		193,463		204,374		204,374	
High Voltage (Up to 10,000 kW) ^{(7)(b)}		530		530		1,754	
High Voltage (Over 10,000 kW) ^{(7)(b)}		1,552		1,552		2,795	
Primary Voltage Service Points with ComEd Transformers							
Small Load (0 to 100 kW) ⁽⁷⁾		721		751		1,081	
Medium Load (Over 100 to 400 kW) ^(a)		15,774		16,623		19,726	
Large Load (Over 400 to 1000 kW) ^(a)		28,701		31,652		33,526	
Very Large Load (Over 1,000 to 10,000 kW)		388,757		413,230		437,702	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾		137,671		141,383		141,383	
High Voltage (Up to 10,000 kW) ^{(7)(b)}		27		1,298		1,298	
High Voltage (Over 10,000 kW) ^{(7)(b)}		4,306		4,306		4,381	
High Voltage CP 69KV & below							
High Voltage (Up to 10,000 kW) ^{(7)(b)}		12,120		12,120			
High Voltage (Over 10,000 kW) ^{(7)(b)}		48,920		48,920			
CP < 69 kV							
High Voltage (Up to 10,000 kW) ^{(7)(b)}		5,142		5,142			
High Voltage (Over 10,000 kW) ^{(7)(b)}		31,830		31,830			

- Notes:
- All of the notes below are consistent with the allocation from the 2022 FRU (22-0302) work paper but with adjustments from the Watt-Hour/Small Load and Lighting Adjustments tabs.
- (1) The weather normal CP-ALL load is the sum of the residential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest single demand for each delivery class in 2021.
- (2) The weather normal CP-ALL load is the sum of the nonresidential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest individual customer class hourly loads in 2018 for the portion of the loads delivered at voltages below 69 kV.
- (3) The loads under column (a) are the hourly loads of individual classes on August 24, 2021 for the hour between 3 pm and 4 pm, reflecting ComEd's system peak hour from 2018.
- (4) The loads under column (b) are the highest individual customer class hourly loads in 2021 for the portion of the loads delivered at voltages below 69 kV.
- (5) The loads under columns (c) and (d) for the residential classes are determined by allocating the totals described in Note (1) to the classes based on the loads shown in columns (a) and (b), respectively.
- (6) The loads under columns (c) and (d) for the smaller nonresidential classes up to the Very Large Load are determined from total nonresidential described in Note (2) after removing the loads for the larger customer classes and lighting classes shown in columns (a) and (b) respectively, and allocating the rest to these smaller nonresidential classes based on the loads shown in columns (a) and (b), respectively.
- (7) The loads for these classes shown in columns (a) and (b) are the same as the loads for these classes shown in columns (c) and (d), respectively.
- (8) Loads presented do not include the Zero Standard Portion described in Rider ZSS - Zero Standard Service.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 204 of 580

Docket No. 23-_____

ComEd Ex. 17.08

Tab: 2025 NCP-SEC LINE

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Commonwealth Edison Company
The Determination of Non-coincident Demands by Customer Class
for Customers Taking Service at Secondary Voltages Distribution Lines (NCP-SEC LINE)

	Class Noncoincident Peak Demand for Load < 69 kV (NCP < 69 kV) in kW ⁽¹⁾	% of Customers Not Taking Service from Secondary Distribution Lines ⁽²⁾	% of Customers Taking Service from Secondary Distribution Lines	NCP-SEC LINE in kW ⁽²⁾
	(A)	(B)	(C) = 1 - (B)	(D) = (A) * (C)
<u>Residential</u>				
1 Single Family Without Electric Space Heat	8,051,700	2.3%	97.7%	7,866,511
2 Multi Family Without Electric Space Heat	1,587,454	18.2%	81.8%	1,298,537
3 Single Family With Electric Space Heat	249,160	18.7%	81.3%	202,518
4 Multi Family With Electric Space Heat	625,133	18.2%	81.8%	511,359
Total Residential	10,513,387			9,878,925
<u>Nonresidential</u>				
5 Watt-Hour	63,305	6.5%	93.5%	59,190
6 Small Load (0 to 100 kW)	2,826,477	13.9%	86.1%	2,433,597
7 Medium Load (Over 100 to 400 kW)	2,323,411	83.8%	16.4%	381,039
8 Large Load (Over 400 to 1000 kW)	1,864,101	100.0%	0.0%	-
9 Very Large Load (Over 1,000 to 10,000 kW)	3,117,666	100.0%	0.0%	-
10 Extra Large Load (Over 10,000 kW)	594,293	100.0%	0.0%	-
11a. High Voltage Up to 10 MW	7,944	100.0%	0.0%	-
11b. High Voltage Over 10 MW	34,059	100.0%	0.0%	-
12 Fixture-Included Lighting	19,818	1.4%	98.6%	19,541
13 Dunk to Dawn Lighting	95,274	1.4%	98.6%	93,940
14 General Lighting	9,303	1.4%	98.6%	9,173
15 Railroad	114,814	100.0%	0.0%	-
Total Nonresidential	11,070,466			2,996,480
Total	21,583,853			12,875,405

Notes:

(1) Transferred from column (d) on the WN CPs/NCPs page.

(2) From a "Estimated Percent of Customers That Do Not Receive Service from the Secondary Distribution System" work paper.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 205 of 580

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Docket No. 23-_____
ComEd Ex. 17.08
Tab: 2026 WN CPs/NCPs

2018 Weather Normalized (3 to 4 PM)	CP-ALL	% of Total	NCP-69 KV	% of Total
Residential(1)	9,232,163	45.6%	10,513,387	48.7%
Nonresidential(2)	11,006,311	54.4%	11,070,467	51.3%
Total	20,238,474	100.0%	21,583,854	100.0%

	2026 Allocation CP-ALL ⁽¹⁾ 3 pm to 4 pm (a)	% of Total	2026 Allocation NCP-69 KV ⁽²⁾ (b)	% of Total	Weather Normal CP-ALL 3 pm to 4 pm (c)	% of Total	Weather Normal NCP-69 KV (d)	% of Total
Single Family Without Electric Space Heat ⁽³⁾	7,701,468	38.3%	7,799,104	37.7%	7,476,428	36.9%	8,051,700	37.3%
Multi Family Without Electric Space Heat ⁽³⁾	1,491,418	7.4%	1,537,653	7.4%	1,447,838	7.2%	1,587,454	7.4%
Single Family With Electric Space Heat ⁽¹⁾	102,636	0.5%	241,285	1.2%	99,637	0.5%	249,100	1.2%
Multi Family With Electric Space Heat ⁽³⁾	214,529	1.1%	605,521	2.9%	208,260	1.0%	625,133	2.9%
Total Residential	9,510,051	47.3%	10,183,563	49.2%	9,232,163	45.6%	10,513,387	48.7%
Watt-Hour ⁽⁶⁾	57,049	0.3%	57,427	0.3%	59,453	0.29%	60,834	0.28%
Small Load (0 to 100 kW) ⁽⁶⁾	2,626,812	13.1%	2,670,787	12.9%	2,737,511	13.53%	2,829,216	13.11%
Medium Load (Over 100 to 400 kW) ⁽⁶⁾	2,099,701	10.4%	2,193,509	10.6%	2,188,187	10.8%	2,323,626	10.8%
Large Load (Over 400 to 1000 kW) ⁽⁶⁾	1,687,001	8.4%	1,759,879	8.5%	1,758,095	8.7%	1,864,274	8.6%
Very Large Load (Over 1,000 to 10,000 kW) ⁽⁶⁾	2,832,228	14.1%	2,943,357	14.2%	2,951,584	14.6%	3,117,955	14.4%
Extra Large Load (Over 10,000 kW) ⁽⁷⁾	580,248	2.9%	594,293	2.9%	580,248	2.9%	594,293	2.8%
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾	37,965	0.2%	7,944	0.0%	37,965	0.2%	7,944	0.0%
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾	608,012	3.0%	34,059	0.2%	608,012	3.0%	34,059	0.2%
Fixture-Included Lighting ⁽⁷⁾	200	0.0%	19,744	0.1%	200	0.0%	19,744	0.09%
Dark to Dawn Lighting ⁽⁷⁾	864	0.0%	94,405	0.5%	864	0.0%	94,405	0.44%
General Lighting ⁽⁷⁾	9,303	0.0%	9,303	0.0%	9,303	0.0%	9,303	0.0%
Railroad ⁽⁷⁾⁽⁹⁾	74,890	0.4%	114,814	0.6%	74,890	0.4%	114,814	0.5%
Nonresidential	10,614,273	52.7%	10,499,521	50.8%	11,006,312	54.4%	11,070,467	51.3%
Total	20,124,324	100.0%	20,683,084	100.0%	20,238,475	100.0%	21,583,854	100.0%

Docket No. 23-
ComEd Ex. 17.08
Tab: 2023 WN CPs/NCPs

The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)
Commonwealth Edison Company

2026 Allocation CP-ALL ^(b) 3 pm to 4 pm (a)		2026 Allocation NCP-69 KV ^(b) % of Total		Weather Normal CP-ALL 3 pm to 4 pm (c)		Weather Normal NCP-69 KV % of Total	
Secondary Voltage Service Points Only		(b)		(c)		(d)	
Small Load (0 to 100 kW) ^(a)		2,624,409		2,735,007		2,826,590	
Medium Load (Over 100 to 400 kW) ^(a)		2,075,015		2,162,461		2,296,832	
Large Load (Over 400 to 1000 kW) ^(a)		1,623,035		1,691,433		1,793,470	
Very Large Load (Over 1,000 to 10,000 kW)		2,176,899		2,268,638		2,373,846	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾		193,463		204,374		204,374	
High Voltage (Up to 10,000 kW) ^{(7)(b)}		530		530		1,754	
High Voltage (Over 10,000 kW) ^{(7)(b)}		1,552		1,552		2,795	
Primary Voltage Service Points with ComEd Transformers							
Small Load (0 to 100 kW) ⁽⁷⁾		721		751		1,081	
Medium Load (Over 100 to 400 kW) ^(a)		15,774		16,439		19,728	
Large Load (Over 400 to 1000 kW) ^(a)		28,701		31,652		33,530	
Very Large Load (Over 1,000 to 10,000 kW)		388,757		413,230		437,743	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾		137,671		141,383		141,383	
High Voltage (Up to 10,000 kW) ^{(7)(b)}		27		27		1,298	
High Voltage (Over 10,000 kW) ^{(7)(b)}		4,306		4,306		4,381	
High Voltage CP 69KV & below							
High Voltage (Up to 10,000 kW) ^{(7)(b)}		12,120		12,120			
High Voltage (Over 10,000 kW) ^{(7)(b)}		48,920		48,920			
CP < 69 kV							
High Voltage (Up to 10,000 kW) ^{(7)(b)}		5,142		5,142			
High Voltage (Over 10,000 kW) ^{(7)(b)}		31,830		31,830			

- Notes:
- All of the notes below are consistent with the allocation from the 2022 FRU (22-0302) work paper but with adjustments from the Watt-Hour/Small Load and Lighting Adjustments tabs.
- (1) The weather normal CP-ALL load is the sum of the residential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest single demand for each delivery class in 2021.
- (2) The weather normal CP-ALL load is the sum of the nonresidential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest individual customer class hourly loads in 2018 for the portion of the loads delivered at voltages below 69 kV.
- (3) The loads under column (a) are the hourly loads of individual classes on August 24, 2021 for the hour between 3 pm and 4 pm, reflecting ComEd's system peak hour from 2018.
- (4) The loads under column (b) are the highest individual customer class hourly loads in 2021 for the portion of the loads delivered at voltages below 69 kV.
- (5) The loads under columns (c) and (d) for the residential classes are determined by allocating the totals described in Note (1) to the classes based on the loads shown in columns (a) and (b), respectively.
- (6) The loads under columns (c) and (d) for the smaller nonresidential classes up to the Very Large Load are determined from total nonresidential described in Note (2) after removing the loads for the larger customer classes and lighting classes shown in columns (a) and (b) respectively, and allocating the rest to these smaller nonresidential classes based on the loads shown in columns (a) and (b), respectively.
- (7) The loads for these classes shown in columns (a) and (b) are the same as the loads for these classes shown in columns (c) and (d), respectively.
- (8) Loads presented do not include the Zero Standard Portion described in Rider ZSS - Zero Standard Service.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 208 of 580

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Docket No. 23-
ComEd Ex. 17.08
Tab. 2025 NCP-SEC LINE

Commonwealth Edison Company
The Determination of Non-coincident Demands by Customer Class
for Customers Taking Service at Secondary Voltages Distribution Lines (NCP-SEC LINE)

	Class Noncoincident Peak Demand for Load < 69 kV (NCP < 69 kV) in kW ⁽¹⁾	% of Customers Not Taking Service from Secondary Distribution Lines ⁽²⁾	% of Customers Taking Service from Secondary Distribution Lines	NCP-SEC LINE in kW ⁽²⁾
	(A)	(B)	(C) = 1 - (B)	(D) = (A) * (C)
Residential				
1 Single Family Without Electric Space Heat	8,051,700	2.3%	97.7%	7,866,511
2 Multi Family Without Electric Space Heat	1,587,454	18.2%	81.8%	1,298,537
3 Single Family With Electric Space Heat	249,160	18.7%	81.3%	202,518
4 Multi Family With Electric Space Heat	625,133	18.2%	81.8%	511,359
Total Residential	10,513,387			9,878,925
Nonresidential				
5 Watt-Hour	60,834	6.5%	93.5%	56,880
6 Small Load (0 to 100 kW)	2,829,216	13.9%	86.1%	2,435,955
7 Medium Load (Over 100 to 400 kW)	2,323,626	83.8%	16.4%	381,075
8 Large Load (Over 400 to 1000 kW)	1,864,274	100.0%	0.0%	-
9 Very Large Load (Over 1,000 to 10,000 kW)	3,117,955	100.0%	0.0%	-
10 Extra Large Load (Over 10,000 kW)	594,293	100.0%	0.0%	-
11a. High Voltage Up to 10 MW	7,944	100.0%	0.0%	-
11b. High Voltage Over 10 MW	34,059	100.0%	0.0%	-
12 Fixture-Included Lighting	19,744	1.4%	98.6%	19,467
13 Dunk to Dawn Lighting	94,405	1.4%	98.6%	93,083
14 General Lighting	9,303	1.4%	98.6%	9,173
15 Railroad	114,814	100.0%	0.0%	-
Total Nonresidential	11,070,467			2,995,633
Total	21,583,854			12,874,558

Notes:

(1) Transferred from column (d) on the WN CPs/NCPs page.

(2) From a "Estimated Percent of Customers That Do Not Receive Service from the Secondary Distribution System" work paper.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 209 of 580

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Docket No. 23-_____
ComEd Ex. 17.08
Tab: 2027 WN CPs/NCPs

2018 Weather Normalized (3 to 4 PM)	CP-ALL	% of Total	NCP-69 KV	% of Total
Residential(1)	9,232,163	45.6%	10,513,387	48.7%
Nonresidential(2)	11,006,311	54.4%	11,070,467	51.3%
Total	20,238,474	100.0%	21,583,854	100.0%

	2027 Allocation CP-ALL ⁽¹⁾ 3 pm to 4 pm	% of Total	2027 Allocation NCP-69 KV ⁽²⁾	% of Total	Weather Normal CP-ALL 3 pm to 4 pm	% of Total	Weather Normal NCP-69 KV	% of Total
	(a)		(b)		(c)		(d)	
Single Family Without Electric Space Heat ⁽³⁾	7,701,468	38.3%	7,799,104	37.7%	7,476,428	36.9%	8,051,700	37.3%
Multi Family Without Electric Space Heat ⁽³⁾	1,491,418	7.4%	1,537,653	7.4%	1,447,838	7.2%	1,587,454	7.4%
Single Family With Electric Space Heat ⁽¹⁾	102,636	0.5%	241,285	1.2%	99,637	0.5%	249,100	1.2%
Multi Family With Electric Space Heat ⁽³⁾	214,529	1.1%	605,521	2.9%	208,260	1.0%	625,133	2.9%
Total Residential	9,510,051	47.3%	10,183,563	49.2%	9,232,163	45.6%	10,513,387	48.7%
Watt-Hour ⁽⁶⁾	54,983	0.3%	55,361	0.3%	57,300	0.28%	58,650	0.27%
Small Load (0 to 100 kW) ⁽⁶⁾	2,628,878	13.1%	2,672,853	12.9%	2,739,664	13.54%	2,831,667	13.12%
Medium Load (Over 100 to 400 kW) ⁽⁶⁾	2,099,701	10.4%	2,193,509	10.6%	2,188,187	10.8%	2,323,841	10.8%
Large Load (Over 400 to 1000 kW) ⁽⁶⁾	1,687,001	8.4%	1,759,879	8.5%	1,758,095	8.7%	1,864,446	8.6%
Very Large Load (Over 1,000 to 10,000 kW) ⁽⁶⁾	2,832,228	14.1%	2,943,357	14.2%	2,951,584	14.6%	3,118,243	14.4%
Extra Large Load (Over 10,000 kW) ⁽⁷⁾	580,248	2.9%	594,293	2.9%	580,248	2.9%	594,293	2.8%
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾	37,965	0.2%	7,944	0.0%	37,965	0.2%	7,944	0.0%
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾	608,012	3.0%	34,059	0.2%	608,012	3.0%	34,059	0.2%
Fixture-Included Lighting ⁽⁷⁾	200	0.0%	19,670	0.1%	200	0.0%	19,670	0.09%
Dark to Dawn Lighting ⁽⁷⁾	864	0.0%	93,536	0.5%	864	0.0%	93,536	0.43%
General Lighting ⁽⁷⁾	9,303	0.0%	9,303	0.0%	9,303	0.0%	9,303	0.0%
Railroad ⁽⁷⁾⁽⁹⁾	74,890	0.4%	114,814	0.6%	74,890	0.4%	114,814	0.5%
Nonresidential	10,614,273	52.7%	10,498,578	50.8%	11,006,312	54.4%	11,070,466	51.3%
Total	20,124,324	100.0%	20,682,141	100.0%	20,238,475	100.0%	21,583,853	100.0%

Docket No. 23-
ComEd Ex. 17.08
Tab: 2027 WN CPs/NCPs

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

2027 Allocation CP-ALL ^(b) 3 pm to 4 pm (a)		2027 Allocation NCP-69 KV ^(b) % of Total		Weather Normal CP-ALL 3 pm to 4 pm (c)		Weather Normal NCP-69 KV % of Total	
Secondary Voltage Service Points Only		(b)		(c)		(d)	
Small Load (0 to 100 kW) ⁽⁶⁾		2,626,475		2,670,375		2,829,041	
Medium Load (Over 100 to 400 kW) ⁽⁶⁾		2,075,015		2,162,461		2,297,045	
Large Load (Over 400 to 1000 kW) ⁽⁶⁾		1,623,035		1,691,040		1,793,636	
Very Large Load (Over 1,000 to 10,000 kW)		2,176,899		2,260,638		2,374,065	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾		193,463		204,374		204,374	
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾		530		530		1,754	
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾		1,552		1,552		2,795	
Primary Voltage Service Points with ComEd Transformers							
Small Load (0 to 100 kW) ⁽⁶⁾		721		751		1,081	
Medium Load (Over 100 to 400 kW) ⁽⁶⁾		15,774		16,623		19,730	
Large Load (Over 400 to 1000 kW) ⁽⁶⁾		28,701		31,652		33,533	
Very Large Load (Over 1,000 to 10,000 kW)		388,757		413,230		437,783	
Extra Large Load (Over 10,000 kW) ⁽⁷⁾		137,671		141,383		141,383	
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾		27		27		1,298	
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾		4,306		4,306		4,381	
High Voltage CP 69KV & below							
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾		12,120		12,120			
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾		48,920		48,920			
CP < 69 kV							
High Voltage (Up to 10,000 kW) ⁽⁷⁾⁽⁸⁾		5,142		5,142			
High Voltage (Over 10,000 kW) ⁽⁷⁾⁽⁸⁾		31,830		31,830			

- Notes:
- All of the notes below are consistent with the allocation from the 2022 FRU (22-0302) work paper but with adjustments from the Watt-Hour/Small Load and Lighting Adjustments tabs.
- (1) The weather normal CP-ALL load is the sum of the residential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest single demand for each delivery class in 2021.
- (2) The weather normal CP-ALL load is the sum of the nonresidential class load on August 24, 2021 for the hour between 3 pm and 4 pm, ComEd's system peak on that day.
The weather normal NCP-69 kV load is the sum of the highest individual customer class hourly loads in 2018 for the portion of the loads delivered at voltages below 69 kV.
- (3) The loads under column (a) are the hourly loads of individual classes on August 24, 2021 for the hour between 3 pm and 4 pm, reflecting ComEd's system peak hour from 2018.
- (4) The loads under column (b) are the highest individual customer class hourly loads in 2021 for the portion of the loads delivered at voltages below 69 kV.
- (5) The loads under columns (c) and (d) for the residential classes are determined by allocating the totals described in Note (1) to the classes based on the loads shown in columns (a) and (b), respectively.
- (6) The loads under columns (c) and (d) for the smaller nonresidential classes up to the Very Large Load are determined from total nonresidential described in Note (2) after removing the loads for the larger customer classes and lighting classes shown in columns (a) and (b) respectively, and allocating the rest to these smaller nonresidential classes based on the loads shown in columns (a) and (b), respectively.
- (7) The loads for these classes shown in columns (a) and (b) are the same as the loads for these classes shown in columns (c) and (d), respectively.
- (8) Loads presented do not include the Zero Standard Portion described in Rider ZSS - Zero Standard Service.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 212 of 580

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Docket No. 23-
ComEd Ex. 17.08
Tab: 2027 NCP-SEC LINE

Commonwealth Edison Company
The Determination of Non-coincident Demands by Customer Class
for Customers Taking Service at Secondary Voltages Distribution Lines (NCP-SEC LINE)

	Class Noncoincident Peak Demand for Load < 69 kV (NCP < 69 kV) in kW ⁽¹⁾	% of Customers Not Taking Service from Secondary Distribution Lines ⁽²⁾	% of Customers Taking Service from Secondary Distribution Lines	NCP-SEC LINE in kW ⁽²⁾
	(A)	(B)	(C) = 1 - (B)	(D) = (A) * (C)
<u>Residential</u>				
1 Single Family Without Electric Space Heat	8,051,700	2.3%	97.7%	7,866,511
2 Multi Family Without Electric Space Heat	1,587,454	18.2%	81.8%	1,298,537
3 Single Family With Electric Space Heat	249,160	18.7%	81.3%	202,518
4 Multi Family With Electric Space Heat	625,133	18.2%	81.8%	511,359
Total Residential	10,513,387			9,878,925
<u>Nonresidential</u>				
5 Watt-Hour	58,650	6.5%	93.5%	54,838
6 Small Load (0 to 100 kW)	2,831,667	13.9%	86.1%	2,438,065
7 Medium Load (Over 100 to 400 kW)	2,323,841	83.8%	16.4%	381,110
8 Large Load (Over 400 to 1000 kW)	1,864,446	100.0%	0.0%	-
9 Very Large Load (Over 1,000 to 10,000 kW)	3,118,243	100.0%	0.0%	-
10 Extra Large Load (Over 10,000 kW)	594,293	100.0%	0.0%	-
11a. High Voltage Up to 10 MW	7,944	100.0%	0.0%	-
11b. High Voltage Over 10 MW	34,059	100.0%	0.0%	-
12 Fixture-Included Lighting	19,670	1.4%	98.6%	19,394
13 Dunk to Dawn Lighting	93,536	1.4%	98.6%	92,227
14 General Lighting	9,303	1.4%	98.6%	9,173
15 Railroad	114,814	100.0%	0.0%	-
Total Nonresidential	11,070,466			2,994,807
Total	21,583,853			12,873,732

Notes:

(1) Transferred from column (d) on the WN CPs/NCPs page.

(2) From a "Estimated Percent of Customers That Do Not Receive Service from the Secondary Distribution System" work paper.

Watt-Hour to Small Load

Delivery Class	Forecasted Number of Customers Changing Delivery Class					
	2021	2022	2023	2024	2025	2026
Watt-Hour		-4500	-3600	-3240	-2760	-2400
Small Load (0 to 100 kW)		4500	3600	3240	2760	2400

Average kW Demand from interval meter data for CP Hour 8/24/21 3-4 PM for ~2,700 accounts that changed from Watt-Hour to Small Load in 2022
0.91 kW Note the NCP was during the same date/hour

CP and NCP kW Adjustment	kW Demand				
	2021	2022	2023	2024	2025
Watt-Hour	(4,079)	(3,263)	(2,937)	(2,502)	(2,175)
Small Load (0 to 100 kW)	4,079	3,263	2,937	2,502	2,175

An adjustment is made to the CPs and NCPs from the test year 2021 kW demand.
For the current year, the value is 1/2 on the CP/NCP tab which assumes 1/2 of the customers transferred by the summer CP peak day. The same assumption is used for the NCP kW demand since they are generally the same hour/day for these delivery classes.

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 214 of 580

		Commonwealth Edition Companies																October 19, 2020	
		Global 500, FTSE 100																Table Water S&P Interest Data	
		The Determination of Whether Nonmember Considered Parties (CPN) and Nonreciprocal Party (NCPN)																	
Deliveries	Service/Class	Cost	Interest	var 001	var 002	var 003	var 004	var 005	var 006	var 007	var 008	var 009	var 010	var 011	var 012	var 013	var 014	var 015	var 016
		Number of	Rate/Day	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy	Energy
L27	C376	32423	0.075	1.45	1.02	0.82	0.81	0.81	0.87	1.075	1.347	1.718	1.810	2.071	2.348	2.525	2.781	3.062	3.281
		1.76	0.24	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02
		Average per Account 3 yrs - 4 yrs																1.02, 1.04	

Docket No. 23-_____

Commonwealth Edison Company
ComEd Ex. 17.08
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)
Tab- Lighting Adjustments

Desk to Down Monthly Burn Hours		Desk to Down Lighting kWhs		Average Demand	kW Reduction from 2021	kW Reduction Year over Year	Fixture- Lighting kWhs	Average Demand		
Jan	629	actual	2020	446,122,093	107,681		2020	108,762,433	26,252	
Feb	544	2021	390,703,396	94,304	-12%	(13,376)	2021	90,203,367	21,772	
Mar	742	(actual and 2022)	2022	381,550,350	92,095	-2%	(2,209)	2022	76,892,450	18,549
Apr	290	2023	376,500,350	90,898	-1%	(1,207)	2023	76,542,650	18,476	
May	363	2024	371,550,350	89,681	-1%	(1,207)	2024	76,238,650	18,401	
Jun	240	2025	367,950,350	88,812	-1%	(869)	2025	75,927,650	18,327	
Jul	288	2026	364,950,350	87,943	-1%	(869)	2026	75,618,250	18,252	
Aug	720	2027	360,750,350	87,074	(7,308)	-1%	(869)	2027	75,311,450	18,178
Sep	340									
Oct	463									
Nov	493									
Dec	417									
Total Hours		4,143								

Commonwealth Edison Company
The Determination of Weather Normalized Coincident Peaks (CPs) and Noncoincident Peak (NCPs)

Docket No. 23-
ComEd Ex. 17.08
Tab: Lighting Adjustments

LW Reduction from 2021	LW Reduction Year over Year	Five Year Deployment Goal
-17%	(4,480)	2018 – 24,000 Complete
-15%	(3,223)	2019 – 21,000 Complete
(3,372)	(74)	2020 – 24,000 Complete
(1,446)	(74)	2021 – 20,800 Complete
(3,529)	(74)	2022 – 16,500 Target
(3,094)	(74)	2023 – Balance of lights remaining

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 217 of 580

Docket No. 23-_____
ComEd Ex. 17.11
2024 Customer-Based Allocation Factors
Tab: Service (SAG)_CT&PTs

Commonwealth Edison Company
The Determination of Allocation Factors for Service Cost

		ALPCC: 40 yr ⁽⁵⁾ 0.0701 (C)		ALPCC: 30 yr ⁽⁵⁾ 0.0777 (C)		ALPCC: 16 yr ⁽⁶⁾ 0.1083		
Number of Standard Services ⁽¹⁾	Cost per Standard Service ⁽²⁾	Annualized Cost per Standard Service	Number of Customers with Meters	Cost per Customer for Standard CTs, PTs, and Relays ⁽³⁾	Annualized Service Cost and per Customer for CTs and PTs Costs per Number of Standard CTs, PTs, and Relays	Cost per Service / CT&PTs Weighting ⁽⁷⁾ (weighting ratio)	Weighted Customers for Service/CT&PTs Cost (unthru)	
(A)	(B)	(D) = (B)*(C)	(E)	(F)	(H) = (F)*(G)	(I) = (A)*(D)/(H)*(A)	(K) = (A) * (I)	
Residential								
1 Single Family Without Electric Space Heat	2,337,059	\$1,147.31	\$80.41	2,337,059	\$1.50	\$80.53	1,000	2,337,059
2 Multi Family Without Electric Space Heat	1,231,492	\$258.09	\$18.12	1,231,492	\$1.50	\$18.24	0.238	278,317
3 Single Family With Electric Space Heat	35,271	\$1,147.31	\$80.41	35,271	\$1.50	\$80.53	1,000	35,271
4 Multi Family With Electric Space Heat	166,665	\$258.09	\$18.12	166,665	\$1.50	\$18.24	0.238	37,666
Nonresidential								
5 Wires-Short	72,436	\$377.91	\$26.40	72,436	\$1.40	\$26.59	0.330	23,904
6 Small Load (0 to 100 kW)	305,135	\$421.76	\$29.56	305,135	\$180.01	\$43.54	0.541	165,078
7 Medium Load (Over 100 to 400 kW)	36,243	\$521.09	\$36.52	16,243	\$945.09	\$73.47	1.366	22,188
8 Large Load (Over 400 to 1000 kW)	3,961	\$738.68	\$51.77	3,961	\$1,382.62	\$129.16	1.976	7,827
9 Very Large Load (Over 1000 to 10,000 kW)	1,837	\$2,186.28	\$153.22	1,837	\$3,330.75	\$228.71	5.115	9,396
10 Extra Large Load (Over 10,000 kW)	88	\$1,459.21	\$102.26	44	\$35,365.85	\$2,747.02	18.326	1,613
11a. High Voltage (Up to 10,000 kW)	60	\$1,459.21	\$102.26	60	\$55,856.53	\$4,338.61	\$5,146	3,399
11b. High Voltage (Over 10,000 kW)	38	\$1,459.21	\$102.26	38	\$55,856.53	\$4,338.61	\$4,480.87	2,896
12 Fixtures-Included Lighting ⁽⁴⁾	171,148	\$154.41	\$10.82	-	\$0.00	\$10.82	0.134	22,934
13 Desk to Down Lighting	167,131	\$154.41	\$10.82	2,923	\$12.24	\$0.95	0.135	22,563
14 General Lighting	14,831	\$154.41	\$10.82	413	\$8.56	\$0.66	0.135	2,002
15 Railroad ⁽⁵⁾	5	\$1,459.21	\$102.26	2	\$16,998.77	\$1,320.37	7.828	39
Total	4,523,400			4,173,579				2,971,261

Notes:

(1) These lighting accounts are customers for lighting services only and do not include lighting accounts that also take electric services.

(2) The customers in the Railroad class use electricity only for traction power.

(3) Each customer has a single service connection except customers in the Extra Large Loads, Lighting, and Railroad classes. Each customer in the Extra Large Load class has two service connections, the two railroads have 5 total connections. The service connections for the lighting classes are estimated from the number of meters, number of bills, and information provided by the City of Chicago.

(4) The investment cost for standard service provided to customers is based on a ComEd service connection facilities study.

(5) The Annual Levelized Premium of Carrying Costs (ALPCC) for services and for CTs and PTs are based on a 40 year useful life and a 30 year useful life, respectively. The 16 year ALPCC is used on the Meter 370 tab.

(6) The investment cost for current and potential transformers (CTs and PTs) provided to customers as standard is based on a ComEd metering facilities study.

(7) Used in ComEd Ex. 17.17, Schedule 2b, Line 38, Pages 1 of 4 and 2 of 4.

Docket No. 23-
ComEd Ex. 17.11
2026 Customer Based Allocation Factors
Tab: Meter_370

Commonwealth Edison Company
The Determination of Meter Factor

	Average Number of Customers with Standard Meters ⁽¹⁾	Investment Cost per Customer for Standard Meters ⁽²⁾	Percent of Mechanical Meters	ALPCC from Service (369) CT&PTs ⁽³⁾	Annual Investment Cost per Customer for Standard Meter	Cost per Customer for Standard Meter Weighting ⁽⁵⁾ (weighting ratio)	Weighted Standard Meter Cost (attribute)
	(A)	(B)	(C)	(D)	(E) = (B) * (C)	(E)	(F) = (A) * (E)
Residential							
1 Single Family Without Electric Space Heat	2,337,059	\$273.59	0.1%	0.1082	\$29.61	1.000	2,337,059
2 Multi Family Without Electric Space Heat	1,231,492	\$273.59		0.1082	\$29.61	1.000	1,231,492
3 Single Family With Electric Space Heat	35,271	\$273.59		0.1082	\$29.61	1.000	35,271
4 Multi Family With Electric Space Heat	166,665	\$273.59		0.1082	\$29.61	1.000	166,665
Nonresidential							
5 Wait-Hour	72,436	\$199.66	0.1%	0.1082	\$21.61	0.730	52,878
6 Small Load (0 to 100 kW)	305,135	\$360.84		0.1083	\$39.94	1.349	411,627
7 Medium Load (Over 100 to 400 kW)	16,243	\$514.49		0.1083	\$55.71	1.881	30,553
8 Large Load (Over 400 to 1000 kW)	3,961	\$518.62		0.1083	\$56.15	1.896	7,510
9 Very Large Load (Over 1,000 to 10,000 kW)	1,837	\$521.62		0.1083	\$56.48	1.907	3,503
10 Extra Large Load (Over 10,000 kW)	44	\$1,765.88		0.1083	\$191.21	6.458	784
11a. High Voltage (Up to 10,000 kW)	60	\$2,645.64		0.1083	\$286.45	9.674	580
11b. High Voltage (Over 10,000 kW)	38	\$2,645.64		0.1083	\$286.45	9.674	368
12 Fixtures-Included Lighting ⁽⁴⁾	n.a.	n.a.		n.a.	n.a.	n.a.	n.a.
13 Dark to Dawn Lighting	2,923	\$301.82		0.1083	\$32.68	1.104	3,227
14 General Lighting	413	\$281.26		0.1083	\$30.45	1.028	425
15 Railroad ⁽⁵⁾	2	\$1,282.94		0.1083	\$138.91	4.691	9
Total	4,173,579						4,281,452

Notes:
(1) These lighting accounts are customers for lighting services only and do not include lighting accounts that also take electric services
(2) The customers in the Railroad class use electricity only for traction power
(3) Other than the lighting classes, the information under this column is the number of customers. The numbers listed for the lighting classes are the number of meters in these classes.
The values are equal to the values in ComEd Ex. 17.17, Schedule 2b, Line 44, Pages 1 and 2 of 4
(4) Standard Meter Investment Cost per Customer is the investment cost for meters provided to customers in each delivery class as standard. It does not include the investment cost for CTs, PTs, and Relays shown on the Service (369), CT&PTs page. The investment cost provided to customers in each delivery class as standard is based on a ComEd metering facilities study
(5) The Annual Levelized Premium of Carrying Costs (ALPCC) is based on a 30 year useful life for residential and wait-hour mechanical meters and a 16 year useful life for all other electronic meters. Percent of mechanical meters are used to weight the ALPCC
(6) Used in ComEd Ex. 17.17, Schedule 2b, Line 43, Pages 1 and 2 of 4.

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 219 of 580

Commonwealth Edison Company
The Determination of Allocation Factor for Meter Reading

Docket No. 23-_____
ComEd Ex. 17.11
2026 Customer Based Allocation Factors
Tab: Meter Reading 902

	Average Number of Customers with Standard Meters	Average Annual Standard Meter Reading Cost per Customer ⁽¹⁾	Per Customer Meter Reading Cost Weighting Factor ⁽²⁾ (weighting ratio)	Weighted Meters for Standard Meter Reading (attribute)
	(A)	(B)	(C)	(D) = (A) * (C)
<u>Residential</u>				
1 Single Family Without Electric Space Heat	2,337,059	\$0.12	1.000	2,337,059
2 Multi Family Without Electric Space Heat	1,231,492	\$0.12	1.000	1,231,492
3 Single Family With Electric Space Heat	35,271	\$0.12	1.000	35,271
4 Multi Family With Electric Space Heat	166,665	\$0.12	1.000	166,665
<u>Nonresidential</u>				
5 Watt-Hour	72,436	\$0.09	0.750	54,327
6 Small Load (0 to 100 kW)	305,135	\$0.12	1.000	305,135
7 Medium Load (Over 100 to 400 kW)	16,243	\$0.18	1.500	24,365
8 Large Load (Over 400 to 1000 kW)	3,961	\$0.21	1.750	6,932
9 Very Large Load (Over 1,000 to 10,000 kW)	1,837	\$0.26	2.167	3,981
10 Extra Large Load (Over 10,000 kW)	44	\$1.04	8.667	381
11a. High Voltage (Up to 10,000 kW)	60	\$0.52	4.333	260
11b. High Voltage (Over 10,000 kW)	38	\$0.52	4.333	165
12 Fixture-Included Lighting ⁽³⁾	n.a.	n.a.	n.a.	n.a.
13 Street Lighting - Dusk to Dawn	2,923	\$0.12	1.000	2,923
14 Street Lighting - All Other Lighting	413	\$0.12	1.000	413
15 Railroad ⁽⁴⁾	2	\$0.30	2.500	5
Total	4,173,579			4,169,373

Notes:

(1) These lighting accounts are customers for lighting services only and do not include lighting accounts that also take electric services.

(2) The customers in the Railroad class use electricity only for traction power.

(3) The per customer meter reading cost is based on a ComEd metering facilities study.

(4) Used in ComEd Ex. 17.17, Schedule 2b, Line 57, Pages 1 and 2 of 13

2024DAI 0000089

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 220 of 580

Commonwealth Edison Company
The Determination of Allocation Factor for Meter O&M

Docket No. 23-_____
ComEd Ex. 17.11
2026 Customer Based Allocation Factors
Tab: Meter O&M

	Average Number of Customers with Standard Meters	Average Annual Maintenance and Testing per Customer ⁽¹⁾	Total Annual Meter Maintenance and Testing	Meter O&M ⁽⁶⁾⁽⁷⁾	Meter O&M Per Customer	Weighted Meter O&M per Customer (6) (weighting ratio)	Weighted Meter O&M (attributed)
	(A)	(B)	(C) = (A) * (B)	(D)	(E)	(F)	(G) = (A) * (F)
Residential				34%			
1 Single Family Without Electric Space Heat	2,337,059	\$0.62	\$1,448,977	\$1,769,868	\$0.76	1.000	2,337,059
2 Multi Family Without Electric Space Heat	1,231,492	\$0.62	\$763,525	\$932,616	\$0.76	1.000	1,231,492
3 Single Family With Electric Space Heat	35,271	\$0.62	\$21,868	\$26,711	\$0.76	1.000	35,271
4 Multi Family With Electric Space Heat	166,665	\$0.62	\$103,332	\$126,446	\$0.76	1.000	166,665
Total Residential	3,770,487		\$2,337,702	\$2,855,411			3,770,487
Nonresidential				66%			
5 Wastewater	72,436	\$1.41	\$102,135	\$68,059	\$0.95	1.250	90,545
6 Small Load (0 to 100 kW)	305,135	\$22.77	\$6,947,924	\$4,684,286	\$15.35	20.197	6,162,812
7 Medium Load (Over 100 to 400 kW)	16,243	\$51.14	\$830,667	\$560,035	\$34.48	45.368	736,912
8 Large Load (Over 400 to 10,000 kW)	3,961	\$51.29	\$203,556	\$137,227	\$34.65	45.592	180,590
9 Very Large Load (Over 1,000 to 10,000 kW)	1,837	\$51.46	\$94,532	\$63,733	\$34.69	45.645	83,850
10 Extra Large Load (Over 10,000 kW)	44	\$99.67	\$4,385	\$2,956	\$67.18	88.395	3,889
11a. High Voltage (Up to 10,000 kW)	60	\$41.75	\$2,505	\$1,689	\$28.15	37.039	2,222
11b. High Voltage (Over 10,000 kW)	38	\$41.75	\$1,587	\$1,070	\$28.16	37.053	1,408
12 Fixture-Included Lighting ⁽³⁾	n.a.	n.a.	n.a.	n.a.	n.a.	n.a.	n.a.
13 Street Lighting - Dark to Dawn	2,023	\$11.14	\$22,562	\$21,953	\$7.51	9.882	20,085
14 Street Lighting - All Other Lighting	413	\$1.10	\$453	\$463	\$2.09	2.750	1,136
15 Railroad ⁽⁵⁾	2	\$128.74	\$257	\$172	\$86.50	113.816	228
Total Nonresidential	403,092		\$8,221,390	\$5,542,854			7,292,477
Total	4,173,579		\$10,559,092	\$8,398,265			11,062,964

Notes:
(1) These lighting accounts are customers for lighting services only and do not include lighting accounts that also take electric services.
(2) The customers in the Railroad class use electricity for traction power.
(3) The average annual maintenance, testing and meter reading per customer is based on a ComEd metering facilities study.
(4) Costs identified as metering services costs in Accounts 586 and 597.
(5) For allocation purposes, 34% of Metering Services O&M to residential based upon completed O&M jobs in Field and Metering Services during 2021 as provided in the "FMS Cost Allocation" page of this exhibit.
(6) Used in ComEd Ex. 17.17, Schedule 2b, Line 62, Pages 3 and 4 of 4.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 221 of 580

2021 ComEd Field and Meter Service Completed Jobs for Allocation

	Total Actual ⁽¹⁾	Residential ⁽²⁾⁽³⁾	Nonresidential ⁽²⁾⁽³⁾
Auxiliary Maintenance	1,532		1,531
Commercial Compliance Investigator	3,827		3,827
Consumption on Cut Meter	3	0	3
Consumption On Location Meter	1,352	445	907
Connectivity Declared	2		2
Connectivity	7,359	2,538	4,821
Cut In ⁽⁴⁾	2,115	1,878	237
Cut Out Commercial ⁽⁴⁾	2,427		2,427
Cut Out Residential ⁽⁴⁾	384	384	
Exchange	551	185	366
CMO No Visual	8,422	2,992	5,430
High Bill	6,129	2,170	3,959
Meter Investigation	45	104	363
Moved Meter	4,772	1,512	2,760
Meter Reading Irregular Condition	586	211	375
New Business Cut	20,619	7,303	13,316
New Business Inspections	4,804	1,701	3,103
New Business Meter	3,329	1,301	2,028
Portable Exchange	9,189	3,253	5,936
Meter Tests Periodics	123	37	86
Meter Tests	924	221	403
Rebills	2,748	2,748	
Rebill Check	620	220	400
Reopen	3,280	1,181	2,100
Reopen	11,397	4,389	7,008
Residential Real Time Pricing	4	4	
Reset Meter	98	36	62
RTSP	9,628	3,125	6,503
Consumption on Off Meters (CCM)			1
Denial of Service	1	0	1
MMT - MM Exchanges	12,328	6,464	5,864
MMT Investigations	24,239	6,582	17,657
MMT	4	1	3
Meter Investigation-Closed Loops	30,738	7,342	23,396
Remote Disconnect Inspections	116,367	60,567	55,800
Total			
Metering Services Related (excluding Cut-ins and Cut-Outs)	171,466	58,305	113,161
Percentages		34%	66%

Notes:

(1) Source: System Wide Completions YTD (Full Year)

(2) Not related to Metering Services

(3) Work that could not be clearly defined as residential or nonresidential, was allocated based on the percentage of Energy Technicians versus Senior Energy Technicians as of Pay Period 26 in 2021. The percentages are as follows:

SET - Nonresidential	104	64.6%
ET - Residential	57	35.4%
Total	161	

(4) Cut in numbers are split at 89% residential and 11% nonresidential based on the cut out orders

Docket No. 23-
ComEd Ex. 17.11
2025 Customer Based Allocation Factors
Tab: FMS cost allocation

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 222 of 580

Docket No. 23-
 ConfId Ex. 17.11
 2026 Customer Based Allocation Factors
 Tab: Accounts 901 902 4803_part 1

Commonwealth Edison Company
 The Determination of Allocation Factor for Customer Accounts - Billing and Accounting

	Average Number of Forecasted Customers in 2026 (3)	Forecasted LCS Cost Allocation % in 2026 (4)	LCS Cost (F) = (D)*(E)	LCS Cost per Account (G) = (F) / (A)	Billing Cost ⁽⁵⁾ (H)	Billing Cost Per Account (I) = (H) / (A)
	(A)	(D)	(F)	(G)	(H)	(I)
Residential						
1 Single Family Without Electric Space Heat	2,337,059	0.0%	\$0	\$0.00	\$2,299,644	\$0.98
2 Multi Family Without Electric Space Heat	1,231,492	0.0%	\$0	\$0.00	\$2,795,774	\$2.27
3 Single Family With Electric Space Heat	35,271	0.0%	\$0	\$0.00	\$45,427	\$1.29
4 Multi Family With Electric Space Heat	166,665	0.0%	\$0	\$0.00	\$306,165	\$1.84
Total Residential	3,770,487 (B)	0.0%	\$0	\$0.00	\$5,447,010	\$1.44
Nonresidential						
5 Watts/Hour	72,436	1.0%	\$94,077	\$1.30	\$509,836	\$7.04
6 Small Load (0 to 100 kW)	305,135	1.5%	\$141,115	\$0.46	\$821,010	\$2.69
7 Medium Load (Over 100 to 400 kW)	16,243	3.5%	\$329,269	\$20.27	\$108,362	\$6.67
8 Large Load (Over 400 to 10,000 kW)	3,961	20.5%	\$1,928,575	\$486.89	\$43,158	\$10.90
9 Very Large Load (Over 1,000 to 10,000 kW)	1,837	68.0%	\$6,397,224	\$3,482.43	\$77,667	\$42.28
10 Extra Large Load (Over 10,000 kW)	44	3.5%	\$329,269	\$7,483.39	\$10,363	\$235.52
11a. High Voltage (Up to 10,000 kW)	60	0.9%	\$84,669	\$1,411.15	\$38,346	\$639.10
11b. High Voltage (Over 10,000 kW)	38	0.6%	\$56,446	\$1,485.42	\$19,485	\$512.76
12 Fixture-Included Lighting ⁽¹⁾	1,770	0.0%	\$0	\$0.00	\$67,018	\$37.86
13 Street Lighting - Dark to Dawn	3,711	0.0%	\$0	\$0.00	\$20,915	\$5.64
14 Street Lighting - All Other Lighting	1,288	0.0%	\$0	\$0.00	\$11,735	\$9.11
15 Railroad ⁽²⁾	2	0.0%	\$47,038	\$23,519.00	\$4,834	\$2,417.00
Total Nonresidential	406,525	100.0%	\$9,407,682	\$23.14	\$1,732,729	\$4.26
Total	4,177,012 (C)	100.0%	\$9,407,682	\$2.25	\$7,179,739 (I)	\$1.72

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 223 of 580

Docket No. 23-
ComEd Ex. 17.11
2026 Customer Based Allocation Factors
Tab: Accounts 901, 902, 8903, part 2

Commonwealth Edison Company The Determination of Allocation Factor for Customer Accounts - Billing and Accounting (Continued)

	Peak Time Rebate (PTR) Costs in Account 901	Other Customer Costs in Accounts 901, 902 & 903 ^(a)	Accounts 901, 902 & 903 Costs (Non SBO, Non Meter, Non SAC, NonCARE)	Accounts 901, 902 & 903 Costs Per Customer (Non SBO, Non Meter, Non SAC, NonCARE)	Per Customer Weights (Non SBO, Non Meter, Non SAC, NonCARE) ⁽¹⁾ (weighting ratio)	Weighted Customers for Customer Accounts (Non SBO, Non Meter, Non SAC, NonCARE) (entirety)
	(J) = (IA) / (BJ) * (K)	(N) = (IA) / (CJ) * (M)	(O) = (F) - (H) - (L) - (N)	(T) = (S) / (A)	(U)	(V) = (U) * (A)
Residential						
1 Single Family Without Electric Space Heat	\$0	\$52,009,459	\$54,309,103	\$23.24	1.000	2,337,059
2 Multi Family Without Electric Space Heat	\$0	\$27,405,912	\$30,201,686	\$24.52	1.055	1,299,224
3 Single Family With Electric Space Heat	\$0	\$784,929	\$830,356	\$23.54	1.013	35,730
4 Multi Family With Electric Space Heat	\$0	\$3,202,002	\$4,013,307	\$4.02	1.042	172,432
Total Residential	\$0	\$83,909,302	\$89,356,312	\$23.70	1.020	3,844,844
Nonresidential						
5 Wren-Hour	\$0	\$1,612,008	\$2,215,921	\$30.59	1.316	95,326
6 Small Load (0 to 100 kW)	\$0	\$6,790,546	\$7,752,671	\$25.41	1.093	333,513
7 Medium Load (Over 100 to 400 kW)	\$0	\$361,476	\$799,107	\$49.20	2.117	34,386
8 Large Load (Over 400 to 1000 kW)	\$0	\$88,149	\$2,059,882	\$520.04	22.377	88,635
9 Very Large Load (Over 1,000 to 10,000 kW)	\$0	\$40,081	\$6,315,772	\$1,546.96	152.623	280,360
10 Extra Large Load (Over 10,000 kW)	\$0	\$979	\$340,611	\$7,741.16	333.096	14,656
11a. High Voltage (Up to 10,000 kW)	\$0	\$1,335	\$124,350	\$2,072.50	89.178	5,351
11b. High Voltage (Over 10,000 kW)	\$0	\$846	\$76,777	\$2,020.45	86.938	3,304
12 Fixtures-Included Lighting ⁽¹⁾	\$0	\$39,390	\$106,408	\$60.12	2.587	4,579
13 Street Lighting - Dark to Dawn	\$0	\$82,585	\$103,500	\$27.89	1.200	4,453
14 Street Lighting - All Other Lighting	\$0	\$28,663	\$40,398	\$31.36	1.349	1,738
15 Railroad ⁽²⁾	\$0	\$45	\$53,817	\$25,924.50	1,116.975	2,734
Total Nonresidential	\$0	\$9,046,903	\$20,187,314	\$49.66	2.137	860,543
Total	\$0	\$92,956,205	\$109,543,626	\$26.23	1.129	4,713,387

Docket No. 23-_____

ComEd Ex. 17.11

2026 Customer Based Allocation Factors

Tab: Accounts 901 902 & 903_part 3

Commonwealth Edison Company

The Determination of Allocation Factor for Customer Accounts - Billing and Accounting

(Continued)

Notes:

- (1) These lighting accounts are customers for lighting services only and do not include lighting accounts that also take electric services.
- (2) The customers in the Railroad class use electricity for traction power.
- (3) The forecasted number of accounts are provided by ComEd's Load Forecasting Department
- (4) Forecasted Large Customer Solutions (LCS) cost in Account 903 for 2026: \$9,407,682 (E)
- (5) Transferred from column (N) on the Billing Cost page.
- (6) Other Customer Costs in Accounts 901, 902 & 903 are costs in these accounts not related to (a) Metering Services,
- (b) Bill Issue and Processing, Cash and Collection related, (c) LCS, (d) Billing costs, (e) Excluded costs and (f) PTR costs:
- | | Total | Metering Services | Excluded Cost |
|---|-------------------|--|------------------|
| Account 901 | \$805,818 | \$0 | (\$7,000) |
| Account 902 | \$21,867,238 | \$21,868,068 | \$0 |
| Account 903 | \$154,085,608 | \$6,463,923 | \$18,914,000 |
| Total | \$176,758,664 (P) | \$28,331,990 (Q) | \$18,907,000 (R) |
| Bill Issue and Processing, Cash and Collection | | \$19,976,048 (M) | |
| PTR Costs | | \$0 (K) | |
| Other Customer Costs in Accounts 901, 902 & 903 | | \$92,956,205 (S) = (P) - (Q) - (R) - (M) - (K) - (E) - (I) | |
- (7) Used in ComEd Ex. 17.17, Schedule 2b, Line 82, Pages 3 and 4 of 4.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 225 of 580

Docket No. 23-_____
ComEd Ex. 17.11
2026 Customer Based Allocation Factors
Tab: Billing Cost

Commonwealth Edison Company
The Determination of Billing Costs by Delivery Class (Excluding Costs related to Bill Issuing and Processing)

	Forecasted Average Number of Customers in Monthly Review Bills in 2026 ⁽¹⁾	Forecasted Total (Average) Number of Review Bills in 2026 ⁽²⁾	Billing Costs Related to Review Bills ⁽³⁾ (F) = (B) * (E) / (I)	Forecasted Total Number of Billing Adjustments in 2026 ⁽⁴⁾	Billing Costs Related to Billing Activities Other than Review Bills ⁽⁵⁾ (M) = (K) * (H) / (L)	Billing Costs ⁽⁶⁾ (N) = (J) + (M)
Residential	(A)	(B)	(F) = (B) * (E) / (I)	(K)	(M) = (K) * (H) / (L)	(N) = (J) + (M)
1 Single Family Without Electric Space Heat	3,337,059	297	\$95,794	8,883	\$2,203,940	\$2,299,644
2 Multi Family Without Electric Space Heat	1,231,482	8	\$2,578	11,258	\$2,793,196	\$2,795,774
3 Single Family With Electric Space Heat	35,271	7	\$2,236	174	\$43,171	\$45,427
4 Multi Family With Electric Space Heat	166,665	-	\$0	1,234	\$336,365	\$336,365
Total Residential	3,770,487	312	\$100,538	21,549	\$5,346,472	\$5,447,010
Nonresidential						
5 Warm-House	72,436	3	\$967	2,051	\$508,869	\$509,836
6 Small Load (0 to 100 kW)	393,135	171	\$53,182	3,087	\$763,908	\$817,010
7 Medium Load (Over 100 to 400 kW)	16,243	36	\$11,600	390	\$96,762	\$108,362
8 Large Load (Over 400 to 1000 kW)	3,961	40	\$12,889	122	\$38,269	\$41,158
9 Very Large Load (Over 1000 to 10,000 kW)	1,037	134	\$45,180	139	\$34,487	\$77,667
10 Extra Large Load (Over 10,000 kW)	44	25	\$6,378	8	\$1,985	\$10,363
11a. High Voltage (Up to 10,000 kW)	60	119	\$38,346	-	\$0	\$38,346
11b. High Voltage (Over 10,000 kW)	38	52	\$16,736	11	\$2,729	\$19,465
12 Firm-Included Lighting ⁽⁷⁾	1,779	151	\$48,658	74	\$18,369	\$67,018
13 Street Lighting - Dark to Dawn	2,711	1	\$322	63	\$28,293	\$28,915
14 Street Lighting - All Other Lighting	1,388	1	\$322	46	\$11,413	\$11,735
15 Railroad ⁽⁸⁾	-	15	\$4,834	-	\$0	\$4,834
Total Nonresidential	406,525	749	\$241,354	6,011	\$1,491,375	\$1,732,729
Total	4,177,012	1,061	(F)	27,560	(L)	\$6,837,847

Notes:

(1) These lighting accounts are customers for lighting services only and do not include lighting accounts that also take electric services

(2) The customers in the Railroad class use electricity only for traction power. The two railroad customers have a total of 14 accounts that are all manually reviewed

(3) From Load Forecasting

(4) Provided by ComEd's System Billing department

(5) Billing costs related to review bills and other billing activities are first determined by the number of billing clerks with responsibility to review bill and other activities.

ComEd Billing Costs in Account 903 not related to Bill Issuing and Processing, in 2021 from ComEd's general ledger

Number of billing clerks, from ComEd's system Billing

Average cost per billing clerk

Number of billing clerks work on Review Bills, provided by ComEd's System Billing

Billing costs related to Review Bills

Billing costs for billing activities other than Review Bills

The billing costs for review bills are allocated to delivery classes based on the average number of review bills by delivery class in 2021 and the remainder of the billing costs are allocated to delivery classes based on the total number of bill adjustments by delivery class in 2021

(6) Transferred to column (I) on the Account 903 B093 page

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 226 of 580

Docket No. 23-_____
ComEd Ex. 17.11
2026 Customer Based Allocation Factors
Tab: Account 587

Commonwealth Edison Company
The Determination of Allocation Factor for Customer Installations Expenses

	Forecasted Average Number of Accounts in 2026(G)	Forecasted Customer Installations Costs in 2026(G)	Forecasted Per Customer Installations Costs (E) = (B) / (A)	Per Customer Installations Costs Weighting Factor ^(H) (weighting factor)	Weighted Customers for Customer Installations Costs (costshare)
	(A)	(B)	(E) = (B) / (A)	(G) = (E) / (F)	(H) = (G) * (A)
Residential					
1 Single Family Without Electric Space Heat	2,337,459	\$11,010,141	\$4.71 (F)	1.000	2,337,459
2 Multi Family Without Electric Space Heat	1,231,492	\$5,801,694	\$4.71	1.000	1,231,492
3 Single Family With Electric Space Heat	35,271	\$166,166	\$4.71	1.000	35,271
4 Multi Family With Electric Space Heat	166,665	\$788,177	\$4.71	1.000	166,665
Total Residential	3,770,487	\$17,763,177	\$4.71		3,770,487
Nonresidential					
5 Walk-In	72,436	\$830,553	\$11.47	2.435	176,382
6 Small Load (0 to 100 kW)	305,135	\$3,498,085	\$11.47	2.435	743,004
7 Medium Load (Over 100 to 400 kW)	16,243	\$186,243	\$11.47	2.435	39,552
8 Large Load (Over 400 to 1000 kW)	3,961	\$45,417	\$11.47	2.435	9,645
9 Very Large Load (Over 1,000 to 10,000 kW)	1,837	\$21,063	\$11.47	2.435	4,473
10 Extra Large Load (Over 10,000 kW)	44	\$505	\$11.47	2.435	107
11a. High Voltage (Up to 10,000 kW)	60	\$688	\$11.47	2.435	146
11b. High Voltage (Over 10,000 kW)	38	\$436	\$11.47	2.435	93
12 Fixture-Included Lighting ^(I)	1,770	\$20,295	\$11.47	2.435	4,310
13 Street Lighting - Dusk to Dawn	3,711	\$42,550	\$11.47	2.435	9,036
14 Street Lighting - All Other Lighting	1,288	\$14,768	\$11.47	2.435	3,136
15 Railroad ^(J)	2	\$23	\$11.47	2.435	5
Total Nonresidential	406,525	\$4,661,225	\$11.47		989,888
Total	4,177,012	\$22,424,402	\$5.37	1.140	4,760,375

Customer Installations costs recorded in Accounts 587:

Customer Installations Expenses				
Account	Amount in 2021 ^(K)	Metering Services	Customer Installations	Residential ^(L) Nonresidential ^(L)
587	\$22,424,402	\$0	\$22,424,402	\$17,763,177 (C) \$4,661,225 (D)

- Notes:
- (1) These lighting accounts are customers for lighting services only and do not include lighting accounts that also take electric services.
 - (2) The customers in the Railroad class use electricity only for traction power.
 - (3) From CIMS, ComEd's billing system.
 - (4) For allocation purposes, uses detailed 2021 costs information recorded in Account 587 in ComEd's general ledger, shown on the Account 587, by Project page.
 - (5) Determined from allocating residential only costs in (C) to residential delivery classes, nonresidential only costs in (D) to nonresidential delivery classes.
 - (6) Used in ComEd Ex. 17.17, Schedule 2b, Line 70, Pages 3 and 4 of 4.

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 227 of 580

Communitasville Edison Company Forecasted 2026 Assignment of Costs to Residential and Nonresidential Customers for Costs Recorded in Account 587, Customer Installations Expenses, using 2021 Data Cost Assignment: R (Residential), N (Nonresidential) Excluded or Not Applicable Estimated Using 2021 Amounts Metering Services Residential Nonresidential

Notes:

(1) The cases of these projects were assigned 90.39%/9.7% to residential and nonresidential customers based on the number of forecasted residential and nonresidential customers in 2026 for mixed use buildings or projects for both sectors.

(2) Forecasted cases of investigating distribution customer complaints were assigned about 90%/10% to residential and nonresidential customers based on the number of non-storm related outages of residential and nonresidential customers being restored in 2021.

(3) Totals are transferred to the Account 587 page.

Page 12 of 12

Worksheet: 23
 Created: 11/11/2024
 2026 Customer Based Allocation Factors
 Year: Account 587, by Project

2024DCAI 0000097

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 228 of 580

Exhibit No. 29
Confidential
2024 Customer Request Allocation System
Tab. Accounts 907-920

Commonwealth Edison Company The Determination of Allocation Factors for Customer Information					
	Forecasted 2026 100% Delivery of Accounts in Determinants (2)	Forecasted Average Number of Accounts in 2026	Allocation of Customer Information Costs to 2026 (3)	% of Total (3) ÷ (C) × (A) ÷ (B)	
	(A)	(C)	(C) × (2) × (A) ÷ (B)	(3) ÷ (C) × (A) ÷ (B)	
Residential					
1 Single-Family Without Electric Space Heat	19,989,851,970		\$24,305,842	61.880%	
2 Multi-Family Without Electric Space Heat	5,000,000,708		\$6,176,316	15.680%	
3 Single-Family With Electric Space Heat	663,002,043		\$807,798	2.024%	
4 Multi-Family With Electric Space Heat	4,404,898,746		\$4,404,898	4.405%	
Total Residential	27,058,453,467 (B)	3,778,487	\$33,394,712	84.074%	
Nonresidential					
5 Water Heat		72,438	\$1,092,128	2.774%	
6 Small Load (Up to 100 kW)		385,135	\$4,698,565	11.489%	
7 Medium Load (Over 100 to 400 kW)		18,243	\$244,098	0.622%	
8 Large Load (Over 400 to 10,000 kW)		3,861	\$58,721	0.142%	
9 Very Large Load (Over 10,000 to 10,000,000 kW)		1,837	\$27,697	0.070%	
10 Extra-Large Load (Over 10,000,000 kW)		44	\$663	0.002%	
11a. High Voltage (Up to 10,000 kW)		60	\$905	0.002%	
11b. High Voltage (Over 10,000 kW)		38	\$573	0.001%	
12 Electric-Included Lighting		1,770	\$26,687	0.080%	
13 Street Lighting - Dark to Dawn		3,711	\$55,951	0.142%	
14 Street Lighting - All Other Lighting		1,280	\$19,419	0.049%	
15 Railroad ⁽¹⁾		2	\$30	0.000%	
Total Nonresidential		498,725	\$6,129,237	15.500%	
Total		4,277,212 (D)	\$39,563,949 (E)	100.000%	

Customer information costs are costs recorded in Accounts 907 through 910

Account	Allocation Using Account to 2021 (A)	Excluded Costs	Residential	Nonresidential
907	\$0	\$0	\$0	\$0
908	\$13,728,082	\$963,280 ⁽²⁾	\$14,691,362 ⁽³⁾	\$5,138,080 ⁽⁴⁾
909	\$5,000,000	\$0	\$5,000,000 ⁽⁵⁾	\$7,988,000 ⁽⁶⁾
910	\$0	\$0	\$0	\$0
Total	\$18,728,082	\$963,280	\$19,694,362 (E)	\$12,126,080 (F)

Notes:

(1) The customers in the Railroad class use electricity only for traction power.

(2) Weather-normalized billing determinants.

(3) Allocation Using Confidential FERC Form No. 1 for 2021, page 321.

(4) Excluded EDIS and C&IE costs are transferred from the Accounts 908 by Project page.

(5) Assignment of the residential and nonresidential costs shown on the Accounts 908 by Project page.

(6) plus the assignment of the residential and nonresidential costs based on the number of residential and nonresidential customers in 2021.

(7) Allocation Using the Total Advertising and Selling Expense from page 1 of WPC-2 attached to Confidential Ex. 2A, the Electric Testimony of Nancy O'Brien from Exhibit No. 22-0362.

(8) Allocation Using the amount recorded in Account 909 for 2021 - Informational and Instructional Expense, was assigned to residential and nonresidential based on the number of residential and nonresidential customers.

(9) Determined from allocating residential only costs to (B) to residential delivery classes and nonresidential only costs to (F) to nonresidential delivery classes. Used in Confidential Ex. 17-17, Schedule 2b, Line 91, Pages 3 and 4 of 4.

Page 12 of 14

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 229 of 580

Order No. 20_____
 Conf No. 17.16
 2020 Customer-Based Allocation Factors
 Tele Account 808_39 Project

[illegible]


Notes:

(1) Allocation for project costs are assigned based upon the benefiting customer group and/or the effort spent for the respective customer groups in 2010.

(2) Assigned to operational and nonoperational by number of customers in each customer group in the *Business 907-910* pg.

(3) Transferred to the *Business 907-910* page.

Category		Sub-category		Item		Description		Value		Unit		Notes	
Category 1	Sub-category 1	Item 1	Description 1	Value 1	Unit 1	Notes 1	Category 1	Sub-category 1	Item 1	Description 1	Value 1	Unit 1	Notes 1
Category 2	Sub-category 2	Item 2	Description 2	Value 2	Unit 2	Notes 2	Category 2	Sub-category 2	Item 2	Description 2	Value 2	Unit 2	Notes 2
Category 3	Sub-category 3	Item 3	Description 3	Value 3	Unit 3	Notes 3	Category 3	Sub-category 3	Item 3	Description 3	Value 3	Unit 3	Notes 3
Category 4	Sub-category 4	Item 4	Description 4	Value 4	Unit 4	Notes 4	Category 4	Sub-category 4	Item 4	Description 4	Value 4	Unit 4	Notes 4
Category 5	Sub-category 5	Item 5	Description 5	Value 5	Unit 5	Notes 5	Category 5	Sub-category 5	Item 5	Description 5	Value 5	Unit 5	Notes 5
Category 6	Sub-category 6	Item 6	Description 6	Value 6	Unit 6	Notes 6	Category 6	Sub-category 6	Item 6	Description 6	Value 6	Unit 6	Notes 6
Category 7	Sub-category 7	Item 7	Description 7	Value 7	Unit 7	Notes 7	Category 7	Sub-category 7	Item 7	Description 7	Value 7	Unit 7	Notes 7
Category 8	Sub-category 8	Item 8	Description 8	Value 8	Unit 8	Notes 8	Category 8	Sub-category 8	Item 8	Description 8	Value 8	Unit 8	Notes 8
Category 9	Sub-category 9	Item 9	Description 9	Value 9	Unit 9	Notes 9	Category 9	Sub-category 9	Item 9	Description 9	Value 9	Unit 9	Notes 9
Category 10	Sub-category 10	Item 10	Description 10	Value 10	Unit 10	Notes 10	Category 10	Sub-category 10	Item 10	Description 10	Value 10	Unit 10	Notes 10



Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 233 of 580

2024 FIRM Budget No. 20-007					2024 FIRM Budget No. 20-007					2024 FIRM Budget No. 20-007				
Account	Current	Proposed	Change	% of Total	Account	Current	Proposed	Change	% of Total	Account	Current	Proposed	Change	% of Total
Category	Value	Value	Value	Value	Category	Value	Value	Value	Value	Category	Value	Value	Value	Value
I. ELECTRIC PLANT IN SERVICE														
A. INTANGIBLE PLANT														
Organization	301	80,275	80,275	-	Organization	301	80,275	80,275	-	Organization	301	80,275	80,275	-
Facilities and Contents	302	-	-	-	Facilities and Contents	302	-	-	-	Facilities and Contents	302	-	-	-
Intangible - Intangible Plant	303	80,275	80,275	-	Intangible - Intangible Plant	303	80,275	80,275	-	Intangible - Intangible Plant	303	80,275	80,275	-
Subtotal - INTANGIBLE PLANT	301-303	80,275	80,275	-	Subtotal - INTANGIBLE PLANT	301-303	80,275	80,275	-	Subtotal - INTANGIBLE PLANT	301-303	80,275	80,275	-
B. TRANSMISSION PLANT														
300-309	5,811,683,177	5,811,683,177	-	100.00%	300-309	5,811,683,177	5,811,683,177	-	100.00%	300-309	5,811,683,177	5,811,683,177	-	100.00%
C. DISTRIBUTION PLANT														
Land and Land Rights	300	75,079,897	75,079,897	0.0%	Land and Land Rights	300	75,079,897	75,079,897	0.0%	Land and Land Rights	300	75,079,897	75,079,897	0.0%
Structures and Improvements	301	874,888,824	874,888,824	0.0%	Structures and Improvements	301	874,888,824	874,888,824	0.0%	Structures and Improvements	301	874,888,824	874,888,824	0.0%
Station Equipment	302	3,394,488,423	3,394,488,423	0.0%	Station Equipment	302	3,394,488,423	3,394,488,423	0.0%	Station Equipment	302	3,394,488,423	3,394,488,423	0.0%
Storage Battery Equipment	303	85,145	85,145	0.0%	Storage Battery Equipment	303	85,145	85,145	0.0%	Storage Battery Equipment	303	85,145	85,145	0.0%
Power, Pumps and Motors	304	2,032,888,399	2,032,888,399	0.0%	Power, Pumps and Motors	304	2,032,888,399	2,032,888,399	0.0%	Power, Pumps and Motors	304	2,032,888,399	2,032,888,399	0.0%
Overhead Conductors and Devices	305	3,094,713,119	3,094,713,119	0.0%	Overhead Conductors and Devices	305	3,094,713,119	3,094,713,119	0.0%	Overhead Conductors and Devices	305	3,094,713,119	3,094,713,119	0.0%
Underground Conductors and Devices	306	6,050,485,959	6,050,485,959	0.0%	Underground Conductors and Devices	306	6,050,485,959	6,050,485,959	0.0%	Underground Conductors and Devices	306	6,050,485,959	6,050,485,959	0.0%
Line Transformers	307	1,477,287,746	1,477,287,746	0.0%	Line Transformers	307	1,477,287,746	1,477,287,746	0.0%	Line Transformers	307	1,477,287,746	1,477,287,746	0.0%
Services	308	1,368,833,089	1,368,833,089	0.0%	Services	308	1,368,833,089	1,368,833,089	0.0%	Services	308	1,368,833,089	1,368,833,089	0.0%
Installations on Customer Premises	309	75,079,897	75,079,897	0.0%	Installations on Customer Premises	309	75,079,897	75,079,897	0.0%	Installations on Customer Premises	309	75,079,897	75,079,897	0.0%
Subtotal - DISTRIBUTION PLANT	300-314	11,889,916,537	11,889,916,537	100.00%	Subtotal - DISTRIBUTION PLANT	300-314	11,889,916,537	11,889,916,537	100.00%	Subtotal - DISTRIBUTION PLANT	300-314	11,889,916,537	11,889,916,537	100.00%
D. GENERAL PLANT														
Land and Land Rights	300	28,118,841	28,118,841	0.0%	Land and Land Rights	300	28,118,841	28,118,841	0.0%	Land and Land Rights	300	28,118,841	28,118,841	0.0%
Structures and Improvements	301	106,463,673	106,463,673	0.0%	Structures and Improvements	301	106,463,673	106,463,673	0.0%	Structures and Improvements	301	106,463,673	106,463,673	0.0%
Leasehold Improvements	302	10,250,000	10,250,000	0.0%	Leasehold Improvements	302	10,250,000	10,250,000	0.0%	Leasehold Improvements	302	10,250,000	10,250,000	0.0%
Other Facilities and Equipment	303	106,463,673	106,463,673	0.0%	Other Facilities and Equipment	303	106,463,673	106,463,673	0.0%	Other Facilities and Equipment	303	106,463,673	106,463,673	0.0%
Transmission Equipment	304	244,583,214	244,583,214	0.0%	Transmission Equipment	304	244,583,214	244,583,214	0.0%	Transmission Equipment	304	244,583,214	244,583,214	0.0%
Station Equipment	305	7,088,441	7,088,441	0.0%	Station Equipment	305	7,088,441	7,088,441	0.0%	Station Equipment	305	7,088,441	7,088,441	0.0%
Power, Pumps and Motors	306	212,467,199	212,467,199	0.0%	Power, Pumps and Motors	306	212,467,199	212,467,199	0.0%	Power, Pumps and Motors	306	212,467,199	212,467,199	0.0%
Laboratory Equipment	307	1,000,000	1,000,000	0.0%	Laboratory Equipment	307	1,000,000	1,000,000	0.0%	Laboratory Equipment	307	1,000,000	1,000,000	0.0%
Communication Equipment	308	1,000,000	1,000,000	0.0%	Communication Equipment	308	1,000,000	1,000,000	0.0%	Communication Equipment	308	1,000,000	1,000,000	0.0%
Other Intangible Equipment	309	1,000,000	1,000,000	0.0%	Other Intangible Equipment	309	1,000,000	1,000,000	0.0%	Other Intangible Equipment	309	1,000,000	1,000,000	0.0%
Subtotal - GENERAL PLANT	300-309	7,088,773,238	7,088,773,238	100.00%	Subtotal - GENERAL PLANT	300-309	7,088,773,238	7,088,773,238	100.00%	Subtotal - GENERAL PLANT	300-309	7,088,773,238	7,088,773,238	100.00%
E. DEPRECIATION RESERVE														
Intangible	000-0	(50,000,000)	(50,000,000)	-	Intangible	000-0	(50,000,000)	(50,000,000)	-	Intangible	000-0	(50,000,000)	(50,000,000)	-
Transmission	000-1	(1,230,561,786)	(1,230,561,786)	-	Transmission	000-1	(1,230,561,786)	(1,230,561,786)	-	Transmission	000-1	(1,230,561,786)	(1,230,561,786)	-
Distribution	000-2	(1,230,561,786)	(1,230,561,786)	-	Distribution	000-2	(1,230,561,786)	(1,230,561,786)	-	Distribution	000-2	(1,230,561,786)	(1,230,561,786)	-

2024DCAI 0000103

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 234 of 580

Commonwealth Edison Company				Docket No. 23-0700			
Allocation of Costs for EGSOs Using Prior EGSOs Allocations				Exhibit C-1, 1A Allocation of Costs for EGSOs WP for 1990 to 2010			
Land and Land Rights	(1,718,702)	(1,718,702)		(1,270,000)	(1,270,000)	448,702	-0.2%
Structures and Improvements	(102,212,240)	(102,212,240)		(100,212,240)	(98,000,000)	22,212,240	1.3%
Station Equipment	(901,100,000)	(901,100,000)		(886,482,000)	(873,000,000)	13,598,000	20.2%
Station Relays and Equipment	(102,140)	(102,140)		(102,140)	(102,140)	-	0.0%
Poles, Towers and Poles	(889,402,000)	(889,402,000)		(1,007,724,000)	(1,007,724,000)	(118,322,000)	-12.4%
Overhead Conductors and Devices	(900,404,000)	(900,404,000)		(1,007,000,000)	(1,007,000,000)	(106,596,000)	-11.8%
Underground Cables	(100,170,700)	(100,170,700)		(100,170,700)	(100,170,700)	-	0.0%
Underground Conductors and Devices	(1,000,214,000)	(1,000,214,000)		(1,007,000,000)	(1,007,000,000)	(93,214,000)	-9.3%
Line Transformers	(700,402,000)	(700,402,000)		(700,402,000)	(700,402,000)	-	0.0%
Service	(800,000,000)	(800,000,000)		(800,000,000)	(800,000,000)	-	0.0%
Meters	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Installation on Customer Premises	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Other Lighting and Signals	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Subtotal - DISTRIBUTION PLANT	(1,000,000,000)	(1,000,000,000)		(1,000,000,000)	(1,000,000,000)	-	0.0%
General	-	-		-	-	-	-
Land and Land Rights	(80,000,000)	(80,000,000)		(80,000,000)	(80,000,000)	-	0.0%
Structures and Improvements	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Landmark Acquisition Reserve	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Office Furniture and Equipment	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Transportation Equipment	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Tools, Shop and Garage Equipment	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Power Generation Equipment	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Communication Equipment	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Miscellaneous Equipment	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Other Intangible Equipment	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Asset Retire Costs & Removal Work in Prog - Gen. Pl.	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Subtotal - GENERAL PLANT	(1,000,000,000)	(1,000,000,000)		(1,000,000,000)	(1,000,000,000)	-	0.0%
ADJUSTMENTS TO DEPRECIATION RESERVE	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Gen. Pl. & Intang. Depreciation & Adjust	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
Subtotal	(100,000,000)	(100,000,000)		(100,000,000)	(100,000,000)	-	0.0%
TOTAL DEPRECIATION RESERVE	100	100,000,000	100,000,000	100	100,000,000	100,000,000	100,000,000

2024DCAI 0000104

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 235 of 580

Commonwealth Edison Company				Docket No. 19-0000			
Allocation of Costs for EGSOs Using Prior EGSOs Allocations				Commodity 1, 1A			
				Allocation of Costs for EGSOs W/P			
				Year 19190 to 20190			
Customer Installation Expenses	587	24,855,945	24,855,945	Customer Installation Expenses	587	23,437,684	23,437,684
Min. Distribution Expenses	588	87,778,262	87,778,262	Min. Distribution Expenses	588	86,853,796	86,853,796
Rates	589	2,986,987	2,986,987	Rates	589	2,793,626	2,793,626
Min. Supervision & Engineering	590	4,752,502	4,752,502	Min. Supervision & Engineering	590	4,402,742	4,402,742
Min. of Structure	591	2,108,982	2,108,982	Min. of Structure	591	2,043,681	2,043,681
Maintenance of Station Equipment	592	48,881,448	48,881,448	Maintenance of Station Equipment	592	48,738,658	48,738,658
Maintenance of Overhead Lines	593	158,521,482	157,533,482	Maintenance of Overhead Lines	593	157,926,108	157,522,268
Maintenance of Underground Lines	594	45,685,882	45,685,882	Maintenance of Underground Lines	594	45,538,487	45,538,487
Maintenance of Line Transformers	595	4,889,821	4,889,821	Maintenance of Line Transformers	595	4,865,284	4,865,284
Maintenance of Street Lights	596	3,186,121	3,186,121	Maintenance of Street Lights	596	2,980,652	2,980,652
Maintenance of Electric Plant	597	4,707,000	4,707,000	Maintenance of Electric Plant	597	4,522,256	4,522,256
Other Pro-Forma Adjustments to Disc. Cost	598	6,795,267	6,795,267	Other Pro-Forma Adjustments to Disc. Cost	598	6,588,617	6,588,617
Subtotal - DISTRIBUTION EXPENSES	587-598	388,987,578	388,987,578	Subtotal - DISTRIBUTION EXPENSES	587-598	379,928,667	379,928,667
Total - OPER. AND MAINT. EXPENSE		834,257,678	834,257,678	Total - OPER. AND MAINT. EXPENSE		815,762,513	815,762,513
C. CUSTOMER ACCOUNTS AND SERVICE				C. CUSTOMER ACCOUNTS AND SERVICE			
Supervision	901	847,228	846,000	Supervision	901	784,724	783,704
Customer Records & Collection Expense	902	147,288,368	147,288,368	Customer Records & Collection Expense	902	147,275,348	147,275,348
On Account to Supply Meter	903	28,816,762	28,816,762	On Account to Supply Meter	903	28,786,488	28,786,488
Min. Customer Accounts Expense	904	-	-	Min. Customer Accounts Expense	904	-	-
Other Customer Accounts Performance	905	-	-	Other Customer Accounts Performance	905	-	-
Subtotal - Customer Accounts Expense	901-905	185,752,358	185,752,358	Subtotal - Customer Accounts Expense	901-905	187,846,560	187,846,560
Supervision	907	-	-	Supervision	907	-	-
Customer Assistance Exp. Electric	908	28,153,862	27,986,262	Customer Assistance Exp. Electric	908	28,114,728	28,061,728
Information, Instructional Advertising	909	9,202,295	9,202,295	Information, Instructional Advertising	909	8,854,894	8,854,894
Pro-Forma Adjustments (C-7 to C-1)	907-909	37,356,158	37,188,557	Pro-Forma Adjustments (C-7 to C-1)	907-909	34,979,622	34,979,622
Subtotal - Customer Service & Info.				Subtotal - Customer Service & Info.			
Supervision	911	-	-	Supervision	911	-	-
Democratizing & Selling Expenses	912	-	-	Democratizing & Selling Expenses	912	-	-
Advertising Expenses	913	-	-	Advertising Expenses	913	-	-
Microbusiness Sales Expenses	914	-	-	Microbusiness Sales Expenses	914	-	-
Subtotal - Sales Expense	911-914	-	-	Subtotal - Sales Expense	911-914	-	-
Total - CUST ACCTG, SERV, & SALES EXP	901-914	219,360,906	219,360,906	Total - CUST ACCTG, SERV, & SALES EXP	901-914	202,285,153	202,285,153
D. ADMINISTRATIVE AND GENERAL				D. ADMINISTRATIVE AND GENERAL			
LABOR RELATED EXPENSES				LABOR RELATED EXPENSES			
Administrative & General Salaries	920	53,759,228	53,759,228	Administrative & General Salaries	920	53,619,187	53,619,187
On to Supply Meter	921	24,288,627	24,288,627	On to Supply Meter	921	24,288,627	24,288,627
Other Supplies & Expenses	922	181,288,778	181,288,778	Other Supplies & Expenses	922	181,288,778	181,288,778
Admin Expenses - Transportation/Comm	923	137,255,650	137,255,650	Admin Expenses - Transportation/Comm	923	137,255,650	137,255,650
Outside Services Employed	924	134,049,897	134,049,897	Outside Services Employed	924	134,049,897	134,049,897
Employee Pension and Benefits	925	134,049,897	134,049,897	Employee Pension and Benefits	925	134,049,897	134,049,897
Healthcare	926	134,049,897	134,049,897	Healthcare	926	134,049,897	134,049,897
Subtotal - C & M Accounts	920-926	458,884,977	458,884,977	Subtotal - C & M Accounts	920-926	458,884,977	458,884,977
PLANT RELATED EXPENSES				PLANT RELATED EXPENSES			
Property Insurance	928	1,135,856	1,135,856	Property Insurance	928	289,146	289,146
Repairs and Damages	929	12,861,148	12,861,148	Repairs and Damages	929	12,861,148	12,861,148
Maintenance of General Plant (disc. acc't 102)	930	42,861,428	42,861,428	Maintenance of General Plant (disc. acc't 102)	930	42,861,428	42,861,428
Subtotal - C & M Accounts Sal. Exp. 102				Subtotal - C & M Accounts Sal. Exp. 102			
OTHER A&G EXPENSES				OTHER A&G EXPENSES			
Franchise Requirements	932	38,883,762	38,883,762	Franchise Requirements	932	35,875,171	35,875,171
Regulatory Commission Expenses	933	2,000,000	2,000,000	Regulatory Commission Expenses	933	2,000,000	2,000,000
A&G Overhead - Subsidies	934	38,883,762	38,883,762	A&G Overhead - Subsidies	934	35,875,171	35,875,171
General Advertising Expenses	935	1,135,856	1,135,856	General Advertising Expenses	935	1,135,856	1,135,856
Microbusiness General Expenses	936	17,705,122	17,705,122	Microbusiness General Expenses	936	17,893,114	17,893,114

2024DCAI 0000105

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 236 of 580

Commonwealth Edison Company Allocation of Costs for EGSOs Using Prior EGSOs Allocations					Docket No. 23-0700 Exhibit C-1, 1-A Allocation of Costs for EGSOs WP Yrs. 2024 to 2026				
Item	901	2,491,854	-	2,491,854	Item	901	2,491,854	-	2,491,854
Plantwide	627-602	21,020,000	(1,700,000)	19,320,000	Plantwide	627-602	21,020,000	(1,700,000)	19,320,000
Subtotal					Subtotal				
SUBTOTAL AGG EXPENSES	620-602	488,388,383	(51,211,528)	437,176,855	SUBTOTAL AGG EXPENSES	620-602	488,388,383	(51,211,528)	437,176,855
PRO FORMA AND RATE MAKING ADJUSTMENTS					PRO FORMA AND RATE MAKING ADJUSTMENTS				
AGG Adjustments		-	-	-	AGG Adjustments		-	-	-
Other Rate-making adjustments to AGG		-	-	-	Other Rate-making adjustments to AGG		-	-	-
Subtotal		-	-	-	Subtotal		-	-	-
TOTAL AGG EXPENSES		488,388,383	(51,211,528)	437,176,855	TOTAL AGG EXPENSES		488,388,383	(51,211,528)	437,176,855
TOTAL OPERATING EXPENSES		1,541,887,788		1,486,612,328	TOTAL OPERATING EXPENSES		1,486,612,328		1,486,612,328
V. DEPRECIATION EXPENSE									
Intangible Plant	404	78,114,355	-	78,114,355	Intangible Plant	404	83,081,437	-	83,081,437
Transmission Plant	403.5	131,429,100		131,429,100	Transmission Plant	403.5	131,429,100		131,429,100
Distribution Plant		85,064		85,064	Distribution Plant		81,709		81,741
Land and Land Rights		13,767,876		13,767,876	Land and Land Rights		13,767,876		13,767,876
Structures and Improvements		75,181,848		75,181,848	Structures and Improvements		75,181,848		75,181,848
Station Equipment		1,548,427		1,548,427	Station Equipment		1,548,427		1,548,427
Storage Battery Equipment		15,811,457		15,811,457	Storage Battery Equipment		15,811,457		15,811,457
Pipes, Trenches and Poles		13,812,232		13,812,232	Pipes, Trenches and Poles		13,812,232		13,812,232
Overhead Conductors and Devices		13,812,232		13,812,232	Overhead Conductors and Devices		13,812,232		13,812,232
Underground Conductors and Devices		13,812,232		13,812,232	Underground Conductors and Devices		13,812,232		13,812,232
Line Transformers		13,812,232		13,812,232	Line Transformers		13,812,232		13,812,232
Service		13,812,232		13,812,232	Service		13,812,232		13,812,232
Meters		13,812,232		13,812,232	Meters		13,812,232		13,812,232
Installations on Customer Premises		13,812,232		13,812,232	Installations on Customer Premises		13,812,232		13,812,232
Street Lighting and Signals		13,812,232		13,812,232	Street Lighting and Signals		13,812,232		13,812,232
Subtotal - DISTRIBUTION PLANT		488,388,383		488,388,383	Subtotal - DISTRIBUTION PLANT		488,388,383		488,388,383
General Plant		1,238,226		1,238,226	General Plant		1,238,226		1,238,226
Leasehold Improv. Amortization		1,238,226		1,238,226	Leasehold Improv. Amortization		1,238,226		1,238,226
Structures and Improvements		1,238,226		1,238,226	Structures and Improvements		1,238,226		1,238,226
Other Furniture and Equipment		1,238,226		1,238,226	Other Furniture and Equipment		1,238,226		1,238,226
Transportation Equipment		1,238,226		1,238,226	Transportation Equipment		1,238,226		1,238,226
Tools, Shop and Garage Equipment		1,238,226		1,238,226	Tools, Shop and Garage Equipment		1,238,226		1,238,226
Laboratory Equipment		1,238,226		1,238,226	Laboratory Equipment		1,238,226		1,238,226
Power Operating Equipment		1,238,226		1,238,226	Power Operating Equipment		1,238,226		1,238,226
Communication Equipment		1,238,226		1,238,226	Communication Equipment		1,238,226		1,238,226
Maintenance Equipment		1,238,226		1,238,226	Maintenance Equipment		1,238,226		1,238,226
Other Intangible - Class 19		1,238,226		1,238,226	Other Intangible - Class 19		1,238,226		1,238,226
Proforma Adjustments		-		-	Proforma Adjustments		-		-
Other Adjustments		-		-	Other Adjustments		-		-
Subtotal		-		-	Subtotal		-		-
TOTAL DEPRECIATION EXPENSE	403	882,288,228	(82,117)	882,215,111	TOTAL DEPRECIATION EXPENSE	403	882,288,228	(82,117)	882,215,111
VI. TAXES OTHER THAN INCOME TAXES (EXCLUDING ALIENS ELECTRICITY DISTRIBUTION TAX)									
Payroll & Other Labor-Related Taxes	408.05	26,762,000	(112,000)	26,650,000	Payroll & Other Labor-Related Taxes	408.05	26,762,000	(112,000)	26,650,000
Sales & Merc. Taxes	408.15	1,000,000	(500,000)	500,000	Sales & Merc. Taxes	408.15	1,000,000	(500,000)	500,000
Real Estate Taxes	408.17	2,000,000	(1,000,000)	1,000,000	Real Estate Taxes	408.17	2,000,000	(1,000,000)	1,000,000
Franchise Taxes		2,000,000	(1,000,000)	1,000,000	Franchise Taxes		2,000,000	(1,000,000)	1,000,000
Other Taxes - Public Utility Fund		2,000,000	(1,000,000)	1,000,000	Other Taxes - Public Utility Fund		2,000,000	(1,000,000)	1,000,000
Subtotal - General Taxes		36,762,000	(1,612,000)	35,150,000	Subtotal - General Taxes		36,762,000	(1,612,000)	35,150,000
VII. OTHER OPERATING REVENUES									

2024DCAI 0000106

Commonwealth Edison Company					Decision No. 22, _____				
Allocation of Costs for ECDS Using Prior ECDS Allocations					ComEd Ex. 17.14				
					Allocation of Costs for ECDS w/				
					Rate 2.076% to 2.078%				
Forfeited Discounts	450	29,074,438	(8,438,000)	22,646,438	Forfeited Discounts	450	29,973,544	(8,387,000)	13,896,544
Misc Service Revenues	451	17,477,789		17,477,789	Misc Service Revenues	451	13,747,781		13,747,781
									(2,838,864)
									(3,729,868)
Rent from Electric Property	454				Rent from Electric Property	454			
Motor and Transformer Rents		52,857,000		52,857,000	Motor and Transformer Rents		52,518,000		(339,000)
Other Rents (Distribution only)		25,423,000		25,423,000	Other Rents (Distribution only)		25,827,000		6,404,000
Transmissions & Non-CST		11,474,000		11,474,000	Transmissions & Non-CST		11,858,000		616,000
Revenues					Revenues				
Total Asset Cost		95,754,227	-	95,754,227	Total Asset Cost		95,353,320	-	4,400,907
Other Ass. Cost (Other Dist. & Trans. Rates)	456	739,739,000		739,739,000	Other Ass. Cost (Other Dist. & Trans. Rates)	456	739,321,000		26,367,000
Additional Fac. Chg. - Fac. Lighting		7,030,000	20,042	7,050,042	Additional Fac. Chg. - Fac. Lighting		6,967,000		(1,46,042)
Nonmajor Whitehead Distribution Revenue		6,600,000		6,600,000	Nonmajor Whitehead Distribution Revenue		6,700,000		122,000
Other Electric Revenues		732,429,000		732,429,000	Other Electric Revenues		705,821,000		26,325,958
Other Adjustment - CST Only		19,829,000		19,829,000	Other Adjustment - CST Only		19,299,000		(570,000)
Total Other Operating Revenues		803,569,207	(8,438,000)	877,174,249	Total Other Operating Revenues		916,094,325	(8,387,000)	905,637,325
									32,863,076
									98.02%
									98.12%
									85.95%
									23.74%
									8.64%
									48.68%

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 238 of 580

Commonwealth Edison Company

Docket No.23-12734

Allocation of Costs for ECOSIS Using Prior ECOSIS Allocations

ComEd Ex. 17.1A

Allocation of Costs for ECOSIS WP

Tab: 23PRJ to 23PRJ

Modified Schedule 1b General Plant DST Factors
to Only Allocate to Distribution to Match MRP Allocation

ECOSIS Line	Current %	Modified DST Costs %
353 TRANSENCON	0.199500	0
354 L-TOTAL DIST.	0.691000	0.804067
355 L-DIST. (R01-916)	0.168600	0.195933
356 GP-389	1.000000	
357	1.000000	
358		
359	Shares	
360 TRANSENCON	0.199500	0
361 L-TOTAL DIST.	0.691000	0.804067
362 L-DIST. (R01-916)	0.168600	0.195933
363 GP-390	1.000000	
364	1.000000	
365		
366		
367 TRANSENCON	0.161337	0
368 L-TOTAL DIST.	0.746461	0.882856
369 L-DIST. (R01-916)	0.098242	0.117144
370 GP-390-L	1.000000	
371	1.000000	
372		
373		
374 TRANSENCON	0.161538	0
375 L-TOTAL DIST.	0.746335	0.882968
376 L-DIST. (R01-916)	0.098127	0.117032
377 GP-390-AR	1.000000	
378	1.000000	
379		
380		
381 TRANSENCON	0.161538	0
382 L-TOTAL DIST.	0.746335	0.882968
383 L-DIST. (R01-916)	0.098127	0.117032
384 GP-390-AM	1.000000	
385	1.000000	
386		
387	Shares	
388 TRANSENCON	0.146000	0
389 L-TOTAL DIST.	0.530700	0.621429
390 L-DIST. (R01-916)	0.323300	0.378571
391 GP-391	1.000000	
392	1.000000	
393		
394	Shares	
395 TRANSENCON	0.083000	0
396 L-TOTAL DIST.	0.830000	0.905125
397 L-DIST. (R01-916)	0.087000	0.094875
398 GP-392	1.000000	
399	1.000000	
400		
401	Shares	
402 TRANSENCON	0.146000	0
403 L-TOTAL DIST.	0.530700	0.621429
404 L-DIST. (R01-916)	0.323300	0.378571
405 GP-393	1.000000	
406	1.000000	
407		
408	Shares	
409 TRANSENCON	0.213900	0.0000
410 L-TOTAL DIST.	0.786100	0.0000
411 L-DIST. (R01-916)	0.000000	0.0000
412 GP-394	1.000000	
413	1.000000	
414		
415	Shares	
416 TRANSENCON	0.213900	0.0000
417 L-TOTAL DIST.	0.786100	0.0000
418 L-DIST. (R01-916)	0.000000	0.0000
419 GP-395	1.000000	
420	1.000000	
421		
422	Shares	
423 TRANSENCON	0.213900	0.0000
424 L-TOTAL DIST.	0.786100	0.0000
425 L-DIST. (R01-916)	0.000000	0.0000
426 GP-396	1.000000	
427	1.000000	
428		
429	Shares	
430 TRANSENCON	0.311000	0.0000
431 L-TOTAL DIST.	0.689000	0.0000
432 L-DIST. (R01-916)	0.000000	0.0000
433 GP-397	1.000000	
434	1.000000	
435		
436	Shares	
437 TRANSENCON	0.146000	0.0000
438 L-TOTAL DIST.	0.530700	0.6214
439 L-DIST. (R01-916)	0.323300	0.3786
440 GP-398	1.000000	
441	1.000000	
442		

Information Request
Re: ICC Docket No. 24-0378 Commonwealth Edison Company, Final Order
Supply-Delivery Cost Allocation Investigation

Commonwealth Edison Company's Response to
Illinois Competitive Energy Association and Retail Energy Supply Association
("ICEA-RESA") Information Requests
ICEA-RESA 1.01 – ICEA-RESA 1.08
Date Received: April 30, 2025
Date Served: June 2, 2025

Given that there are three separate steps in the allocation of costs for rate-making, being Functionalization (allocation between regulated and unregulated functions), Classification (allocation into fixed, variable and customer costs) and Allocation (allocation to customer classes), please answer the following questions:

REQUEST NO. ICEA-RESA 1.02:

Please explain the methods and economic rationale for those methods used in functionalizing costs within each Uniform System of Account ("USoA") account number.

- a. For example, how does ComEd allocate labor costs from its affiliated companies into ComEd?
- b. Please identify for each USoA where there are shared costs with ComEd's parent company (whether direct or indirect) or affiliates how such costs are allocated to ComEd.

RESPONSE:

- a. See the response to subpart b.
- b. Annually, ComEd files its Form 21 Annual Report of Electric Utilities Licensees and/or Natural Gas Utilities with the ICC. That report includes a listing of transactions with affiliated companies showing the services provided, the associated affiliate, the FERC accounts charged, the amount and the method of cost allocation. See the attachment labeled as ICEA-RESA 1.02_Attach 1 for ComEd's 2024 Form 21 that was filed in March 2025. On pages 47, 47.1-47.5, it describes the transactions and cost allocations used. In many instances, Exelon Business Service Company ("Exelon BSC") provides services directly to ComEd. The costs for these services are "directly billed" to ComEd. In other instances, Exelon BSC provides services to more than one Exelon operating company. In such cases, the costs cannot be directly assigned, but are instead allocated to ComEd and other entities using allocation methods and ratios described in the ICC-approved General Services Agreement ("GSA") applicable to ComEd and Exelon BSC, and Illinois Amendment No. 1 to the GSA filed with the ICC. See the attachment labeled as ICEA-RESA 1.02_Attach 2 for the GSA agreement. The allocation factors used are also filed with the ICC. The listing of allocation percentages, as of January 1, 2025, used to charge ComEd is included and described in the attachment labeled as ICEA-RESA 1.02_Attach 3. Each of these methodologies is designed to assign the costs to the particular utility or other Exelon company that caused the costs to be incurred (i.e., the cost causation principle) and provide a high degree of assurance that ComEd customers pay only for Exelon BSC services provided on their behalf.

FORM 21 ILCC

ANNUAL REPORT OF ELECTRIC UTILITIES
LICENSEES AND/OR NATURAL GAS UTILITIES

TO THE

ILLINOIS COMMERCE COMMISSION



Exact Legal Name of Respondent (Company)	Year of Report
Commonwealth Edison Company	December 31, 2024

This state agency is requesting disclosure of information that is necessary to accomplish the statutory purpose as outlined in Section 5-109 of the Public Utilities Act [220 ILCS 5/5-109]. Disclosure of this information is REQUIRED. Failure to provide any information could result in a fine of \$100 per day under Section 5-109 of the Public Utilities Act.

2024DCAI 0000110

ANNUAL REPORT OF ELECTRIC UTILITIES,
LICENSEES AND/OR NATURAL GAS UTILITIES

Name of Respondent	This Report Is: Date of Report (Mo./Da./Yr.)	Year of Report
Commonwealth Edison Company	(X) An Original	December 31, 2024

Exact Legal Name of Respondent:

Commonwealth Edison Company

Previous Name and Date of Change (if name changed during reporting year):

Address of Principal Office at End of Year (street, city, state, zip code):
10 S. Dearborn Street, Chicago, Illinois 60603

Name and Title of Contact Person:
Caroline Fulginiti, Vice President and Assistant Controller, Exelon

Address of Contact Person (street, city, state, zip code):
2301 Market Street, Philadelphia, Pennsylvania, 19103

Telephone Number of Contact Person, including Area Code:
(215) 841-5790

Email address of Contact Person:

caroline.fulginiti@exeloncorp.com

Utility website:

www.comed.com

ANNUAL REPORT OF ELECTRIC UTILITIES,
LICENSEES AND/OR NATURAL GAS UTILITIES
INSTRUCTIONS FOR FILING FORM 21 ILCC

GENERAL INFORMATION

- I. **PURPOSE:**
This form is a regulatory support requirement (Public Utilities Act, Section 5-109). It is designed to collect financial and operational information from electric and gas utilities subject to the jurisdiction of the Illinois Commerce Commission.
- II. **WHO MUST SUBMIT:**
All electric and gas utilities subject to the Illinois Commerce Commission jurisdiction.
- III. **WHAT, WHERE AND WHEN TO SUBMIT**
i. Submit a completed and verified copy of Form 21 ILCC on or before MARCH 31 of the year following the year covered by this report (three hole punched but not bound) to:
ILLINOIS COMMERCE COMMISSION
527 East Capitol Avenue
Springfield, IL 62701
ii. Submit immediately upon publication one copy of the submitted FERC Form Nos. 1 and/ or 2, if applicable, to the above address. The submitted copy should be three hole punched, but not bound.
iii. Submit immediately upon publication one copy of the SEC 10-K Report, if applicable, to the above address. The submitted copy should be three hole punched.
iv. Submit immediately upon publication one copy of the Annual Report to Stockholders. The submitted copy should be three hole punched.
v. Submit an electronic file of Form 21 ILCC and electronic files or hyperlinks to the FERC Form 1, the SEC 10-K, and the Annual Report to Stockholders when submitted in hard copy to the Illinois Commerce Commission to fad@icc.illinois.gov.
- IV. **REGISTERED AGENT**
Exact Name of Registered Agent: E. Glenn Rippie, Senior Vice President and General Counsel, Commonwealth Edison Company
Street or Local Address: 10 S. Dearborn Street
City: Chicago State: Illinois Zip Code: 60603
Telephone (779) 231-0107

ANNUAL REPORT OF ELECTRIC UTILITIES,
LICENSEES AND/OR NATURAL GAS UTILITIES

GENERAL INSTRUCTIONS

- I. This form of annual report is prepared in conformity with the applicable Uniform System of Accounts and all of the accounting terminology used herein is in accordance therewith.
- II. Enter in whole numbers only, except where otherwise noted. (Enter cents for averages and figures per unit where cents are important.) The truncating of cents is allowed except on the four basic financial statements where rounding to dollars is required. The amounts shown on all supporting pages must agree with the amounts entered on the statements that they support. When applying thresholds to determine significance for reporting purposes, use for balance sheet accounts in the balances at the end of the current reporting year, and use for statement of income accounts the current year's amounts.
- III. Complete each question fully and accurately, even if it has been answered in a previous annual report. Enter the word "NONE" where it truly and completely states the fact.
- IV. The schedules within Form 21ILCC are classified as follows:
- 0 Series - General Corporate Schedules required by all utilities filing Form 21 ILCC
 - 100 Series - General Corporate Schedules required by gas only utilities not submitting FERC Form No. 2.
 - 200 Series - Balance Sheet Supporting Schedules required by gas utilities not submitting FERC Form No. 2.
 - 300 Series - Income Supporting Schedules required by gas utilities not submitting FERC Form No. 2.
 - 500 Series - Gas Plant Statistical Data required by gas utilities not submitting FERC Form No. 2.
 - 600 Series - Electric Data required by all electric utilities.
 - 700 Series - Gas Data required by all gas utilities.
- Electric only utilities that submit FERC Form No. 1 to the Illinois Commerce Commission (ICC) must submit the following schedules : 0 Series and 600 Series.
- Combination utilities (utilities that provide both electric and gas service in Illinois) that submit FERC Form No. 1 (but not FERC Form No. 2) to the ICC must submit the following schedules: 0 Series, 200 Series, 300 Series, 500 Series, 600 Series, and 700 Series.
- Combination utilities (utilities that provide both electric and gas service in Illinois) that submit FERC Form Nos. 1 and 2 to the ICC must submit the following schedules: 0 Series, 600 Series and 700 Series.
- Gas only utilities that submit FERC Form No. 2 to the ICC must submit the following schedules: 0 Series and 700 Series.
- Gas only utilities that do not submit FERC Form No. 2 to the ICC must submit the following schedules: 0 Series, 100 Series, 200 Series, 300 Series, 500 Series and 700 Series.
- If a schedule within a series is not applicable to the respondent, enter the words "NOT APPLICABLE" on the particular page or omit the page and enter "N/A" or "NOT APPLICABLE" in the "Remarks" column on the List of Schedules on pages vi through x. If pages are deleted, indicate in the footer of the prior provided page number of the next subsequently provided page.
- V. It is preferred that all data be typed on the form. Entries of an opposite character (such as decreases reported in a column providing for both increases and decreases) should be enclosed in parentheses.
- VI. Enter the month, day and year for all dates. Use customary abbreviations. The "Date of Report" at the top of each page is applicable only to the resubmission (see VII below).
- VII. When making revisions, resubmit only those pages that have been changed from the original submission. Submit the same number of copies as required for filing the form. Include with the resubmission the Identification and Attestation page as the last page. Mail dated resubmission to:
ILLINOIS COMMERCE COMMISSION
527 East Capitol Avenue
Springfield, IL 62701
- VIII. Provide a supplemental statement further explaining accounts or pages as necessary. Attach the supplemental statement (8 1/2 x 11 inch size) to the page being supplemented. Provide the appropriate identification information, including the title(s) of the page and the page number supplemented.
- IX. Do not make references to reports of previous years or to other reports in lieu of required entries, except as specifically authorized. The annual report should in all particulars be complete in itself.
- X. Wherever (schedule) pages refer to figures from a previous year, the figures reported must be based upon those shown on the annual report of the previous year, or an appropriate explanation given as to why the different figures were used.
- XI. Respondents may submit computer printed schedules (reduced to 8 1/2 x 11) instead of the schedules herein if they are substantially the same format.
- XII. Where Illinois Commerce Commission authority is to be supplied, enter the applicable docket number.
- XIII. The word "respondent", whenever used in this report, means the person, corporation, licensee, agency, authority, or other legal entity or instrumentality in whose behalf the report is made.
- XIV. Because of the limited space afforded on some Form 21 ILCC schedules, dollar signs may be omitted where necessary. The rounding of numbers in thousands is permissible in cases where there is insufficient room for all digits. However, notations to this effect must be made in a conspicuous location on the page on which the rounding occurs.

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 244 of 580

FORM 21 ILCC LIST OF SCHEDULES		
Schedules	Page	Remarks
Identification	i	
General Information	ii	
General Instructions	iii	
Excerpts from the Law	iv	N/A
List of Schedules	v-vii	
GENERAL CORPORATE SCHEDULES REQUIRED BY ALL UTILITIES FILING FORM 21 ILCC (0 Series)		
Verification, Attestation	1	
Comparative Balance Sheet	2-5	
Statement of Retained Earnings	6-6a	
Statement of Income for the Year	7-7b	
Illinois Electric Operating Revenues	8-8a	
Illinois Megawatt Hrs. Sold/Delivered & Avg. No. of Customers per Month	9-9a	
Illinois Gas Net Operating Revenues	11-11a	N/A
Gas Transportation Revenues	11b	N/A
Cost Allocation Methodologies	12	N/A
Identification of Differences between Information Reported on FERC Schedules and Information Reported on Pages 2 through 7 of Form 21 ILCC	13	
Analysis of Unbilled Revenues	13(a)	
Reconciliation of Gross Revenue Tax	14	N/A
Promotional Practices of Electric and Gas Public Utilities	15	N/A
Special Funds	16	
Special Deposits	16	
Notes Receivable	17	
Other Accounts Receivable	17	
Receivables from Associated Companies	18	
Miscellaneous Current and Accrued Assets	19	
Materials and Supplies	20	
Notes Payable	21	
Payables to Associated Companies	21	
Long Term Debt (Accounts 221, 222, 223 & 224)	22-23	
Unamortized Loss and Gain on Reacquired Debt (Accts. 189, 257)	24	
Discount on Common Stock Issuance and Preferred Stock Issuance	25	
Unamortized Debt Expense Premium & Discount on Long-Term Debt	26-27	
Securities Issued or Assumed and Securities Refunded or Retired During the Year	28	
Investments (Accounts 123, 124, 136)	29-30	
Particulars Concerning Certain Other Income Accounts	31	
Employee Data	32	
Charges for Outside, Professional & Other Consultative Services	33	
Common Utility Plant & Expense	34	N/A
Nonutility Property	41	
Accumulated Provision for Depreciation & Amortization of Nonutility Property	41	
Accumulated Deferred Income Taxes - Accelerated Amortization Property	42-43	N/A
General Description of Construction Overhead Procedure	44	
Capital Stock Subscribed, Liability for Conversion, Premium on Capital Stock and Installments Received on Capital Stock	45	
Discount on Capital Stock and Capital Stock Expense	46	
Transactions with Associated (Affiliated) Companies (Effective 1/1/2009)	47	
Accumulated Provision for Uncollectible Accounts Receivable	48	

Form 21 ILCC

page v

2024DCAI 0000114

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 245 of 580

FORM 21 ILCC		
LIST OF SCHEDULES		
Schedules	Page	Remarks
GENERAL CORPORATE SCHEDULES REQUIRED BY GAS ONLY UTILITIES NOT SUBMITTING FERC FORM NO. 2 (100 Series)		
General Information	101	N/A
Control Over Respondent	102	N/A
Corporations Controlled by Respondent	103	N/A
Officers	104	N/A
Directors	105	N/A
Security Holders and Voting Powers	106-107	N/A
Important Changes During the Year	108-109	N/A
Comparative Balance Sheet	110-113	N/A
Statement of Income for the Year	114-117	N/A
Statement of Retained Earnings for the Year	118-119	N/A
Statement of Cash Flows	120-121	N/A
Notes to Financial Statements	122-123	N/A
Statement of Accumulated Comprehensive Income and Hedging Activities	122a-b	N/A
BALANCE SHEET SUPPORTING SCHEDULES REQUIRED BY GAS UTILITIES NOT SUBMITTING FERC FORM NO. 2 (200 Series)		
Summary of Utility Plant and Accumulated Provisions for Depreciation, Amortization and Depletion	200-201	N/A
Gas Plant in Service	204-209	N/A
Manufactured Gas Production Plant - Supplemental Schedule	210	N/A
Gas Plant Leased to Others	213	N/A
Gas Plant Held for Future Use	214	N/A
Construction Work in Progress - Gas (Account 107)	216	N/A
Accumulated Provision for Depreciation of Gas Utility Plant (Account 108)	219	N/A
Gas Stored (Acct. 117, 164.1, 164.2 and 164.3)	220	N/A
Investments in Subsidiary Companies (Account 123.1)	224-225	N/A
Prepayments (Account 165)	230	N/A
Extraordinary Property Losses (Account 182.1)	230	N/A
Unrecovered Plant and Regulatory Study Costs (Account 182.2)	230	N/A
Other Regulatory Assets (Account 182.3)	232	N/A
Miscellaneous Deferred Debits (Account 186)	233	N/A
Accumulated Deferred Income Taxes (Account 190)	234-235	N/A
Capital Stock (Accounts 201 and 204)	250-251	N/A
Other Paid-in Capital	253	N/A
Reconciliation of Reported Net Income with Taxable Income for Federal Income Taxes	261	N/A
Taxes Accrued, Prepaid and Charged During Year	262-263	N/A
Distribution of Taxes Charged	262-263	N/A
Other Deferred Credits (Account 253)	269	N/A
Accumulated Deferred Income Taxes - Other Property (Account 282)	274-275	N/A
Accumulated Deferred Income Taxes - Other	276-277	N/A
Other Regulatory Liabilities (Account 254)	278	N/A
INCOME SUPPORTING SCHEDULES REQUIRED BY GAS UTILITIES NOT SUBMITTING FERC FORM NO. 2 (300 Series)		
Gas Operating Revenues (Account 400)	300-301	N/A
Residential & Commercial Space Heating Customers	305	N/A
Interruptible, Off Peak & Firm Sales to Distribution System Industrial Customers	305	N/A
Other Gas Revenues (Account 495)	308	N/A
Sales for Resale Natural Gas (Account 483)	310-311	N/A
Discounted Rate Services and Negotiated Rate Services	313	N/A
Gas Operation and Maintenance Expenses	320-325	N/A
Miscellaneous General Expenses (Account 930.2) (Gas)	335	N/A
Depreciation, Depletion & Amortization of Gas Plant (Accounts 403, 404.1, 404.2, 404.3, and 405)	336-338	N/A
Particulars Concerning Certain Income Deductions & Interest Charges Accounts	340	N/A
Regulatory Commission Expense	350-351	N/A
Employee Pensions and Benefits (Account 926)	352	N/A
Distribution of Salaries and Wages	354-355	N/A

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 246 of 580

FORM 21 ILCC LIST OF SCHEDULES		
Schedules	Page	Remarks
GAS PLANT STATISTICAL DATA REQUIRED BY GAS UTILITIES NOT SUBMITTING FERC FORM NO. 2 (500 Series)		
Auxiliary Peaking Facilities	519	N/A
ELECTRIC DATA REQUIRED BY ALL ELECTRIC UTILITIES (600 Series)		
Internal Combustion Engine & Gas - Turbine Generating Plants	600-601	N/A
Steam-Electric Generating Plants	602-603	N/A
Hydroelectric Generating Plants	604-605	N/A
Changes Made or Scheduled to be Made In Generating Plant Capacities	606	N/A
Electric Plant Acquisition Adjustments & Accumulated Provision for Amortization of Electric Plant Acquisition Adjustments (Accounts 114 and 115)	607	
Franchise Requirements (Account 927) (Electric)	608	
Territory Served (Electric)	609-610	
Construction Overheads - Electric	611	
Electric Distribution Meters and Line Transformers	612	
Environmental Protection Facilities	613	
Environmental Protection Expenses	614	
GAS DATA REQUIRED BY ALL GAS UTILITIES (700 Series)		
Mains in Illinois	700	N/A
Meters in Illinois	701	N/A
Services in Illinois	702	N/A
System Load Statistics in Illinois	703	N/A
Underground Gas Storage	704-705	N/A
Summary of Gas Account	706	N/A
Summary of Revenues, Terms & Customers by Gas Rates	707	N/A
Purchased Gas (Accounts 800, 801, 802, 803, 804, and 805)	708-709	N/A
Gas Plant Acquisition Adjustments & Accumulated Provision for Amortization of Gas Plant Acquisition Adjustments (Account 114, 115)	710	N/A
Franchise Requirements (Account 927) (Gas)	711	N/A
Territory Served (Gas)	712-713	N/A
Construction Overheads - Gas	714	N/A
Uncollectibles Accounts Expense	715	N/A
Enterprise Zone Revenues	716	N/A

UTILITY NAME Commonwealth Edison Company	Year of Report December 31, 2024
---	-------------------------------------

VERIFICATION
The responsible accounting officer shall verify this report under oath.

STATE OF Illinois

COUNTY OF Cook

Caroline Fulginiti makes oath and says that she is

Vice President and Assistant Controller

(Official Title of Affidavit)

Exelon Corporation

(Exact Legal Title or Name of Respondent)

that he/she has examined the following report; that to the best of his/her knowledge, information, and belief, all statements of fact contained in the said report are true, and the said report is a correct statement of the business and affairs of the above-named respondent in respect to each and every matter set forth therein during the period from and including January 1, 2024, to and including December 31, 2024.

Caroline Fulginiti

(Signature of Affiant)

Subscribed and sworn to before me, a Notary Public in and for the State and County named,

this 26 day of March, 2028

My Commission expires April 4, 2028

Barbara Haltom Stauffer

(Signature of Oath Administer)

OFFICIAL SEAL
BARBARA HALTOM STAUFFER
Notary Public, State of Illinois
Commission No. 989190
My Commission Expires April 04, 2028

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 248 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.) December 31, 2024	Year of Report December 31, 2024
BALANCE SHEET				
Instructions:				
Line No.	Title of Account (a)	Page Ref FERC Form 1 and/or 2 or ILCC Form 21 (b)	Balance at Beginning of Year (c)	Balance at End of Year (d)
1	UTILITY PLANT			
2	Utility Plant (101-106, and 114)	200-201	40,315,002,584	41,967,470,622
3	Construction Work in Progress (107)	200-201	1,395,544,738	1,220,404,574
4	TOTAL Utility Plant (Enter Total of lines 2 and 3)		41,710,547,322	43,187,875,196
5	(Less) Accum. Prov. For Depr. Amort. Depl. (108, 111, and 115)	200-201	11,713,087,084	12,206,668,082
6	Net Utility Plant (Enter Total of line 4 less 5)		29,997,450,238	30,981,207,104
7	Nuclear Fuel (120.1-120.4, and 120.6)	202-203	—	—
8	(Less) Accum. Prov. For Amort. Of Nuci. Assembl. (120.5)		—	—
9	Net Nuclear Fuel (Enter total of line 7 less line 8)		—	—
10	Net Utility Plant (Enter total of lines 6 and 9)		29,997,450,238	30,981,207,104
11	Utility Plant Adjustments (116)		—	—
12	Gas Stored Underground-Noncurrent (117)	220	—	—
13	OTHER PROPERTY AND INVESTMENTS			
14	Nonutility Property (121)	41	9,697,258	9,697,258
15	(Less) Accum. Prov. For Depr. And Amort. (122)	41	1,905,868	1,935,976
16	Investment in Associated Companies (123)	29-30	—	—
17	Investment in Subsidiary Companies (123.1)	224-225	102,288,128	106,206,800
18	(For Cost of account 123.1, see footnote FERC Form 1 page 224, line 42)		—	—
19	Noncurrent Portion of Allowances		—	—
20	Other Investments (124)	29-30	37,334	43,427
21	Special Funds (125-128)	16	—	—
22	TOTAL Other Property and Investments (Total of lines 14-17 and 19-21)		110,116,852	114,011,509
23	CURRENT AND ACCRUED ASSETS			
24	Cash (131)		45,643,539	17,224,016
25	Special Deposits (132-134)	16	401,566,878	485,877,839
26	Working Funds (135)		—	—
27	Temporary Cash Investments (136)	29-30	23,989,634	39,423,613
28	Notes Receivable (141)	17	—	—
29	Customer Accounts Receivable (142)		508,571,219	659,142,561
30	Other Accounts Receivable (143)	17	242,277,627	281,592,347
31	(Less) Accum. Prov. For Uncollectibles Acct. - Credit (144)		86,250,851	143,245,638
32	Notes Receivable from Associated Companies (145)	18	—	—
33	Accounts Receivable from Assoc. Companies (146)	18	70,491	528,228
34	Fuel Stock (151)	20	—	—
35	Fuel Stock Expense Undistributed (152)	20	—	—
36	Residuals (Elec.) and Extracted Products (153)	20	—	—
37	Plant Materials and Operating Supplies (154)	20	285,561,287	297,689,734
38	Merchandise (155)	20	—	—
39	Other Materials and Supplies (156)	20	—	—
40	Nuclear Materials Held for Sale (157)	202-203/227	—	—
41	Allowances (158.1 and 158.2)	228-229	—	—
42	(Less) Noncurrent Portion of Allowances		—	—
43	Stores Expenses Undistributed (163)	20	—	—
44	Gas Stored Underground - Current (164.1)		—	—
45	Liquefied Natural Gas Stored and Held for Processing (164.2 - 164.3)		—	—
46	Prepayments (165)		102,590,569	115,572,656
47	Advances for Gas (166-167)		—	—
48	Interest and Dividends Receivable (171)		10,540	12,699
49	Rents Receivable (172)		—	—
50	Accrued Utility Revenue (173)		351,134,876	334,534,395
51	Miscellaneous Current and Accrued Assets (174)	19	4,318,888	4,020,994

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 249 of 580

Name of Respondent Commonwealth Edison Company	This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.)	Year of Report December 31, 2024		
Instructions: Include in columns (e) through (i), total company balances of Utility Plant in Service and associated balances corresponding to the line number on page (2), lines 1 through 12. Include in column (g), Total Company Common Utility, balances that cannot be directly assigned to a specific service in columns (e), (f) or (h). Columns (e) thru (i) must total column (d) on page 2. For amounts in columns (e) thru (i), show corresponding Illinois jurisdictional amounts in columns (j) thru (n).					
BALANCE SHEET					
Total Company Direct Electric Utility (e)	Total Company Direct Gas Utility (f)	Total Company Common Utility (g)	Total Company Competitive Utility (h)	Total Company Other Utility (i)	Line No.
					1
41,967,470,622					2
1,220,404,574					3
43,187,875,196					4
12,206,668,092					5
30,981,207,104					6
---					7
---					8
---					9
30,981,207,104					10
---					11
---					12
					13

Illinois Direct Electric Utility (j)	Illinois Direct Gas Utility (k)	Total Company Common Utility (l)	Total Company Competitive Utility (m)	Total Company Other Utility (n)	Line No.
					1
41,967,470,622					2
1,220,404,574					3
43,187,875,196					4
12,206,668,092					5
30,981,207,104					6
---					7
---					8
---					9
30,981,207,104					10
---					11
---					12
					13

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 250 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.) December 31, 2024	Year of Report December 31, 2024
BALANCE SHEET Cont'd				
Instructions:				
Line No.	Title of Account (a)	Page Ref FERC Form 1 and/or 2 or ILCC Form 21 (b)	Balance at Beginning of Year (c)	Balance at End of Year (d)
52	Derivative Instrument Assets (175)		—	—
53	Derivative Instrument Assets - Hedges (176)		—	—
54	TOTAL Current and Accrued Assets (Enter total of lines 24 thru 53)		1,879,484,697	2,092,373,444
55	DEFERRED DEBITS			
56	Unamortized Debt Expense (181)		99,782,409	103,067,099
57	Extraordinary Property Losses (182.1)	230	—	—
58	Unrecovered Plant and Regulatory Study Costs (182.2)	230	—	—
59	Other Regulatory Assets (182.3)	232	4,396,564,225	3,996,746,550
60	Prelim. Survey and Investigation Charges (Electric) (183)		—	—
61	Prelim. Survey and Investigation Charges (Gas) (183.1, 183.2)		—	—
62	Clearing Accounts (184)		325	(56)
63	Temporary Facilities (185)		—	—
64	Miscellaneous Deferred Debits (186)	233	4,997,467,960	5,977,542,374
65	Def. Losses from Disposition of Utility Plant (187)		—	—
66	Research, Devel and Demonstration Expenditures (188)	352-353	—	—
67	Unamortized Loss on Reacquired Debt (189)	24	16,424,002	14,839,627
68	Accumulated Deferred Income Taxes (190)	234-235	1,006,863,343	871,112,133
69	Unrecovered Purchased Gas Costs (191)		—	—
70	TOTAL Deferred Debits (Enter total of lines 56 thru 69)		10,517,102,264	10,963,307,727
71	TOTAL Assets and Other Debits (Enter total of lines 10,11,12,22,54,70)		42,504,154,051	44,150,899,784

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 251 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.):	Year of Report December 31, 2024
BALANCE SHEET				
Instructions:				
Line No.	Title of Account (a)	Page Ref FERC Form 1 and/or 2 or ILCC Form Z1 (b)	Balance at Beginning of Year (c)	Balance at End of Year (d)
1	PROPRIETARY CAPITAL			
2	Common Stock Issued (201)	250-251	1,587,297,032	1,587,297,245
3	Preferred Stock Issued (204)	250-251	—	—
4	Capital Stock Subscribed (202,205)	45	—	—
5	Stock Liability for Conversion (203,206)	45	—	—
6	Premium on Capital Stock (207)	45	5,020,104,944	5,020,105,353
7	Other Paid in Capital (208-211)	253	5,388,756,067	5,615,312,040
8	Installments Received on Capital Stock (212)	45	—	—
9	(Less) Discount on Capital Stock (213)	46	—	—
10	(Less) Capital Stock Expense (214)	46	6,942,925	6,942,925
11	Retained Earnings (215, 215.1, and 216)	6	2,327,289,291	2,608,976,284
12	Unappropriated Undistributed Subsidiary Earnings (216.1)	6	51,743,312	60,499,848
13	(Less) Reacquired Capital Stock (217)	250-251	—	—
14	Accumulated Other Comprehensive Income (219)	122(a)(b)	—	—
15	TOTAL Proprietary Capital (Enter total of lines 2 thru 14)		14,368,247,721	14,885,247,845
16	LONG-TERM DEBT			
17	Bonds (221)	22-23	11,603,600,000	12,153,600,000
18	(Less) Reacquired Bonds (222)	22-23	—	—
19	Advances from Associated Companies (223)	22-23	206,186,000	206,186,000
20	Other Long-Term Debt (224)	22-23	—	—
21	Unamortized Premium on Long-Term Debt (225)		—	—
22	(Less) Unamortized Discount on Long-Term Debt-Debit (226)		28,371,972	30,683,580
23	TOTAL Long-Term Debt (Enter total of lines 17 thru 22)		11,781,414,028	12,329,102,420
24	OTHER NONCURRENT LIABILITIES			
25	Obligations Under Capital Leases-Noncurrent (227)		7,532,029	7,475,353
26	Accumulated Provision for Property Insurance (228.1)		—	—
27	Accumulated Provision for Injuries and Damages (228.2)		81,424,515	120,642,632
28	Accumulated Provision for Pensions and Benefits (228.3)		197,131,365	191,071,720
29	Accumulated Miscellaneous Operating Provisions (228.4)		302,552,734	284,584,833
30	Accumulated Provision for Rate Refunds (229)		7,188,191	8,484,459
31	Asset Retirement Obligations (230)		151,156,355	169,137,189
32	TOTAL Other Noncurrent Liabilities (Enter total of lines 25 thru 31)		746,985,189	781,396,186
33	CURRENT AND ACCRUED LIABILITIES			
34	Notes Payable (231)	21	601,937,997	35,995,450
35	Accounts Payable (232)		828,813,132	713,392,804
36	Notes Payable to Associated Companies (233)	21	—	—
37	Accounts Payable to Associated Companies (234)	21	72,879,463	77,043,053
38	Customer Deposits (235)		118,238,326	134,362,405
39	Taxes Accrued (236)	262-263	211,291,922	95,223,579
40	Interest Accrued (237)		149,033,092	151,720,942
41	Dividends Declared (238)		—	—
42	Matured Long-Term Debt (239)		—	—
43	Matured Interest (240)		—	—
44	Tax Collections Payable (241)		31,397,970	28,435,908
45	Miscellaneous Current and Accrued Liabilities (242)		440,174,247	504,717,529
46	Obligations Under Capital Leases-Current (243)		70,210	76,276

Form Z1 ILCC

page 4

2024DCAI 0000121

Name of Respondent		This Report Is:	Date of Report (Mo./Da./Yr.):	Year of Report
Commonwealth Edison Company		(1) An Original		December 31, 2024
BALANCE SHEET Cont'd				
Instructions:				
Line No.	Title of Account (a)	Page Ref FERC Form 1 and/or 2 or ILCC Form 21 (b)	Balance at Beginning of Year (c)	Balance at End of Year (d)
47	Derivative Instrument Liabilities (244)		—	—
48	Derivative Instrument Liabilities - Hedging (245)		—	—
49	TOTAL Current and Accrued Liabilities (Enter Total of Lines 34 thru 48)		2,453,836,359	1,740,967,946
50	DEFERRED CREDITS			
51	Customer Advances for Construction (252)		455,558,952	781,908,871
52	Accumulated Deferred Investment Tax Credits (255)	266-267	6,810,301	6,278,126
53	Deferred Gains from Disposition of Utility Plant (256)			
54	Other Deferred Credits (253)	269	120,260,137	116,180,770
55	Other Regulatory Liabilities (254)	278	6,253,543,172	7,052,743,824
56	Unamortized Gain on Reacquired Debt (257)	24	—	—
57	Accumulated Deferred Income Taxes (281-283)	272-277	6,317,498,192	6,457,073,796
58	TOTAL Deferred Credits (Enter total lines 51 thru 57)		13,153,670,754	14,414,185,387
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69	TOTAL Liab. And Other Credits (Enter total of lines 15,23,32,49 & 58)		42,504,154,051	44,150,899,784

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 253 of 580

Name of Respondent Commonwealth Edison Company	This Report Is:	Date of Report (Mo./Da./Yr.)	Year of Report December 31, 2024
STATEMENT OF RETAINED EARNINGS			
Instructions:			
1. Report all changes in appropriated retained earnings, unappropriated retained earnings, and unappropriated, undistributed subsidiary earnings for the year.			
2. Each credit and debit during the year should be identified as to the retained earnings account in which recorded. Show the contra primary account affected in column (b).			
3. State the purpose and amount of each reservation or appropriation of retained earnings.			
4. List first account 439 Adjustments to Retained Earnings, reflecting adjustments to the opening balance of retained earnings. Follow by credit, then debit items in that order.			
5. Show dividends for each class and series of capital stock.			
6. Show separately the State and Federal income tax effect of items in account 439, Adjustments to Retained Earnings.			
7. Explain in a footnote the balance for determining the amount reserved or appropriated. If such reservation or appropriation is to be recurrent, state the number and annual amounts to be reserved or appropriated as well as the totals eventually to be accumulated.			
8. If any notes appearing in the report to stockholders are applicable to this statement, include them on pages 122-123.			
Line No.	Item (a)	Contra primary Account Affected (b)	Amount (c)
UNAPPROPRIATED RETAINED EARNINGS (216)			
1	Balance-Beginning of Year		(1,689,302,284)
2	Changes		
3	Adjustments to Retained Earnings (439)		
4	Comprehensive Income		
5			
6			
7			
8			
9	Total Credits to Retained Earnings (439)		—
10	Adjustment of the Adoption of FASB Interpretation No. (FIN) 48		
11			
12			
13			
14			
15	Total Debits to Retained Earnings (439)		—
16	Balance Transferred from Income (Account 433 less Account 418.1)		1,056,937,750
17	Appropriations to Retained Earnings (436)		—
18	Transfer to appropriated retained earnings for payment of future dividends	215	1,066,087,097
19			
20			
21			
22	Total Appropriations of Retained Earnings (436)		1,066,087,097
23	Dividends Declared-Preferred Stock (437)		
24			
25			
26			
27			
28			
29	Total Dividends Declared-Preferred Stock (437)		—
30	Dividends Declared-Common Stock (438)		
31			
32			
33			
34			
35			
36	Total Dividends Declared-Common Stock (438)		—
37	Transfers from Account 216.1, Unappropriated, Undistributed, Subsidiary Earnings	216	392,811
38	Balance-End of Year (Total lines 1,9,15,16,22,29,36,37)		(1,698,058,820)

Name of Respondent Commonwealth Edison Company	This Report Is: 1/2/2025	Date of Report (Mo./Da./Yr.): December 31, 2024	Year of Report December 31, 2024
STATEMENT OF RETAINED EARNINGS, cont'd			
Instructions: 1. Report all changes in appropriated retained earnings, unappropriated retained earnings, and unappropriated, undistributed subsidiary earnings for the year. Each credit and debit during the year should be identified as to the retained earnings account in which recorded. Show the contra primary account affected in column (b). State the purpose and amount of each reservation or appropriation of retained earnings. List first account 439 Adjustments to Retained Earnings, reflecting adjustments to the opening balance of retained earnings. Follow by credit, then debit items in that order. Show dividends for each class and series of capital stock. Show separately the State and Federal income tax effect of items in account 439, Adjustments to Retained Earnings. 7. Explain in a footnote the balance for determining the amount reserved or appropriated. If such reservation or appropriation is to be recurrent, state the number and annual amounts to be reserved or appropriated as well as the totals eventually to be			
Line No.	Item (a)	Contra primary Account Affected (b)	Amount (c)
	APPROPRIATED RETAINED EARNINGS (215)		
39	Balance - Beginning of Year (Debit or Credit)		4,016,591,575
40	Appropriations of retained earnings for future dividend payments	216	1,066,087,097
41	Dividends Declared	238	(775,643,568)
42	Tax Adjustment for FIN48		
43			
44			
45	TOTAL Appropriated Retained Earnings (215)		4,307,035,104
46	TOTAL Appropriated Retained Earnings-Amort. Reserve, Federal (215.1)		---
47	TOTAL Appropriated Retained Earnings (215, 215.1) (Enter total lines 45 and 46)		4,307,035,104
48	TOTAL Retained Earnings (215, 215.1, 216) (Enter total lines 38 and 47)		2,608,976,284
	UNAPPROPRIATED UNDISTRIBUTED SUBSIDIARY EARNINGS (216.1)		
49	Balance-Beginning of Year (Debit or Credit)		51,743,312
50	Equity in Earnings for Year (Credit) (418.1)		9,149,347
51	(Less) Dividends Received (Debit)	216	392,811
52	Tax Sharing Benefit to Subsidiary		
53	Balance - End of Year (Total lines 49 thru 52)		60,499,848

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 255 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.)	Year of Report December 31, 2024
STATEMENT OF INCOME FOR THE YEAR				
Instructions: 1. Report the amounts derived from total company operations for the current year and the previous year on this page.				
Line No.	Account (a)	FERC Form 1 and 2 (Ref) Page No. (b)	Total Company Current Year (c)	Total Company Previous Year (d)
1	UTILITY OPERATING INCOME			
2	Operating Revenues (400)	300-301	8,163,984,950	7,847,450,785
3	Operating Expenses			
4	Operation Expenses (401)	320-323	4,234,423,204	3,832,950,659
5	Maintenance Expenses (402)	320-323	492,900,321	459,380,558
6	Depreciation Expense (403)	336-337	1,052,277,392	1,006,052,806
7	Depreciation Expense for Asset Retirement Costs (403.1)	336-337	1,830,160	1,858,923
8	Amortization & Depletion Of Utility Plant (404-405)	336-337	129,435,286	100,660,161
9	Amortization Of Utility Plant Acquisition Adjustment (406)	336-337	—	—
10	Amort. Of Property Losses, Unrecovered Plant and Regulatory Study Costs (407.1)		—	—
11	Amort. Of Conversion Expense (407.2)		—	—
12	Regulatory Debits (407.3)		346,966,972	305,964,625
13	Regulatory Credits (407.4)		118,650,816	62,177,236
14	Taxes Other Than Income Taxes (408.1)	262-263	372,144,480	367,534,329
15	Income Taxes - Federal (409.1)	262-263	70,955,520	129,557,732
16	Income Taxes - Other (409.1)	262-263	61,713,309	(11,432,424)
17	Provision for Deferred Income Taxes (410.1)	234,272-277	463,852,957	592,520,153
18	(Less) Provision for Deferred Income Taxes-Cr. (411.1)	243,272-277	488,297,479	399,639,434
19	Investment Tax Credit Adj.-Net (411.4)		(993,294)	(1,218,203)
20	(Less) Gains from Disp. Of Utility Plant (411.6)		—	—
21	Losses from Disp. Of Utility Plant (411.7)		—	—
22	(Less) Gains from Disposition of Allowances (411.8)		—	—
23	Losses from Disposition of Allowances (411.9)		—	—
24	Accretion Expense (411.10)		30,043	51,297
25	Total Utility Operating Expenses (Total lines 4 through 24)		6,618,588,055	6,322,063,946
26	Net Utility Operating Income (Enter total of line 2 less line 25. Carry forward to page 7b, line 27)		1,545,396,895	1,525,386,839

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 256 of 580

Name of Respondent		This Report Is:		Date of Report (Mo./Da./Yr.)		Year of Report	
Commonwealth Edison Company		(1) An Original				December 31, 2024	
Instructions: For balances that cannot be allocated to a specific jurisdiction or service, reflect "*****" in the cell (box) and provide the total gas or electric company balance in the Total gas or electric Company column.							
STATEMENT OF INCOME FOR THE YEAR							
Illinois Electric Utility (e)	Total Company Electric Utility (f)	Illinois Gas Utility (g)	Total Company Gas Utility (h)	Other Utility (i)	Line No.		
					1		
8,163,984,950	8,163,984,950				2		
					3		
4,234,423,204	4,234,423,204				4		
492,900,321	492,900,321				5		
1,052,277,392	1,052,277,392				6		
1,830,160	1,830,160				7		
129,435,286	129,435,286				8		
—	—				9		
—	—				10		
—	—				11		
346,966,972	346,966,972				12		
118,650,816	118,650,816				13		
372,144,480	372,144,480				14		
70,955,520	70,955,520				15		
61,713,309	61,713,309				16		
463,852,957	463,852,957				17		
488,297,479	488,297,479				18		
(993,294)	(993,294)				19		
—	—				20		
—	—				21		
—	—				22		
—	—				23		
30,043	30,043				24		
6,618,588,055	6,618,588,055				25		
1,545,396,895	1,545,396,895				26		

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 257 of 580

Name of Respondent		This Report Is:	Date of Report (Mo./Da./Yr.)	Year of Report	
Commonwealth Edison Company		(1) An Original		December 31, 2024	
STATEMENT OF INCOME FOR THE YEAR					
Instructions: Report the amounts derived from total company operations for the current year and the previous year on this page. Explain in a footnote if the previous year's amounts are different from that reported in prior years.					
Line No.	Account (a)	FERC Form 1 and 2 (Ref) Page No. (b)	Total Company Current Year (c)	Total Company Previous Year (d)	
27	Net Utility Operating Income (page 7, line 26)		1,545,396,895	1,525,386,839	
28	OTHER INCOME AND DEDUCTIONS				
29	Other Income				
30	Non-utility Operating Income				
31	Revenues from Merchandising, Jobbing and Contract Work (415)		77,031,423	22,794,716	
32	(Less) Costs and Exp. Of Merchandising, Job & Contract Work (416)		77,606,927	22,319,615	
33	Revenues from Non-Utility Operations (417)		—	—	
34	(Less) Expenses of Non-Utility Operations (417.1)		—	—	
35	Nonoperating Rental Income (418)		—	—	
36	Equity in Earnings of Subsidiary Companies (418.1)		9,149,347	5,517,419	
37	Interest and Dividend Income (419)		23,310,870	22,029,291	
38	Allowance for Other Funds Used During Construction (419.1)		46,146,117	33,462,076	
39	Miscellaneous Nonoperating Income (421)		23,253,461	17,817,710	
40	Gain on Disposition of Property (421.1)		0	—	
41	Total Other Income (Enter total of lines 31 through line 40)		101,284,291	79,301,597	
42	Other Income Deductions				
43	Loss on Disposition of Property (421.2)		—	—	
44	Miscellaneous Amortization (425)	340	—	—	
45	Miscellaneous Income Deductions (426.1-426.5)	340	71,768,269	28,880,313	
46	Total Other Income Deductions (Total of lines 43 through 45)		71,768,269	28,880,313	
47	TAXES APPLICABLE TO OTHER INCOME AND DEDUCTIONS				
48	Taxes Other than Income Taxes (408.2)	262-263	2,503,180	956,149	
49	Income Taxes-Federal (409.2)	262-263	2,979,344	6,753,836	
50	Income Taxes-Other (409.2)	262-263	(2,385,084)	1,295,297	
51	Provision for Deferred Income Taxes (410.2)	234,272-277	5,403,183	—	
52	(Less) Provision for Deferred Income Taxes-Cr. (411.2)	234,272-277	—	4,162,560	
53	Investment Tax Credit Adj. (411.5)		—	—	
54	(Less) Investment Tax Credits (420)		—	—	
55	Total Taxes on Other Income and Deduct. (Total of line 48 through 54)		8,500,623	4,842,722	
56	Net Other Income and Deductions (Enter Total lines 41, 46, 55)		21,015,399	45,578,562	
57	INTEREST CHARGES				
58	Interest on Long-Term Debt (427)		483,054,341	457,291,632	
59	Amort. Of Debt Disc. And Expense (428)		7,724,318	7,063,111	
60	Amortization of Loss on Reacquired Debt (428.1)		1,584,375	1,584,375	
61	(Less) Amort. Of Premium on Debt-Credit (429)		—	—	
62	(Less) Amort. Of Gain on Reacquired Debt-Credit (429.1)		—	—	
63	Interest on Debt to Assoc. Companies (430)	340	13,092,811	13,092,811	
64	Other Interest Expense (431)	340	23,810,563	36,332,711	
65	(Less) Allowance for Borrowed Funds Used During Construction - Cr. (432)		28,941,211	38,477,582	
66	Net Interest Charges (Enter total of lines 58 through 65)		500,325,197	476,887,058	
67	Income Before Extraordinary Items		1,066,087,097	1,094,078,343	
68	EXTRAORDINARY ITEMS				
69	Extraordinary Income (434)		—	—	
70	(Less) Extraordinary Deductions (435)		—	—	
71	Net Extraordinary Items (Enter total of line 69 less line 70)		—	—	
72	Income Taxes-Federal and Other (409.3)	262-263	—	—	
73	Extraordinary Items After Taxes (Enter total of line 71 less line 72)		—	—	
74	Net Income (Enter total of lines 67 and 73)		1,066,087,097	1,094,078,343	

Form 21 ILCC

page 7b

2024DCAI 0000127

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 258 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) As Original		Date of Report (Mo./Da./Yr.): December 31, 2024		
ILLINOIS ELECTRIC NET OPERATING REVENUES						
1. Report the amounts derived from providing utility services in Illinois. Only revenues resulting from tariffed services are to be reported on lines 1 through 8.						
2. In columns (b) and (c), Supply-Fixed Price Service and Supply-Hourly Priced Service, the revenues reported shall include all supply charges. Revenues from supply charges shall include revenues for the cost of energy, transmission charges, and any ancillary services.						
3. In column (d), Delivery Charges-Full Service Customers, the revenues reported shall include the delivery service charges for full service customers. Full service customers are those customers receiving either Fixed Price Service or Hourly Priced Service from the utility.						
4. In column (e), Delivery Charges-Delivery of RES Power, report delivery service charge revenues for the power that is delivered to customers and that is purchased from Retail Electric Suppliers.						
5. If the actual amounts are not available, an estimate should be reported. If an estimate is reported, the fact should be footnoted and the supporting documents that show the derivation of the estimate should be sent to the Director of the Financial Analysis Division and the Director of the Energy Division of the Illinois Commerce Commission.						
6. If the utility has used Account 456 to record revenues from the tariffed transmission of the utility's own electricity rather than limiting transmission revenues in Account 456 to only revenues from transmission of electricity of others over transmission facilities of the utility, report those revenues in the appropriate column on line 20.						
Report supply charge revenues from the Power Purchase Option in Supply-Fixed Price Service or Supply-Hourly Priced Service, as appropriate, and in a footnote to this page.						
If the utility has offered bundled service, report fixed price bundled service in column (b) and time of day and/or hourly priced bundled service in column (c). Additionally, note the reporting of bundled service amounts in a footnote.						
All of the revenue effects (customer credits and generator reimbursements) of the 2007 Settlement Agreement shall be shown on lines 2 and 4 in the appropriate columns.						
Illinois Electric Operating Revenue for the Reporting Year						
Line No.	Title of Account (a)	Supply-Fixed Price Service (b)	Supply-Hourly Priced Service (c)	Delivery Charges-Full Service Customers (d)	Delivery Charges-Delivery of RES Power (e)	Total (f)
1	ELECTRIC SERVICE REVENUES					
2	(440) Residential Sales	1,284,725,487	21,751,979	1,861,596,979	566,658,668	3,734,733,091
3	(442) Commercial and Industrial Sales					
4	Small or Commercial	304,279,091	138,210,105	567,982,319	1,206,778,122	2,217,249,637
5	Large or Industrial	603,005	59,824,668	63,558,872	983,273,414	1,107,156,099
6	(444) Public Street and Highway Lighting	1,592,851	2,414,368	18,705,844	23,022,741	43,735,834
7	(445) Other Sales to Public Authorities	---	---	---	---	---
8	(446) Sales to Railroads and Railways	(160)	15,216	(23,313)	14,508,358	14,504,101
9	SALES TO ULTIMATE CUSTOMERS (Sum of Lines 2 through 8)	1,591,100,254	222,220,308	2,509,820,501	2,794,241,301	7,117,382,362
10	(447) Sales for Resale	---	---	---	---	20,927,738
11	(448) Interdepartmental Sales	---	---	---	---	---
12	TOTAL SALES OF ELECTRICITY (Sum of Lines 9 through 11)	1,591,100,254	222,220,308	2,509,820,501	2,794,241,301	7,138,310,098
13	Lines (449-1) Provision for Rate Refunds	---	---	---	---	---
14	TOTAL SALES OF ELECTRICITY NET OF PROVISION FOR RATE	1,591,100,254	222,220,308	2,509,820,501	2,794,241,301	7,138,310,098
15	(450) Forfeited Discounts					14,347,873
16	(451) Miscellaneous Service Revenues					19,000,238
17	(453) Sales of Water and Water Power					0
18	(454) Rent from Electric Property					95,390,314
19	(455) Interdepartmental Rent					0
20	(456) Other Electric Revenues					896,936,369
21	TOTAL OTHER OPERATING REVENUES (Sum of Line 15 thru Line 20)	---	---	---	---	1,025,674,852
22	TOTAL ELECTRIC OPERATING REVENUES (Line 14 + Line 21)	1,591,100,254	222,220,308	2,509,820,501	2,794,241,301	8,163,984,950
23	Unbilled Revenues Included in Line 12	(11,965,424)	811,448	(176,969,056)	(263,814,478)	(451,537,510)
Page 8, Line No. 23, Column (f) - The change in unbilled revenues reported for 2024 was \$830,887,854 lower than the change in unbilled revenues reported for 2023.						

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 259 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original		Date of Report (Mo./Da./Yr.) December 31, 2024	Year of Report December 31, 2024	
ILLINOIS ELECTRIC NET OPERATING REVENUES FOR THE PRIOR YEAR						
1. Report the amounts derived from providing utility services in Illinois. Only revenues resulting from tariffed services are to be reported on lines 1 through 8.						
2. In columns (b) and (c), Supply-Fixed Price Service and Supply-Hourly Priced Service, the revenues reported shall include all supply charges. Revenues from supply charges shall include revenues for the cost of energy, transmission charges, and any ancillary services.						
3. In column (d), Delivery Charges-Full Service Customers, the revenues reported shall include the delivery service charges for full service customers. Full service customers are those customers receiving either Fixed Price Service or Hourly Priced Service from the utility.						
4. In column (e), Delivery Charges-Delivery of RES Power, report delivery service charge revenues for the power that is delivered to customers and that is purchased from Retail Electric Suppliers.						
5. If the actual amounts are not available, an estimate should be reported. If an estimate is reported, the fact should be footnoted and the supporting documents that show the derivation of the estimate should be sent to the Director of the Financial Analysis Division and the Director of the Energy Division of the Illinois Commerce Commission.						
6. If the utility has used Account 456 to record revenues from the tariffed transmission of the utility's own electricity rather than limiting transmission revenues in Account 456 to only revenues from transmission of electricity of others over transmission facilities of the utility, report those revenues in the appropriate column on line 20.						
7. Report supply charge revenues from the Power Purchase Option in Supply-Fixed Price Service or Supply-Hourly Priced Service, as appropriate, and in a footnote to this page.						
8. If the utility has offered bundled service, report fixed price bundled service in column (b) and time of day and/or hourly priced bundled service in column (c). Additionally, note the reporting of bundled service amounts in a footnote.						
9. All of the revenue effects (customer credits and generator reimbursements) of the 2007 Settlement Agreement shall be shown on lines 2 and 4 in the appropriate columns.						
Illinois Electric Operating Revenues for the Prior Year						
Line No.	Title of Account (a)	Supply--Fixed Price Service (b)	Supply--Hourly Priced Service (c)	Delivery Charges--Full Service Customers (d)	Delivery Charges--Delivery of RES Power (e)	Total (f)
1.	ELECTRIC SERVICE REVENUES	1,555,420,272	19,155,191	1,821,102,107	486,598,191	3,862,275,761
2.	(440) Residential Sales	---	---	---	---	---
3.	(442) Commercial and Industrial Sales	---	---	---	---	---
4.	Small or Commercial	371,084,294	143,040,145	492,342,845	1,020,121,692	2,027,188,286
5.	Large or Industrial	139,938	32,908,393	43,954,377	799,056,338	866,068,048
6.	(444) Public Street and Highway Lighting	2,267,494	2,893,670	17,724,592	22,462,997	45,348,663
7.	(445) Other Sales to Public Authorities	---	---	---	---	---
8.	(446) Sales to Railroads and Railways	---	---	22,774	12,219,207	12,241,981
9.	SALES TO ULTIMATE CUSTOMERS (Sum of Lines 2 through 8)	1,928,921,708	218,997,299	2,375,146,795	2,320,497,425	6,843,163,227
10.	(447) Sales for Resale	---	---	---	---	27,394,638
11.	(448) Interdepartmental Sales	---	---	---	---	---
12.	TOTAL SALES OF ELECTRICITY (Sum of Lines 9 through 11)	1,928,921,708	218,997,299	2,375,146,795	2,320,497,425	6,870,558,065
13.	Less: (449.1) Provision for Rate Refunds	---	---	---	---	---
14.	TOTAL SALES OF ELECTRICITY NET OF PROVISION FOR RATE REFUND	1,928,921,708	218,997,299	2,375,146,795	2,320,497,425	6,870,558,065
15.	(450) Forfeited Discounts	---	---	---	---	28,067,219
16.	(451) Miscellaneous Service Revenues	---	---	---	---	19,161,315
17.	(453) Sales of Water and Water Power	---	---	---	---	---
18.	(454) Rent from Electric Property	---	---	---	---	87,133,133
19.	(455) Interdepartmental Rent	---	---	---	---	---
20.	(456) Other Electric Revenues	---	---	---	---	842,531,053
21.	TOTAL OTHER OPERATING REVENUES (Sum of Line 15 thru Line 20)	---	---	---	---	978,892,720
22.	TOTAL ELECTRIC OPERATING REVENUES (Line 14 + Line 21)	1,928,921,708	218,997,299	2,375,146,795	2,320,497,425	7,847,450,785
23.	Unbilled Revenues Included in Line 12	(42,904,954)	(5,830,703)	251,949,821	178,236,280	379,450,444

Page 8 of 23, Column (f) - The change in unbilled revenues reported for 2023 was \$450,752,515 higher than the change in unbilled revenues reported for 2022.

Form 21 I.L.C.C. page 8a

Page 8, Line No. 23, Column (f) - The change in unbilled revenues reported for 2023 was \$450,752,515 higher than the change in unbilled revenues reported for 2022.

Form 21 ILCC

page 8a

2024DCAI 0000129

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 260 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original		Date of Report (Mo./Da./Yr.): December 31, 2024		Year of Report
ILLINOIS MEGAWATT HOURS SOLD OR DELIVERED AND AVERAGE NUMBER OF ILLINOIS ELECTRIC CUSTOMERS PER MONTH						
1. Report the megawatt hours sold or delivered from providing utility services in Illinois and the average number of electric customers per month. Information reported should correspond to information reported on page 8, Illinois Electric Operating Revenues for the reporting year.						
2. If the actual amounts are not available, an estimate should be reported. If an estimate is reported, the fact should be footnoted and the supporting documents that show the derivation of the estimate should be sent to the Director of the Financial Analysis Division and the Director of the Energy Division of the Illinois Commerce Commission.						
3. Report supply charge megawatt hours and average number of customers from the Power Purchase Option in Supply-Fixed Price Service or Supply-Hourly Priced Service, as appropriate, and in a footnote to this page.						
Megawatt Hours Sold or Delivered for the Reporting Year						
Line No.	Title of Account (a)	Supply-- Fixed Price Service (b)	Supply-- Hourly Priced Service (c)	No Entry Required (d)	Delivery Charges-- Delivery of RES Power (e)	Total (f)
1	ELECTRIC SERVICE REVENUES					
2	(440) Residential Sales	19,996,514	450,261		6,827,049	27,273,824
3	(442) Commercial and Industrial Sales	4,682,206	3,266,668		20,417,706	28,366,580
4	Small or Commercial	9,251	1,599,439		26,260,940	27,869,630
5	Large or Industrial	40,931	71,649		332,249	444,829
6	(444) Public Street and Highway Lighting	—	—		—	—
7	(445) Other Sales to Public Authorities	—	—		—	—
8	(446) Sales to Railroads and Railways	—	—		376,332	376,332
9	SALES TO ULTIMATE CUSTOMERS (Sum of Lines 2 through 8)	24,728,902	5,388,017		54,214,276	84,331,195
10	(447) Sales for Resale	—	—		—	791,465
11	(448) Interdepartmental Sales	—	—		—	—
12	TOTAL SALES OF ELECTRICITY (Sum of Lines 9 through 11)	24,728,902	5,388,017		54,214,276	85,122,660
Average Number of Customers per Month for the Reporting Year						
Line No.	Title of Account (a)	Supply-- Fixed Price Service (b)	Supply-- Hourly Priced Service (c)	No Entry Required (d)	Delivery Charges-- Delivery of RES Power (e)	Total (f)
13	ELECTRIC SERVICE REVENUES					
14	(440) Residential Sales	2,877,589	44,635		805,452	3,727,676
15	(442) Commercial and Industrial Sales	220,863	8,530		166,122	395,515
16	Small or Commercial	220,863	8,530		166,122	395,515
17	Large or Industrial	26	164		1,661	2,051
18	(444) Public Street and Highway Lighting	3,193	940		1,573	5,706
19	(445) Other Sales to Public Authorities	—	—		—	—
20	(446) Sales to Railroads and Railways	—	—		—	—
21	SALES TO ULTIMATE CUSTOMERS (Sum of Lines 12 through 20)	3,101,471	54,269		975,010	4,130,750
22	(447) Sales for Resale	—	—		—	—
23	(448) Interdepartmental Sales	—	—		—	—
24	TOTAL SALES OF ELECTRICITY (Sum of Lines 21 through 23)	3,101,471	54,269		975,010	4,130,750

Form 21 R/C

page 9

2024CAI 0000130

Appendix C - Stakeholder Presentation

Rate Design Investigation

Page 261 of 580

Name of Respondent Commonwealth Edison Company		This Report is: (1) An Original		Date of Report (Mo./Da./Yr.) December 31, 2024		
ILLINOIS MEGAWATT HOURS SOLD OR DELIVERED AND AVERAGE NUMBER OF ILLINOIS ELECTRIC CUSTOMERS PER MONTH						
1. Report the megawatt hours sold or delivered from providing utility services in Illinois and the average number of electric customers per month. Information reported should correspond to information reported on page 8, Illinois Electric Operating Revenues for the reporting year.						
2. If the actual amounts are not available, an estimate should be reported. If an estimate is reported, the fact should be footnoted and the supporting documents that show the derivation of the estimate should be sent to the Director of the Financial Analysis Division and the Director of the Energy Division of the Illinois Commerce Commission.						
3. Report supply charge megawatt hours and average number of customers from the Power Purchase Option in Supply-Fixed Price Service or Supply-Hourly Priced Service, as appropriate, and in a footnote to this page.						
4. If the utility has offered bundled service, report fixed price bundled service in column (b) and time of day and/or hourly priced bundled service in column (c). Additionally, note the reporting of bundled service amounts in a footnote.						
Megawatt Hours Sold or Delivered for the Prior Year						
Line No.	Title of Account (a)	Supply-- Fixed Price Service (b)	Supply-- Hourly Priced Service (c)	No Entry Required (d)	Delivery Charges-- Delivery of RES Power (e)	Total (f)
1	ELECTRIC SERVICE REVENUES					
2	(440) Residential Sales	20,210,650	400,908		5,411,007	26,022,565
3	(442) Commercial and Industrial Sales					
4	Small or Commercial	4,662,441	3,197,650		20,625,602	28,705,693
5	Large or Industrial	2,116	1,347,711		25,358,007	26,707,834
6	(444) Public Street and Highway Lighting	44,481	76,215		331,612	454,308
7	(445) Other Sales to Public Authorities	---	---		---	---
8	(446) Sales to Railroads and Railways	---	---		399,921	399,921
9	SALES TO ULTIMATE CUSTOMERS (Sum of Lines 2 through 8)	24,939,688	5,024,484		52,326,049	82,290,221
10	(447) Sales for Resale	---	---		---	888,910
11	(448) Interdepartmental Sales	---	---		---	---
12	TOTAL SALES OF ELECTRICITY (Sum of Lines 9 through 11)	24,939,688	5,024,484		52,326,049	83,279,131
Average Number of Customers per Month for the Prior Year						
Line No.	Title of Account (a)	Supply-- Fixed Price Service (b)	Supply-- Hourly Priced Service (c)	No Entry Required (d)	Delivery Charges-- Delivery of RES Power (e)	Total (f)
13	ELECTRIC SERVICE REVENUES					
14	(440) Residential Sales	2,964,203	42,353		725,903	3,732,459
15	(442) Commercial and Industrial Sales					
16	Small or Commercial	223,921	8,475		159,010	391,406
17	Large or Industrial	3	149		1,723	1,875
18	(444) Public Street and Highway Lighting	2,572	834		1,390	4,796
19	(445) Other Sales to Public Authorities	---	---		---	---
20	(446) Sales to Railroads and Railways	---	---		2	2
21	SALES TO ULTIMATE CUSTOMERS (Sum of Lines 2 through 8)	3,190,699	51,811		888,028	4,130,538
22	(447) Sales for Resale	---	---		---	---
23	(448) Interdepartmental Sales	---	---		---	---
24	TOTAL SALES OF ELECTRICITY (Sum of Lines 9 through 11)	3,190,699	51,811		888,028	4,130,538

Form 21 ILCC

page 3a

2024DAI 0000131

[illegible]

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original		Date of Report December 31, 2024	Year of Report December 31, 2024
IDENTIFICATION OF DIFFERENCES BETWEEN INFORMATION REPORTED ON FERC SCHEDULES AND INFORMATION REPORTED ON PAGES 2 THROUGH 7 OF FORM 21 ILCC					
Item Number	Description	Amount	Affected Accounts Form 21 ILCC	FERC Form No. 1	Authorization for Accounting Treatment - See Footnote
1	Arbitration settlement costs - City of Chicago	---	DR 426.5	CR 930.2	A
1	City of Chicago and Midwest Generation settlement	---	DR 426.5	CR 930.2	B
	Total Item 1	---			
2	Gains on dispositions of property	---	CR 421.1	DR 411.6	C
	Total Item 2	---			
3	Federal income taxes applicable to Arbitration settlements costs - City of Chicago	---	CR 409.2	DR 409.1	A
3	Federal income taxes applicable to City of Chicago and Midwest Generation settlement	---	CR 409.2	DR 409.1	B
3	Federal income taxes applicable to Gains on dispositions of property	---	CR 409.2	CR 409.1	C
	Total Item 3	---			
4	State income taxes applicable to Arbitration settlement costs - City of Chicago	---	CR 409.2	DR 409.1	A
4	State income taxes applicable to City of Chicago and Midwest Generation settlement	---	CR 409.2	DR 409.1	B
4	State income taxes applicable to Gains on dispositions of property	---	DR 409.2	CR 409.1	C
	Total Item 4	---			
A) Represents costs incurred in connection with a settlement agreement between ComEd and City of Chicago. ComEd has made a determination that it will not seek recovery of these operating expenses from Illinois retail customers, and as such, has recorded these expenses and applicable income taxes "below the line" in Account 426.5, Other Deductions and Account 409.2, Income Taxes Federal & Other, for ICC reporting purposes. This settlement was fully amortized as of December 31, 2020, and as such, there was no activity in 2024 for the settlement agreement between ComEd and City of Chicago.					
B) Represents costs incurred in connection with a settlement agreement between ComEd and the City of Chicago and Midwest Generation. ComEd has made a determination that it will not seek recovery of these operating expenses from Illinois retail customers, and as such, has recorded these expenses and applicable income taxes "below the line" in Account 426.5, Other Deductions and Account 409.2, Income Taxes Federal & Other, for ICC reporting purposes. This settlement was fully amortized as of December 31, 2020, and as such, there was no activity in 2024 for the settlement agreement between ComEd and the City of Chicago and Midwest Generation.					
C) The ICC accounting treatment for these items is in accordance with 83 ILCS Admin. Code 415, Uniform System of Accounts for Electric Utilities, effective December 15, 1994.					

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 264 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original		Year of Report December 31, 2024
ANALYSIS OF UNBILLED REVENUE				
Line No.		Prior Year	Current Year	ILCC Form 21 Reference
1	Electric Utility Revenue	7,468,000,341	8,615,522,460	
2	Less: Prior Year Unbilled Revenue	(234,676,034)	144,774,410	Pg. 13(a), Ln 3 prior year
3	Add: Current Year Unbilled Revenue	144,774,410	(306,763,100)	
4	Gross Electric Utility Operating Revenue	7,847,450,785	8,163,984,950	Pg. 7a, col. (f), Ln 2
5	Gas Utility Revenue			
6	Less: Prior Year Unbilled Revenue			Pg. 13(a), Ln 7 prior year
7	Add: Current Year Unbilled Revenue			
8	Gross Gas Utility Operating Revenue	—	—	Pg. 7a, col. (g), Ln 2
9	Total Utility Revenue (Ln 1 + Ln 5)	7,468,000,341	8,615,522,460	
10	Less: Total Prior Year Unbilled Revenue (Ln 2 + Ln 6)	(234,676,034)	144,774,410	Pg. 13 (a), Ln 11 prior year
11	Add: Total Current Year Unbilled Revenue (Ln 3 + Ln 7)	144,774,410	(306,763,100)	
12	Total Gross Utility Operating Revenue	7,847,450,785	8,163,984,950	Pg. 14, Ln 1

Name of Respondent Commonwealth Edison Company	This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.): December 31, 2024	Year of Report December 31, 2024
---	------------------------------------	--	-------------------------------------

SPECIAL FUNDS (Accounts 125, 126, 127, 128)

Instructions:
Report below the balance at the end of year of each special fund maintained during the year. Identify each fund as to which account it is included.
Indicate the nature of any funds included in Account 128 Other Special Funds.
If the trustee of any fund is an associated company, give name of such associated company.
If assets other than cash comprise any fund, furnish a list of the securities or other assets, giving interest or dividend rate of each, cost to respondent, number of shares or principal amount, and book cost at end of year.

Line No.	Name of Fund and Trustee, if any (a)	Balance End of Year (b)
1	None	
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19	TOTAL	-

SPECIAL DEPOSITS (Accounts 132, 133, 134)

Instructions:
Report below the amounts of special deposits by classes at end of year.
If any deposit consists of assets other than cash, give a brief description of such assets.
If any deposit is held by an associated company, give name of company.

Line No.	Description and Purpose of Deposit (a)	Balance End of Year (b)
1	Mortgage release reserve associated with property sales	31,230
2	Collateral held from energy and renewable energy certificate suppliers	175,540,619
3	Escrow for environmental work at Rockford Library	1,515,309
4	Alternative compliance payments from RES pursuant to FEJA	308,790,661
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19	TOTAL	485,877,839

**Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 266 of 580**

[illegible]

[illegible]

[illegible]

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 269 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.): December 31, 2024	Year of Report December 31, 2024
MATERIALS AND SUPPLIES				
Instructions: 1. For Account 154, report the amounts of plant materials and operating supplies under the primary functional classifications as indicated in column (a); estimates of amounts by function are acceptable. In column (d), designate the department or departments that use the class of material. 2. Explain important inventory adjustments during the year (on a supplemental page) showing general classes of materials and supplies and the various accounts (operating expenses, clearing accounts, plant, etc.) affected - debited or credited.				
Line No.	Account (a)	Balance Beginning of Year (b)	Balance End of Year (c)	Department Which Used Material (d)
1	Fuel Stock (Account 151)			
2	Fuel Stock Expenses Undistributed (Account 152)			
3	Residuals and Extracted Products (Account 153)			
4	Plant Materials and Operating Supplies (Account 154)			
5	Assigned to - Construction (Estimated)	268,199,577	181,978,717	
6	Assigned to - Operations and Maintenance			
7	Production Plant (Estimated)			
8	Transmission Plant (Estimated)	4,642,775	7,595,643	Transmission
9	Distribution Plant (Estimated)	12,718,935	108,115,374	Distribution
10	Regional Transmission and Market Operation Plant (Estimated)			
11	Assigned to - Other (provide details in footnote)			
12	TOTAL Account 154 (Enter Total of lines 5 thru 11)	285,561,287	297,689,734	
13	Merchandise (Account 155)			
14	Other Materials and Supplies (Account 156)			
15	Nuclear Materials Held for Sale (Account 157) (Not applic to Gas Util)			
16	Stores Expense Undistributed (Account 163)			
17				
18				
19				
20	TOTAL Materials and Supplies (Per Balance Sheet)	285,561,287	297,689,734	
FOOTNOTE DATA				
Assigned to - Construction (Estimated)				
Transmission Plant (Estimated)		\$	47,487,920	
Distribution Plant (Estimated)			134,490,797	
Assigned to - Construction (Estimated)		\$	181,978,717	

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 270 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original		Date of Report (Mo./Da./Yr.): December 31, 2024	
NOTES PAYABLE (Account 231)					
Instructions:					
1. Report the particulars indicated concerning notes payable at end of year.					
2. Give the particulars of collateral pledged, if any.					
3. Any demand notes should be designated as such in column (c).					
Line No.	Payee (a)	Purpose for Which Issued (b)	Date of Note (c)	Interest Rate % (d)	Balance End of Year (e)
1	Commercial Paper issued by:				
2	Citi Bank	General Purpose/Working Capital	12/20/2023	4.55 %	36,000,000
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14	Discount on Commercial Paper				(4,550)
15					
16	Notes Payable issued by:				
17					
18					
19	TOTAL				35,995,450
PAYABLES TO ASSOCIATED COMPANIES (Accounts 233, 234)					
Instructions:					
1. Report the particulars of notes and accounts to associated companies at end of year.					
2. Provide separate totals for Accounts 233, Notes Payable to Associated Companies, and 234, Accounts Payable to Associated Companies, in addition to the total for the combined accounts.					
3. List each note separately and state the purpose for which issued. Show also in column (a) date of note and maturity.					
4. Include in column (e) the amount of any interest expense during the year on notes or accounts that were paid before the end of year.					
Line No.	Name of Company (a)	Commission Authorization (b)	Balance End of Year (c)	Interest for Year	
				Rate % (d)	Amount (e)
1	Account 233:				
2	None			---	
3					
4					
5					
6	Account 234:				
7	ComEd Financing III		3,855,106		
8	Edison, LLC		(86,159)		
9	Exelon Business Services Company, LLC		67,386,193		
10	Exelon Corporation		4,731,704		
11	PECO Energy Company		0		
12	PHI Service Company		13,979		
13	Baltimore Gas & Electric		78,485		
14	Commonwealth Edison of Indiana		708,280		
15	Potomac Electric Power Company		355,465		
16					
17	Total Account 234		77,043,053		
18					
19	TOTAL		77,043,053		

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 271 of 580

Name of Respondent		This Report Is:		Date of Report (Mo./Da./Yr.)	Year of Report
Commonwealth Edison Company		(1) An Original			December 31, 2024
LONG TERM DEBT (Accounts 221, 222, 223 and 224)					
Instructions:					
1. Report by balance sheet Account the particulars (details) concerning long-term debt included in Accounts 221- Bonds, 222- Reacquired Bonds, 223- Advances from Associated Companies, and 224- Other Long-Term Debt. If information to meet the stock exchange reporting requirement outlined in column (a) is available from the SEC 10-K Report Form filing, a specific reference to the report form (i.e. year and company title) may be reported in column (a) provided the fiscal years for both the 10-K report and this report are compatible.					
2. For bonds assumed by the respondent, include in column (a) the name of the issuing company as well as a description of the bonds.					
3. For advances from Associated Companies, report separately advances on notes and advances on open accounts.					
Designate demand notes as such. Include in column (a) the name of associated companies from which advances were received.					
For receivers' certificates, show in column (a) the name of the court and date of court order under which such certificates were issued.					
5. In a supplemental statement, give explanatory particulars (details) for Accounts 223 and 224 of net changes during the year.					
With respect to long-term advances, show for each company: (a) principal advanced during year, (b) interest added to principal amounts, and					
(c) principal repaid during year. Give commission authorization numbers and dates.					
Line No.	Class and Series of Obligation, Coupon Rate (a)	Principal Amount of Debt Issued (b)	Nominal Date of Issue (c)	Date of Maturity (d)	Outstanding (Total amount outstanding without reduction for amounts held by respondent) (e)
1	Account 221 (1)				
2	First Mortgage Bonds -				
3	100, 5.875%	350,000,000	1/22/2003	2/1/2033	253,600,000
4	103, 5.900%	325,000,000	3/6/2006	3/15/2036	325,000,000
5	103B, 5.900%	300,000,000	3/22/2007	3/15/2036	300,000,000
6	107, 6.450%	450,000,000	1/16/2008	1/15/2038	450,000,000
7	113, 3.800%	350,000,000	10/1/2012	10/1/2042	350,000,000
8	114, 4.600%	350,000,000	8/19/2013	8/15/2043	350,000,000
9	116, 4.700%	350,000,000	1/10/2014	1/15/2044	350,000,000
10	117, 3.100%	250,000,000	11/10/2014	11/1/2024	—
11	118, 3.700%	400,000,000	3/2/2015	3/1/2045	400,000,000
12	119, 4.350%	450,000,000	11/19/2015	11/15/2045	450,000,000
13	120, 2.550%	500,000,000	6/27/2016	6/15/2026	500,000,000
14	121, 3.650%	700,000,000	6/27/2016	6/15/2046	700,000,000
15	122, 2.950%	350,000,000	8/23/2017	8/15/2027	350,000,000
16	123, 3.750%	650,000,000	8/23/2017	8/15/2047	650,000,000
17	124, 4.000%	800,000,000	2/20/2018	3/1/2048	800,000,000
18	125, 3.700%	550,000,000	8/14/2018	8/15/2028	550,000,000
19	126, 4.000%	400,000,000	2/19/2019	3/1/2049	400,000,000
20	127, 3.200%	300,000,000	11/12/2019	11/15/2049	300,000,000
21	128, 2.200%	350,000,000	2/18/2020	3/1/2030	350,000,000
22	129, 3.000%	650,000,000	2/18/2020	3/1/2050	650,000,000
23	130, 3.125%	700,000,000	3/9/2021	3/15/2051	700,000,000
24	131, 2.750%	450,000,000	8/12/2021	9/1/2051	450,000,000
25	132, 3.150%	300,000,000	3/15/2022	3/15/2032	300,000,000
26	133, 3.850%	450,000,000	3/15/2022	3/15/2052	450,000,000
27	134, 4.900%	400,000,000	1/10/2023	2/1/2033	400,000,000
28	135, 5.300%	575,000,000	1/10/2023	2/1/2053	575,000,000
29	136, 5.300%	400,000,000	5/13/2024	6/1/2034	400,000,000
30	137, 5.650%	400,000,000	5/13/2024	6/1/2054	400,000,000
31	Total First Mortgage Bonds and Account 221				12,153,600,000
32					
33	Account 222 -- None				—
34					
35	Account 223				
36	6.350% Subordinated Deferrable Interest Debentures				
37	ComEd Financing III	206,186,000	3/17/2003	3/15/2033	206,186,000
38	Total Account 223				206,186,000
39					
40	Account 224 --None				—
41					
42	Totals	12,706,186,000			12,359,786,000

2024DCAI 0000141

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 273 of 580

Name of Respondent Commonwealth Edison Company	This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.) December 31, 2024	Year of Report December 31, 2024
LONG TERM DEBT (Accounts 221, 222, 223 and 224)			
Instructions: 6. If the respondent has pledged any of its long-term debt securities, give particulars (details) in a footnote, including name of the pledgee and purpose of the pledge. 7. If the respondent has any long-term securities which have been nominally issued and are nominally outstanding at end of year, describe such securities in a footnote. 8. If interest expense was incurred during the year on any obligation retired or reacquired before end of year, include interest expense in column (g). Explain in a footnote any difference between the total of column (g) and the total Account 427, Interest on Long-Term Debt and Account 430, Interest on Debt to Associated Companies. Give particulars (details) concerning any long-term debt authorized by a regulatory commission but not yet issued. In column (b) show the principal amount of bonds or other long-term debt originally issued. 11. In column (i) provide redemption price in % or per \$100 of face amount outstanding. If the respondent has provided information required in column (i) in a document filed pursuant to Article 6 of the Illinois Public Utilities Act, respondent may reference that document in a footnote in lieu of providing the information here.			
INTEREST FOR YEAR		HELD BY RESPONDENT	
Amount (10) (f)	Reacquired Bonds (Acct. 222) (g)	Sinking and Other Funds (h)	Redemption Price at End of Year (i)
			Line No.
			1
			2
	14,899,000	---	(5) 3
	19,175,000	---	(5) 4
	17,700,000	---	(5) 5
	29,025,000	---	(6) 6
	13,300,000	---	(3) 7
	16,100,000	---	(3) 8
	16,450,000	---	(3) 9
	4,520,833	---	(2) 10
	14,800,000	---	(4) 11
	19,575,000	---	(4) 12
	12,750,000	---	(3) 13
	25,550,000	---	(4) 14
	10,325,000	---	(2) 15
	24,375,000	---	(3) 16
	32,000,000	---	(3) 17
	20,350,000	---	(2) 18
	16,000,000	---	(4) 19
	9,600,000	---	(3) 20
	7,700,000	---	(2) 21
	19,500,000	---	(3) 22
	21,875,000	---	(3) 23
	12,375,000	---	(3) 24
	9,450,000	---	(4) 25
	17,325,000	---	(5) 26
	19,600,000	---	(4) 27
	30,475,000	---	(5) 28
	13,426,667	---	(3) 29
	14,313,333	---	(4) 30
	482,534,833		
			31
			32
			33
			34
	13,092,811		100% 35
	13,092,811		
			37
			38
			39
	495,627,644		
			40

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 275 of 580

Name of Respondent	This Report Is:	Date of Report (Mo./Da./Yr.)	Year of Report
Commonwealth Edison Company	(1) An Original		December 31, 2024

LONG TERM DEBT (Accounts 221, 222, 223 and 224)									
(1)	Changes in Account 221 during the year:	Issuances	Retirements						
	First Mortgage Bonds	\$800,000,000	\$250,000,000						
The unamortized debt discount, premium or expense on reacquired debt are transferred to Account 189, Unamortized Loss on Reacquired Debt, or Account 257, Unamortized Gain on Reacquired Debt, as appropriate, and amortized to expense over the life of the new long-term debt issued to finance the debt redemption, and/or over the life of the original debt issuance if the debt is not refinanced. These bonds may be redeemed in whole or in part at any time at a redemption price equal to the greater of 100%, or the sum of the present values of the remaining scheduled payments of principal and interest on the bonds to be redeemed discounted to the redemption date on a semi-annual basis at the Adjusted Treasury Rate plus 12.5 basis points. (2) These bonds may be redeemed in whole or in part at any time at a redemption price equal to the greater of 100%, or the sum of the present values of the remaining scheduled payments of principal and interest on the bonds to be redeemed discounted to the redemption date on a semi-annual basis at the Adjusted Treasury Rate plus 15 basis points. (3) These bonds may be redeemed in whole or in part at any time at a redemption price equal to the greater of 100%, or the sum of the present values of the remaining scheduled payments of principal and interest on the bonds to be redeemed discounted to the redemption date on a semi-annual basis at the Adjusted Treasury Rate plus 20 basis points. (4) These bonds may be redeemed in whole or in part at any time at a redemption price equal to the greater of 100%, or the sum of the present values of the remaining scheduled payments of principal and interest on the bonds to be redeemed discounted to the redemption date on a semi-annual basis at the Adjusted Treasury Rate plus 25 basis points. (5) These bonds may be redeemed in whole or in part at any time at a redemption price equal to the greater of 100%, or the sum of the present values of the remaining scheduled payments of principal and interest on the bonds to be redeemed discounted to the redemption date on a semi-annual basis at the Adjusted Treasury Rate plus 35 basis points. (6) These bonds may be redeemed in whole or in part at any time at a redemption price equal to the greater of 100%, or the sum of the present values of the remaining scheduled payments of principal and interest on the bonds to be redeemed discounted to the redemption date on a semi-annual basis at the Adjusted Treasury Rate plus 40 basis points. (7) (10) This footnote pertains to column (f) <table style="width: 100%; margin-top: 10px;"> <tr> <td style="width: 50%;">Total interest reported on pages 22-23</td> <td style="width: 50%; text-align: right;">\$ 495,627,644</td> </tr> <tr> <td>Amortization of settled cash flow swaps</td> <td style="text-align: right;">519,508</td> </tr> <tr> <td>Total of Accounts 427 and 430</td> <td style="text-align: right; border-top: 1px solid black; border-bottom: 3px double black;">\$ 496,147,152</td> </tr> </table>				Total interest reported on pages 22-23	\$ 495,627,644	Amortization of settled cash flow swaps	519,508	Total of Accounts 427 and 430	\$ 496,147,152
Total interest reported on pages 22-23	\$ 495,627,644								
Amortization of settled cash flow swaps	519,508								
Total of Accounts 427 and 430	\$ 496,147,152								

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original		Date of Report (Mo./Da./Yr.) December 31, 2024		Year of Report December 31, 2024				
UNAMORTIZED LOSS AND GAIN ON REACQUIRED DEBT (Accounts 189, 257)										
1.	Report under separate subheadings for Unamortized Loss and Unamortized Gain on Reacquired Debt, particulars (details) of gains and losses, including maturity date, on reacquisition applicable to each class and series of long-term debt. If gains or losses resulted from a refunding transaction, include also the maturity date of the new issue.									
2.	In column (e) show the principal amounts of bonds or other long-term debt reacquired.									
3.	In column (f) show the net gain or net loss realized on each debt reacquisition as computed in accordance with General Instruction 17 of the Uniform System of Accounts.									
4.	Show loss amounts by enclosing the figures in parentheses.									
5.	Explain in a footnote any debits and credits other than amortization debited to Account 428.1, Amortization of Loss on Reacquired Debt, or credited to Account 429.1, Amortization of Gain on Reacquired Debt-Credit.									
		Amortization Period								
Line No.	Designation of Long-Term Debt	Date Reacquired (b)	Date From (c)	Date To (d)	Principal of Debt Reacquired (e)	Net Gain or Net Loss (f)	Balance at Beginning of Year (g)	Debits During Year (h)	Credits During Year (i)	Balance at End of Year (j)
1	Unamortized Loss on Reacquired Debt (1)(2)(3)									
2										
3	8.375% 86 09/15/22	09/16/02	01/22/03	02/01/33			1,070,364	—	117,744	952,620
4	5.875% 100 02/01/33	07/27/04	01/01/07	02/01/33	11,400,000	(788,382)	251,586	—	27,627	223,959
5	5.875% 100 02/01/33	08/06/04	01/01/07	02/01/33	40,000,000	(4,283,438)	1,368,254	—	150,246	1,218,008
6	5.875% 100 02/01/33	08/25/04	01/01/07	02/01/33	45,000,000	(6,455,972)	2,066,016	—	226,863	1,839,153
7										
8										
9										
10										
11										
12										
13										
14										
15										

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original			Date of Report (Mo./Da./Yr.)		Year of Report December 31, 2024			
UNAMORTIZED LOSS AND GAIN ON REACQUIRED DEBT (Accounts 189, 257)										
1. Report under separate subheadings for Unamortized Loss and Unamortized Gain on Reacquired Debt, particulars (details) of gains and losses, including maturity date, on reacquisition applicable to each class and series of long-term debt. If gains or losses resulted from a refunding transaction, include also the maturity date of the new issue.										
2. In column (e) show the principal amounts of bonds or other long-term debt reacquired.										
3. In column (f) show the net gain or net loss realized on each debt reacquisition as computed in accordance with General Instruction 17 of the Uniform System of Accounts.										
4. Show loss amounts by enclosing the figures in parentheses.										
5. Explain in a footnote any debits and credits other than amortization debited to Account 428.1, Amortization of Loss on Reacquired Debt, or credited to Account 429.1, Amortization of Gain on Reacquired Debt-Credits.										
Line No.	Designation of Long-Term Debt (a)	Date Reacquired (b)	Amortization Period		Principal of Debt Reacquired (e)	Net Gain or Net Loss (f)	Balance at Beginning of Year (g)	Debits During Year (h)	Credits During Year (i)	Balance at End of Year (j)
			Date From (c)	Date To (d)						
1	Subordinated Deferrable Interest Notes -									
2	8.480% 09/30/33	03/20/03	03/20/03	03/15/33	206,190,000	(20,228,911)	6,209,115	—	674,297	5,534,818
3										
4	8.500% Subord. Deferrable Interest Debentures, ComEd	03/07/08	03/07/08	01/15/38	154,640,000	(11,579,481)	5,458,667	—	387,598	5,071,069
5										
6										
7										
8										
9										
10										
11										
12										
13										
14										
15										
16										
17										
18										
19										
20										
21										
22										
23										
24										
25										
26										
27										
28	Total Account 189						16,424,002	—	1,584,375	14,839,627
29										
30										
31										

Name of Respondent	This Report Is:	Date of Report (Mo./	Year of Report
Commonwealth Edison Company	(1) An Original	Da./Yr.)	December 31, 2024
UNAMORTIZED LOSS AND GAIN ON REACQUIRED DEBT (Accounts 188, 287)			
Note:			
(1) Refunded with the proceeds from issuance of long-term debt with the following maturity dates:			
	Rate	Series	Maturity Date(s) of New Debt Issues
First Mortgage Bonds	8.375 %	86	Feb-2033 (A)

Name of Respondent Commonwealth Edison Company		This Report is: (1) An Original	Date of Report (Mo./Da./Yr.)	Year of Report December 31, 2024
UNAMORTIZED LOSS AND GAIN ON REACQUIRED DEBT (Accounts 189, 257)				
Note:				
	Rate	Series	Maturity Date(s) of New Debt Issuances	
Subordinated Deferrable Interest Debentures -	8.500 %	ComEd Financing II	Jan-2038	
Subordinated Deferrable Interest Note -	8.480 %	ComEd Financing I	Mar-2033	
(A) The amortization period has been changed due to the refunding of the long-term debt originally issued to refund this issue. Maturity date is that of the new long-term-debt issue.				
(2) The following debt items were not refinanced:				
	Rate	Series	Maturity Date(s) of New Debt Issuances	
First Mortgage Bonds -	5.875 %	100	Feb-2033	
Notes - None				
(3) The ICC's Order in Docket No. 05-0597 allows for the recovery of \$87 million of losses related to the extinguishment of long-term debt recorded in 2004. As a result, such losses were recorded in Account 189 in 2006.				

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.) December 31, 2024	Year of Report December 31, 2024
DISCOUNT ON COMMON STOCK AND PREFERRED STOCK ISSUANCES (Accounts 201 through 204 and 207)				
1. Identify the amounts of discount or expense, including underwriting discounts, recorded in account 214, Capital Stock Expense, that has accumulated since December 31, 1993. Amounts recorded before December 31, 1993 may also be included.				
Line No.	Account Title (a)	Amount of Discount (b)	Amount Recovered through Rates (c)	
1	Account 201, Common Stock Issued	6,942,925	—	
2	Account 202, Common Stock Subscribed	—	—	
3	Account 203, Common Stock Liability for Conversion	—	—	
4	Account 204, Preferred Stock Issued	—	—	
5	Account 207, Premium on Capital Stock	—	—	
6	Total	6,942,925	—	
Page 25, Line 1, Column (a) : Includes capital stock expense that was recorded before December 31, 1993				

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 281 of 580

Name of Respondent		This Report Is:	Date of Report (Mo./ Da./Yr.)	Year of Report			
Commonwealth Edison Company		(1) An Original		December 31, 2024			
UNAMORTIZED DEBT EXPENSE, PREMIUM & DISCOUNT ON LONG-TERM DEBT							
(Accounts 181, 225, 226)							
Instructions:							
1. Report under separate subheadings for Unamortized Debt Expense, Unamortized Premium on Long-Term Debt and Unamortized Discount on Long-Term Debt, particulars (details) of expenses, premiums or discounts applicable to each class and series of long-term debt.							
2. Show premium amounts by enclosing the figures in parentheses.							
3. In column (b) show the principal amounts of bonds or other long-term debt originally issued.							
4. In column (c) show the expenses, premiums or discounts with respect to the amounts of bonds or other long-term debt originally issued.							
Line No.	Designation of Long-Term Debt (a)	Principal Amount of Debt Issued (b)	Total Expenses, Premium or Discount (c)	AMORTIZATION PERIOD			
				Date From (d)	Date To (e)		
1	First Mortgage Bonds - (1)						
2	100, 5.875%	350,000,000	3,525,036	1/22/2003	2/1/2033		
3			1,526,000				
4	103, 5.900%	325,000,000	3,488,737	3/6/2006	3/15/2036		
5			2,044,250				
6	103B, 5.900%	300,000,000	1,048,534	3/22/2007	3/15/2036		
7			12,435,000				
8	107, 6.450%	450,000,000	4,468,683	1/16/2008	1/15/2038		
9			1,359,000				
10	113, 3.800%	350,000,000	3,497,084	10/1/2012	10/1/2042		
11			623,000				
12	114, 4.600%	350,000,000	4,224,661	8/19/2013	8/15/2043		
13			791,000				
14	116, 4.700%	350,000,000	3,670,733	1/10/2014	1/15/2044		
15			115,500				
16	117, 3.100%	250,000,000	2,675,378	11/10/2014	11/1/2024		
17			212,500				
18	118, 3.700%	400,000,000	4,487,725	3/2/2015	3/1/2045		
19	119, 4.350%	450,000,000	5,643,725	11/19/2015	11/15/2045		
20			3,501,000				
21	120, 2.550%	500,000,000	4,325,512	6/27/2016	6/15/2026		
22	121, 3.650%	700,000,000	7,630,653	6/27/2016	6/15/2046		
23			4,543,000				
24	122, 2.950%	350,000,000	3,084,480	8/23/2017	8/15/2027		
25			959,000				
26	123, 3.750%	650,000,000	7,187,392	8/23/2017	8/15/2047		
27			1,625,000				
28	124, 4.000%	800,000,000	8,806,005	2/20/2018	3/1/2048		
29			152,000				
30	125, 3.700%	550,000,000	5,724,371	8/14/2018	8/15/2028		
31			1,320,000				
32	126, 4.000%	400,000,000	5,320,038	2/19/2019	3/1/2049		
33			3,256,000				
34	127, 3.200%	300,000,000	3,958,928	11/12/2019	11/15/2049		
35			2,349,000				
36	128, 2.200%	350,000,000	3,831,804	2/18/2020	3/1/2030		
37			1,054,000				
38	129, 3.000%	650,000,000	8,523,636	2/18/2020	3/1/2050		
39			897,000				
40	130, 3.125%	700,000,000	9,221,373	3/9/2021	3/15/2051		
41			952,000				
42	131, 2.750%	450,000,000	4,695,716	6/12/2021	9/1/2051		
43			94,500				
44	132, 3.150%	300,000,000	3,265,761	3/15/2022	3/15/2032		
45			384,000				
46	133, 3.850%	450,000,000	5,905,442	3/15/2022	3/15/2052		
47			796,500				
48	134, 4.900%	400,000,000	4,419,289	1/10/2023	2/1/2033		
49			1,336,000				
50	135, 5.300%	575,000,000	7,643,212	1/10/2023	2/1/2053		
51			1,397,250				
52	136, 5.300%	400,000,000	4,042,973	5/13/2024	6/1/2034		
53			1,432,000				
54	137, 5.650%	400,000,000	4,942,973	5/13/2024	6/1/2054		
55			2,592,000				
56							
57	SUBTOTAL	12,500,000,000	187,026,158				
58							
59	Subordinated Deferrable Interest Debentures, 6.350%	206,186,000	2,256,515	3/17/2003	3/15/2033		

2024DCAI 0000151

60			186,000		
61					
62	TOTAL	12,706,186,000	189,468,673		
63					
64					
65					
66	Adjustments				
67					
68	TOTAL				

Form 21 ILCC

page 26

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 283 of 580

Name of Respondent		This Report Is:		Date of Report (Mo/Da/Yr):	Year of Report
Commonwealth Edison Company		(1) An Original			December 31, 2024
UNAMORTIZED DEBT EXPENSE, PREMIUM & DISCOUNT ON LONG-TERM DEBT					
(Accounts 181, 225, 226) (continued)					
Instructions:					
5. Furnish in a footnote particulars (details) regarding the treatment of Unamortized debt expenses, premiums or discounts associated with issues redeemed during the year. Also, give in a footnote the date of the Commission's authorization of treatment other than as specified by the Uniform System of Accounts.					
6. Identify separately undisposed amounts applicable to issues that were redeemed in prior years.					
7. Explain any debits and credits other than amortization debited to Account 428- Amortization of Debt Discount and Expenses, or credited to Account 429 - Amortization of Premium on Debt - Credit.					
	Balance at Beginning of Year (f)	Debits During Year (g)	Credits During Year (h)	Balance at End of Year (i)	No. 1
E	784,828	—	86,403	698,425	2
D	331,883	—	36,537	295,346	3
E	1,422,195	—	116,520	1,305,675	4
D	851,014	—	68,085	782,929	5
E	441,836	—	36,199	405,637	6
D	5,237,170	—	429,081	4,808,089	7
E	2,092,988	—	149,085	1,943,903	8
D	636,021	—	45,304	590,717	9
E	2,185,713	—	116,571	2,069,142	10
D	389,375	—	20,767	368,608	11
E	2,765,963	—	140,961	2,625,002	12
D	517,565	—	26,376	491,189	13
E	2,453,722	—	122,448	2,331,274	14
D	77,115	—	3,848	73,267	15
E	224,203	—	224,203	—	16
D	17,752	—	17,753	(1)	17
E	3,170,888	—	149,806	3,021,082	18
E	4,152,561	—	189,855	3,962,706	19
D	2,533,434	—	116,743	2,416,691	20
E	1,174,459	—	469,197	705,262	21
D	6,417,348	—	186,469	6,230,879	22
D	3,828,490	—	111,245	3,717,245	23
E	1,229,714	—	326,046	903,668	24
D	382,345	—	101,375	280,970	25
E	6,258,458	—	166,954	6,091,504	26
D	1,415,803	—	37,769	1,378,034	27
E	7,793,192	—	194,602	7,598,590	28
D	134,517	—	3,359	131,158	29
E	2,901,915	—	685,266	2,216,647	30
D	672,090	—	135,549	536,541	31
E	4,850,064	—	112,652	4,737,412	32
D	2,968,364	—	68,946	2,899,418	33
E	3,591,920	—	89,580	3,502,340	34
D	2,144,043	—	53,471	2,090,572	35
E	2,436,288	—	371,604	2,064,684	36
D	662,054	—	104,033	558,021	37
E	7,743,594	—	196,370	7,547,224	38
D	820,452	—	20,806	799,646	39
E	8,872,539	—	203,902	8,668,637	40
D	895,277	—	21,049	874,228	41
E	4,442,927	—	108,121	4,334,806	42
D	89,413	—	2,176	87,237	43
E	2,752,767	—	297,390	2,455,377	44
D	322,965	—	34,890	288,065	45
E	5,707,410	—	113,322	5,594,088	46
D	768,855	—	15,266	753,589	47
E	4,061,050	—	110,588	3,950,462	48
D	1,227,674	—	20,216	1,207,458	49
E	7,503,568	—	361,925	7,141,643	50
D	1,371,718	—	109,412	1,262,306	51
E	—	4,042,972	206,571	3,836,401	52
D	—	1,432,000	73,956	1,358,044	53
E	—	4,942,973	53,273	4,889,700	54
D	—	2,582,000	28,181	2,563,819	55
	125,547,591	13,009,945	7,192,078	131,365,456	56
					57
E	691,902	—	75,161	616,741	59
D	57,072	—	6,200	50,872	60
					61

	748,975	—	81,361	667,613	62
		—			63
	126,296,566	13,009,945	7,273,439	132,033,069	64
					65
	-41,483	756	-41,483	756	66
					67
	126,255,083	13,010,701	7,231,956	132,033,825	68

Form 21 ILCC

page 27

Name of Respondent	This Report Is:	Date of Report (Mo./Da./Yr.)	Year of Report
Commonwealth Edison Company	(1) An Original		December 31, 2024
UNAMORTIZED DEBT EXPENSE, PREMIUM & DISCOUNT ON LONG-TERM DEBT			
(Accounts 181, 225, 226) (continued)			
NOTES:			
(1) \$250M First Mortgage Bond Series 117 was retired on August 1, 2024. See Page 28 for information regarding this transaction.			
(2) Summary of Totals:			
<u>Account</u>	<u>12/31/2023</u>	<u>12/31/2024</u>	
181	97,925,756	101,349,765	
225	—	—	
226	28,329,327	30,684,060	
	<u>\$ 126,255,083</u>	<u>\$ 132,033,825</u>	
(3)			
This footnote pertains to column (g) and (h) -			
Total debit/credit activity reported on pages 26-27		5,778,742	
Payments related to debt expense, premium, discount		(13,010,701)	
Debt expenses - not deferred to Account 181		(230,360)	
PJM Surety Bond Reclass charged to 428		(261,999)	
Total Activity in Account 428 and 429		<u>\$ (7,724,318)</u>	

Name of Respondent	This Report Is:	Date of Report (Mo./Da./Yr.)	Year of Report
Commonwealth Edison Company	(1) An Original		December 31, 2024
UNAMORTIZED DEBT EXPENSE, PREMIUM & DISCOUNT ON LONG-TERM DEBT			
(Accounts 181, 225, 226) Supplemental Page			
Supplemental Note to Pages 26-27 On October 20, 2000, Exelon became the parent corporation of PECO Energy Company and ComEd. The merger was accounted for using the purchase method of accounting. Purchase transactions resulting in one entity becoming substantially wholly owned by the acquiror establish a new basis of accounting in the acquired entity's records for the purchased assets and liabilities. In the merger ComEd was the acquired entity. Thus, the purchase price has been allocated to the underlying assets purchased and liabilities assumed, including long-term debt, based on their estimated fair values at the acquisition date. In ComEd's Initial Brief in ICC Docket No. 01-0423, in the event that the information is needed for use in future rate cases, ComEd agreed to track and record separately the unamortized balance and annual amortization of the original discount and premium on long-term debt, excluding the effects of purchase accounting. As a result, for purposes of reporting on these supplemental pages to ILCC Form 21 pages 26- 27, the amounts reflect each individual debt issue as if purchase accounting had not been recorded.			

Name of Respondent	This Report Is:	Date of Report (Mo./Da./Yr.)	Year of Report																																																																																
Commonwealth Edison Company	(1) An Original		December 31, 2024																																																																																
SECURITIES ISSUED OR ASSUMED AND SECURITIES REFUNDED OR RETIRED DURING THE YEAR																																																																																			
1. Furnish a supplemental statement giving a brief description of security financing and refinancing transactions during the year and the accounting for the securities, discounts, premiums, expenses, and related gains or losses. Identify as to Commission authorization numbers and dates. 2. Furnish particulars (details) showing fully the accounting for the total principal amount, par value, or stated value of each class and series of security issued, assumed, retired, or refunded and the accounting for premiums, discounts, expenses, and gains or losses relating to the securities. Set forth the facts of the accounting clearly with regard to redemption premiums, unamortized discounts, expenses, and gains or losses relating to the securities retired or refunded, including the accounting for such amounts carried in the respondent's accounts at the date of the refunding or refinancing transactions with respect to securities previously refunded or retired. 3. Include in the identification of each class and series of security, as appropriate, the interest or dividend rate, nominal date of issuance, maturity date, aggregate principal amount, par value or stated value, and number of shares. Give also the issuance or redemption price and name of the principal underwriting firm through which the security transactions were consummated. 4. Where the accounting for the amounts relating to securities refunded or retired is other than that specified in General Instruction 17 of the Uniform System of Accounts, give references to the Commission authorization for the different accounting and state the accounting method. 5. For securities assumed, give the name of the company for which the liability on the securities was assumed as well as particulars (details) of the transactions whereby the respondent undertook to pay obligations of another company. If any unamortized discount, premiums, expenses, and gains or losses were taken over onto the respondent's books, furnish details of these amounts with amounts relating to refunding securities clearly earmarked.																																																																																			
<table><tr><th rowspan="2">New Issues</th><th rowspan="2">Issue</th><th rowspan="2">Principal</th><th rowspan="2">Issue Date</th><th rowspan="2">Maturity Date</th><th rowspan="2">Account</th><th colspan="3">Unamortized Debt</th><th rowspan="2">ICC, Author & Date</th><th rowspan="2">Underwriting Firm</th></tr><tr><th>Discount Account 226</th><th>Premium Account 225</th><th>Expense Account 181</th></tr><tr><td>First Mortgage Bond, Series 136</td><td>5.300%</td><td>\$ 400,000,000</td><td>5/13/2024</td><td>6/1/2034</td><td>221</td><td>1,432,000</td><td>—</td><td>4,042,973</td><td>18-0777</td><td>Goldman Sachs & Co. LLC, U.S. Bancorp Investments, Inc., Wells Fargo Securities, LLC, J.P. Morgan Securities LLC, Mizuho Securities USA LLC, SMBC Niko Securities America, Inc., Harrington Securities, Inc., Santander US Capital Markets LLC, Sunbelt Western Bank & Co. LLC, Bancsoft Capital, LLC, Loop Capital Markets LLC, Pimco Securities LLC, Stein Brothers & Co.</td></tr><tr><td>First Mortgage Bond, Series 137</td><td>5.650%</td><td>\$ 400,000,000</td><td>5/13/2024</td><td>6/1/2034</td><td>221</td><td>2,392,000</td><td>—</td><td>4,942,972</td><td>18-0777</td><td>Goldman Sachs & Co. LLC, U.S. Bancorp Investments, Inc., Wells Fargo Securities, LLC, J.P. Morgan Securities LLC, Mizuho Securities USA LLC, SMBC Niko Securities America, Inc., Harrington Securities, Inc., Santander US Capital Markets LLC, Sunbelt Western Bank & Co. LLC, Bancsoft Capital, LLC, Loop Capital Markets LLC, Pimco Securities LLC, Stein Brothers & Co.</td></tr><tr><td>Retired at Maturity</td><td>Issue</td><td>Principal</td><td>Maturity Date</td><td>Account</td><td colspan="6"></td></tr><tr><td colspan="11">None</td></tr><tr><td colspan="11">Assumed or Refunded</td></tr><tr><td colspan="11">None</td></tr></table>				New Issues	Issue	Principal	Issue Date	Maturity Date	Account	Unamortized Debt			ICC, Author & Date	Underwriting Firm	Discount Account 226	Premium Account 225	Expense Account 181	First Mortgage Bond, Series 136	5.300%	\$ 400,000,000	5/13/2024	6/1/2034	221	1,432,000	—	4,042,973	18-0777	Goldman Sachs & Co. LLC, U.S. Bancorp Investments, Inc., Wells Fargo Securities, LLC, J.P. Morgan Securities LLC, Mizuho Securities USA LLC, SMBC Niko Securities America, Inc., Harrington Securities, Inc., Santander US Capital Markets LLC, Sunbelt Western Bank & Co. LLC, Bancsoft Capital, LLC, Loop Capital Markets LLC, Pimco Securities LLC, Stein Brothers & Co.	First Mortgage Bond, Series 137	5.650%	\$ 400,000,000	5/13/2024	6/1/2034	221	2,392,000	—	4,942,972	18-0777	Goldman Sachs & Co. LLC, U.S. Bancorp Investments, Inc., Wells Fargo Securities, LLC, J.P. Morgan Securities LLC, Mizuho Securities USA LLC, SMBC Niko Securities America, Inc., Harrington Securities, Inc., Santander US Capital Markets LLC, Sunbelt Western Bank & Co. LLC, Bancsoft Capital, LLC, Loop Capital Markets LLC, Pimco Securities LLC, Stein Brothers & Co.	Retired at Maturity	Issue	Principal	Maturity Date	Account							None											Assumed or Refunded											None										
New Issues	Issue	Principal	Issue Date							Maturity Date	Account	Unamortized Debt			ICC, Author & Date	Underwriting Firm																																																																			
				Discount Account 226	Premium Account 225	Expense Account 181																																																																													
First Mortgage Bond, Series 136	5.300%	\$ 400,000,000	5/13/2024	6/1/2034	221	1,432,000	—	4,042,973	18-0777	Goldman Sachs & Co. LLC, U.S. Bancorp Investments, Inc., Wells Fargo Securities, LLC, J.P. Morgan Securities LLC, Mizuho Securities USA LLC, SMBC Niko Securities America, Inc., Harrington Securities, Inc., Santander US Capital Markets LLC, Sunbelt Western Bank & Co. LLC, Bancsoft Capital, LLC, Loop Capital Markets LLC, Pimco Securities LLC, Stein Brothers & Co.																																																																									
First Mortgage Bond, Series 137	5.650%	\$ 400,000,000	5/13/2024	6/1/2034	221	2,392,000	—	4,942,972	18-0777	Goldman Sachs & Co. LLC, U.S. Bancorp Investments, Inc., Wells Fargo Securities, LLC, J.P. Morgan Securities LLC, Mizuho Securities USA LLC, SMBC Niko Securities America, Inc., Harrington Securities, Inc., Santander US Capital Markets LLC, Sunbelt Western Bank & Co. LLC, Bancsoft Capital, LLC, Loop Capital Markets LLC, Pimco Securities LLC, Stein Brothers & Co.																																																																									
Retired at Maturity	Issue	Principal	Maturity Date	Account																																																																															
None																																																																																			
Assumed or Refunded																																																																																			
None																																																																																			

Appendix C - Stakeholder Presentation
Rate Design Investigation
Page 288 of 580

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original		Date of Report (Mo./Da./Yr.) December 31, 2024	Year of Report December 31, 2024
INVESTMENTS (Accounts 123, 124, 136)					
Instructions: Report below investments in Accounts 123- Investments in Associated Companies, 124- Other Investments, and 136-Temporary Cash Investments. Provide a subheading for each account and list there under the information called for: (a) Investment in Securities - List and describe each security owned, giving name of issuer, date acquired and date of maturity. For bonds, also give principal amount, date of issue, maturity and interest rate. For capital stock (including capital stock of respondent) reacquired under a definite plan for resale pursuant to authorization by the Board of Directors, and included in Account 124- Other Investments, state number of shares, classes, and series of stock. Minor investments may be grouped by classes. Investments included in Account 136- Temporary Cash Investments, also may be grouped by classes. (b) Investment Advances - Report separately for each person or company the amounts of loans or investment advances which are properly includable in Account 123. Advances subject to current repayment should be included in Accounts 145 and 146. With respect to each advance, show whether the advance is a note or open account.					
Line No.	Description of Investment (a)	Book Cost at Beginning of Year (If book cost is different from cost to respondent, give cost to respondent in a footnote and explain difference) (b)	Purchases or Additions During Year (c)		
1	123 - Investments in Associated Companies				
2	None		—		—
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15	124 - Other Investments				
16	Cash Surrender Value, Corporate Owned				
17	Life Insurance	18,778		6,093	
18	Monetized Stock	18,556		—	
19					
20					
21					
22	Total	37,334		6,093	
23					
24					
25					
26	136 - Temporary Cash Investments				
27	Money Market Accounts	23,989,634		2,453,499,342	
28					
29					
30	Total	23,989,634		2,453,499,342	
31					
32					
33					
34					
35					
36					
37					
38					
39					

Name of Respondent Commonwealth Edison Company		This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.): December 31, 2024	Year of Report December 31, 2024	
INVESTMENTS (Accounts 123, 124, 136) (continued)					
Instructions: Each note should be listed giving date of issuance, maturity date, and specifying whether note is a renewal. Designate any advances due from officers, directors, stockholders, or employees. Exclude amounts reported on page 229, of FERC Form 1. For any securities, notes or accounts that were pledged, designate with an asterisk such securities, notes or accounts and in a footnote state the name of pledges and purpose of the pledge. If Commission approval was required for any advances made or securities acquired, designate such fact in a footnote and give name of Commission, date of authorization, and case or docket number. Report in column (g) interest and dividend revenues from investments including such revenues from securities disposed of during the year. In column (h) report for each investment disposed of during the year the gain or loss represented by the difference between cost of the investment (or the other amount at which carried in the books of account if different from					
Sales or Other Dispositions During Year (d)	Principal Amount of No. of Shares at End of Year (e)	Book Cost at End of Year (If book cost is different from cost to respondent, give cost to respondent in a footnote and explain difference). (f)	Revenues for year (g)	Gain or Loss from Investment Disposed of (h)	Line No.
123 - Investment in Associated Companies					1
		—			2
					3
					4
					5
					6
					7
					8
					9
					10
					11
					12
					13
					14
124 - Other Investments					15
					16
—		24,871	—	—	17
—		18,556	—	—	18
					19
					20
—		43,427	—	—	21
					22
					23
					24
					25
136 Temporary Cash Investments					26
2,438,065,363		39,423,613	—	—	27
					28
					29
2,438,065,363		39,423,613	—	—	30
					31
					32
					33
					34
					35
					36
					37
					38
					39

Name of Respondent Commonwealth Edison Company	This Report Is: (1) An Original	Date of Report (Mo./Da./Yr.) December 31, 2024	Year of Report December 31, 2024
PARTICULARS CONCERNING CERTAIN OTHER INCOME ACCOUNTS			
Instructions:			
1. Report in this schedule the revenues and expenses with respect to: Income from Nonutility Operations (Account 417), Expenses of Nonutility Operations (Account 417.1), Nonoperating Rental Income (Account 418), Equity Earnings in Subsidiary Companies (Account 418.1), Interest and Dividend Income (Account 419), Allowances for Other Funds Used During Construction (Account 419.1), Miscellaneous Nonoperating Income (Account 421), and Gains on Disposition of Property (Account 421.1).			
2. Give the basis of any important segregation of income and expense between Utility and Nonutility operations.			
3. Minor items may be grouped by classes, show number of items.			
Item (a)		Amount (b)	
Account 417 - Revenues from Nonutility Operations			
None			
Account 417.1 - Expenses of Nonutility Operations			
None			
Account 418 - Nonoperating Rental Income			
None			
Account 418.1 - Equity in Earnings of Subsidiary Companies			
Commonwealth Edison Company of Indiana, Inc.		8,756,536	
ComEd Financing III		392,811	
Total Account 418.1		9,149,347	
Account 419 - Interest and Dividend Income			
Interest on marketable securities		2,900	
Other interest		23,307,970	
Total Account 419		23,310,870	